
CONTRACT NO. 72A56

			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	· ·	140. 12	~50
F.A.I. RTE.	SECTION		COUNTY		TOTAL SHEETS	SHEE NO.
55	•	5	ANGA	NON	26	25
STA.	A. TO STA.					
FED. ROAD DIST. NO. IL		ILLINOIS	FED.	AID	PROJECT	

- D-6 CABLE MEDIAN BAR #2



CABLE POST -

CABLE GUARD MARKER

			QUANTITY
LOCATION	(EACH)		
LT STA 374+25.00	TO	STA 446+29.54 BK	180
LT STA 446+39.17 AH	TO	STA 456+25.00	25
LT STA 468+34.00	TO	STA 521+73.00	133
RT STA 522+61.00	TO	STA 582+64.00	150
RT STA 618+49.00	TO	STA 695+32.26 BK	192
RT STA 355+49.48 AH	TO	STA 347+81.00	19
TOTAL	699		

NOTES:

MATERIAL: THE MATERIAL SHALL BE IN ACCORDANCE WITH SECTION 1090 AND 1091 OF THE STANDARD SPECIFICATIONS.

CONSTRUCTION REQUIREMENTS: THE REFLECTIVE SHEETING SHALL BE INSTALLED DIRECTLY ON THE CABLE POSTS. THE REFLECTIVE SHEETING SHALL BE INSTALLED AS SHOWN IN THE PLANS, ON EVERY OTHER POST (IN ORDER TO PROVIDE A SPACING OF 40'). THE SURFACE OF THE POST SHALL BE CLEANED OF ALL CONTAMINANTS PRIOR TO THE INSTALLATION OF THE REFLECTIVE SHEETING. THE SURFACE SHALL BE CLEANED USING A 5-8 PERCENT PHOSPHORIC ACID SOLUTION AND RINSED WITH CLEAN WATER OR AS RECOMMENDED BY THE MANUFACTURER OF THE REFLECTIVE SHEETING AND AS APPROVED BY THE ENGINEER.

BASIS OF PAYMENT: THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR CABLE GUARD MARKER.

REVISIONS
NAME

DATE

CABLE GUARD MARKER DETAIL

FAI 55 (I-55)

SECTION D-6 CABLE MEDIAN BAR #2

SANGAMON COUNTY

SCALE: HORIZ.

DRAWN BY