

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	54BR-1	MADISON	61	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

RESURFACING SCHEDULE

STATION		HMA BS COURSE WIDENING (SQ YD)	AGGREGATE PRIME COAT (TON)	BITUMINOUS MATERIAL PRIME COAT (TON)	HMA BINDER COURSE (TON)	HMA SURF. CSE, SUPER. MIX "C", N70 (TON)	HMA SHLD 1 1/2" (SQ YD)	AGG. SHLD TYPE B 6" (SQ YD)	AGG. BSE CSE TYPE B 8" (SQ YD)	SUB-BASE GR. MAT'L TYPE A 4" (SQ YD)	TEMP. RAMP (SQ YD)	BRIDGE APPROACH PVM'T (SQ YD)	STRIP REFL CRACK CTRL TREATMENT (FT)
665+15.50	RT/LT										86.67		
665+15.50 TO 667+99.00	RT/LT	189.00	1.22	0.26	596.15	63.51	252.00	189.00		220.5			567.00
666+03.00	FE							85.46					
667+99.00 TO 668+29.00	RT/LT											120.00	
671+02.00 TO 671+32.00	RT/LT											120.00	
671+32.00 TO 674+15.50	RT/LT	189.00	1.23	0.26	525.76	63.51	252.00	189.00		220.5			567.00
674+15.50	RT/LT										86.67		
TOTAL		378.00	2.45	0.52	1121.91	127.02	504.00	378.00	85.46	441.0	173.34	240.00	1134.00

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION		PAVEMENT MARKING	4" LINE PAVEMENT (FT)	4" LINE BRIDGE (FT)	6" LINE PAVEMENT (FT)	6" LINE BRIDGE (FT)	24" LINE PAVEMENT (FT)	WORK ZONE PVM'T MKNG REMOVAL (SQ FT)	PVM'T MKRG REMOVAL (SQ FT)	BARRIER WALL MKRS, TYPE C (EA)	
											STOP BAR
662+38.50		RT					13	4.3			
662+38.50 TO 664+00.00	CL	STAGE I	40.38					13.5			
664+14.89 TO 675+16.98	LT	STAGE I			823	333			23.1		
662+38.50 TO 665+15.50	CL										
665+15.50 TO 674+15.50	RT/LT	STAGE I	1378.00	422.00				600.0			
665+15.00 TO 675+17.00		STAGE I&II								28	
674+15.50 TO 676+87.00	CL								22.6		
675+00.00 TO 676+87.00	CL	STAGE I	46.8					15.6			
676+87.00	LT	STOP BAR					13.0	4.3			
664+08.42 TO 674+88.49	RT	STAGE II			801.0	333.0					
665+15.50 TO 674+15.50	RT/LT	STAGE II	1134.0	666.0				600.0			
TOTAL			2599.1	1088.0	1624.0	666.0	26.0	1237.7	45.7	28	
			3687.1		2290.0						

PAVEMENT MARKING SCHEDULE

STATION		PAVEMENT			BRIDGE		
		4" WHITE LINE (FT)	YELLOW SKIP DASH LINE 4" (FT)	DOUBLE AMBER RSD REFL PMK MKR (EA)	4" WHITE LINE (FT)	YELLOW SKIP DASH LINE 4" (FT)	DOUBLE AMBER RSD REFL PMK MKR (EA)
662+38.50 TO 667+99.00	CL		140.13	7			
665+15.50 TO 667+99.00	RT/LT	567.00					
667+99.00 TO 671+32.00	CL				83.25	4	
667+99.00 TO 671+32.00	RT/LT				666.00		
671+32.00 TO 676+87.00	CL		138.75	7			
671+32.00 TO 674+18.50	RT/LT	573.00					
SUB-TOTAL		1140.00	278.88	14	666.00	83.25	4
TOTAL			1418.88	14	749.25	4	

REMOVAL SCHEDULE

LOCATION		PVM'T REMOVAL (SQ YD)	HMA SURF. REM. BUTT JOINT (SQ YD)	SPBGR REMOVAL (FT)	PIPE CULV. REMOVAL 15" (FT)	RAISED REFL PVM'T MKRS REMOVAL (EA)
662+38.50 TO 667+99.00	CL					7
665+15.50 TO 665+71.00			160.33			
667+50.86	FE				44.50	
667+54.06 TO 668+79.06	LT			125.00		
667+66.56 TO 668+79.06	RT			112.50		
667+99.00 TO 668+79.06		235.82				
670+90.94 TO 671+32.00		123.17				
670+90.94 TO 672+15.94	LT			125.00		
670+90.94 TO 672+15.94	RT			125.00		
671+32.00 TO 676+87.00	CL					7
673+67.00 TO 674+15.50			140.11			
TOTAL		358.99	300.44	487.50	44.50	14

ROW MARKERS SCHEDULE

STA	OFFSET	RT/LT	ROW MKRS (EA)
667+00.00	40	RT	1
667+00.00	75	RT	1
667+02.34	40	LT	1
667+02.34	75	LT	1
672+50.00	40	RT	1
672+50.00	75	RT	1
672+50.00	40	LT	1
672+50.00	75	LT	1
TOTAL			8

ROW MARKER TO BE SET AT 1' OFFSET TO ROW/PROPERTY CORNER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

FAS ROUTE 1842
SECTION 106BR
ST CLAIR COUNTY

SCALE: VERT. DATE
HORIZ. DATE
DRAWN BY
CHECKED BY