

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9079	65BR	MADISON	46	7
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

WIDENING SCHEDULE

LOCATION	LT OR RT	HOT-MIX ASPHALT BASE COURSE	AGGREGATE SHOULDERS, TYPE B 6"
STATION TO STATION		SQ YD	SQ YD
STA 386+00.00 TO STA 386+55.00	LT	38.3	
STA 386+00.00 TO STA 386+53.50	RT	32.7	
STA 386+53.50 TO STA 387+74.96	RT	108.1	53.3
STA 386+55.00 TO STA 388+22.31	LT	176.7	34.4
BRIDGE OMISSION			
STA 388+58.81 TO STA 390+34.86	LT	185.9	33.1
STA 389+12.96 TO STA 390+36.49	RT	109.9	54.2
STA 390+34.86 TO STA 390+75.00	LT	27.9	
STA 390+36.49 TO STA 390+75.00	RT	23.5	
TOTAL		703	175

GUARDRAIL SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	TERMINAL MARKERS - DIRECT APPLIED	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	GUARDRAIL MARKERS, TYPE A
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
NW QUADRANT	1	1	1	1	1			1
NE QUADRANT	1	1	1	1	1			1
SW QUADRANT	1		1		1			1
SE QUADRANT	1		1		1			1
EASTBOUND						2	2	
WESTBOUND						2	2	
TOTAL	4	2	4	2	4	4	4	4

2 EACH TBT, TY 1 SPC (TANG) WILL BE PLACED PRIOR TO STAGE I CONSTRUCTION AS SHOWN ON THE PLANS.
2 EACH TBT, TY 6A WILL BE PLACED PRIOR TO STAGE I CONSTRUCTION AS SHOWN ON THE PLANS.

EROSION CONTROL SCHEDULE

LOCATION	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
	FOOT	EACH
NORTHWEST	219	2
NORTHEAST	300	2
SOUTHWEST	280	3
SOUTHEAST	370	1
TOTAL	1170	8

REMOVAL ITEMS SCHEDULE

LOCATION	LT OR RT	PAVED SHOULDER REMOVAL	PAVEMENT REMOVAL
STATION TO STATION		SQ YD	SQ YD
STA 386+55.00 TO STA 388+22.31	LT	51.0	
STA 387+74.96 TO STA 388+22.31			105.0
BRIDGE OMISSION			
STA 388+58.81 TO STA 389+12.96			120.0
STA 388+58.81 TO STA 390+34.86	LT	57.2	
TOTAL		108	225

STAGING SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAVEMENT MARKING LINE 6"	STEEL RAILING (TEMPORARY)	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE)
	FOOT	FOOT	FOOT	FOOT	EACH	EACH
STAGE I	250		250	38	2	
STAGE II		250				2
TOTAL	250	250	250	38	2	2

PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING LINE - 4"	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING -4"		POLYUREA PAVEMENT MARKING TYPE I-LINE 4"		PAVEMENT MARKING REMOVAL		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	REPLACEMENT REFLECTOR
			SKIP-DASH YELLOW	EDGE LINE WHITE	SKIP-DASH YELLOW	EDGE LINE WHITE	SKIP-DASH YELLOW	SOLID EDGE LINE WHITE			
STATION TO STATION	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	EACH	EACH	EACH
STA 385+34.77 TO STA. 386+00.00	146.8	48.9	16.3	130.5			5.6	43.5	1		1
STA 386+00.00 TO STA. 387+80.96	407.1	135.8	45.2	361.9			15.2	120.7	2		2
STA 387+80.96 TO STA. 389+06.96	284.0	94.7			31.6	252.4	10.6	84.0		2	
STA 389+06.96 TO STA. 390+75.00	378.1	126.1	42.0	336.1			14.2	112.1	2		2
STA 390+75.00 TO STA. 391+02.99	63.0	21.0	7.0	56.0			2.4	18.7			
SUBTOTAL			110.5	884.5	31.6	252.4	48.0	379.0			
TOTAL	1279	426.5		995		284	427		5	2	5

REPLACEMENT REFLECTORS (REMOVED DURING STAGE CONSTRUCTION) ARE FROM STOP BAR TO STOP BAR.

RIGHT-OF-WAY MARKERS SCHEDULE

LOCATION	LT OR RT	OFFSET DISTANCE	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS
STATION		FOOT	EACH
STA. 385+50	LT	40	1
STA. 385+50	RT	25	1
STA. 386+50	LT	107	1
STA. 387+50	RT	118	1
STA. 389+50	LT	107	1
STA. 389+75	RT	118	1
STA. 390+50	LT	77.61	1
STA. 390+50	RT	63.06	1
TOTAL			8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAU ROUTE 9079
SECTION 65BR
MADISON COUNTY
SN 060-0069 (E) 0236 (P)