

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	*	MADISON	26	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* 60-(7,8,9,10)I-2,60-(L2)I-3

GUARDRAIL REMOVAL				
RT/LT	STATION	TO	STATION	FT
RT	537+43		539+63	220
LT	575+98		579+16	318
RT	799+72		803+05	333
RT	872+88		875+58	270
RT	1344+22		1341+14	308
LT	1305+38		1302+43	295
LT	1292+12		1289+95	217
LT	1280+15		1276+83	332
LT	1268+84		1265+52	332
LT	1216+41		1213+12	329
			TOTAL	2954

RT/LT	STATION	TO	STATION	HTC BARRIER	
				FOOT	TERMINAL
RT	515+84		516+34		1
RT	516+34		524+69	835	
RT	524+69		525+19		1
LT	524+82		525+32		1
LT	525+32		529+00	368	
LT	529+00		542+39	1339	
LT	542+39		542+89		1
RT	546+13		546+63		1
RT	546+63		559+00	1237	
RT	559+00		566+65	765	
RT	566+65		567+15		1
RT	568+14		568+64		1
RT	568+64		574+00	536	
RT	574+00		586+67	1267	
RT	586+67		587+17		1
LT	586+84		587+34		1
LT	587+34		589+00	166	
LT	589+00		604+00	1500	
LT	604+00		619+00	1500	
LT	619+00		623+94	494	
LT	623+94		624+44		1
RT	626+22		626+72		1
RT	626+72		634+00	728	
RT	634+00		649+00	1500	
RT	649+00		664+00	1500	
RT	664+00		669+68	568	
RT	669+68		670+18		1
LT	669+82		670+32		1
LT	670+32		679+00	868	
LT	679+00	*	690+69	1167	
LT	* 696+65		700+00	333	
LT	700+00		714+70	1470	
LT	714+70		715+20		1
RT	713+95		714+45		1
RT	714+45		730+00	1555	
RT	730+00		745+00	1500	
RT	745+00		759+89	1489	
RT	759+89		760+39		1
RT	761+36		761+86		1
RT	761+86		775+00	1314	
RT	775+00		782+64	764	
RT	782+64		783+14		1
LT	782+85		783+35		1
LT	783+35		790+00	665	
LT	790+00		791+60	160	
LT	791+60		792+10		1
RT	793+77		794+27		1
RT	794+27		805+00	1073	
RT	805+00		820+00	1500	
RT	820+00		835+00	1500	
RT	835+00		850+00	1500	
RT	850+00		865+00	1500	
RT	865+00		880+00	1500	
RT	880+00	**	885+68	579	
RT	**1353+21		1344+00	921	
RT	1344+00		1329+00	1500	
RT	1329+00		1314+00	1500	
RT	1314+00		1311+36	264	
RT	1311+36		1310+86		1
LT	1311+14		1310+64		1
LT	1310+64		1299+00	1164	
LT	1299+00		1284+00	1500	
LT	1284+00		1269+00	1500	
LT	1269+00		1254+00	1500	
LT	1254+00		1239+00	1500	
LT	1239+00		1235+54	346	
LT	1235+54		1235+04		1
LT	1234+17		1233+67		1
LT	1233+67		1224+00	967	
LT	1224+00		1209+00	1500	
LT	1209+00		1194+00	1500	
LT	1194+00		1190+61	339	
LT	1190+61		1190+11		1
			TOTAL	50741	26

HOT MIX ASPHALT SHOULDER, 4"

RT/LT	STATION	TO	STATION	LENGTH	WIDTH	SQ YD
RT	515+84		525+19	935	4	416
LT	524+82		542+89	1807	4	803
RT	546+13		567+15	2102	4	934
RT	568+14		587+17	1903	4	846
LT	586+84		624+44	3760	4	1671
RT	626+22		670+18	4396	4	1954
LT	669+82	*	690+69	2034	4	904
LT	* 696+65		715+20	1851	4	823
RT	713+95		760+39	4644	4	2064
RT	761+36		783+14	2178	4	968
LT	782+85		792+10	925	4	411
RT	793+77	**	885+68	9189	4	4084
RT	** 1353+21		1310+86	4235	4	1882
LT	1311+14		1235+04	7610	4	3382
LT	1234+17		1190+11	4406	4	1958
			TOTAL			23100

* STA. EQUATION:
STA. 690+69 = STA 696+65

** STA. EQUATION:
STA. 885+68 =
STA. 1353+21

PLOT DATE = 12/11/2006
DRAWN BY = JACOB VANDERKAM
CHECKED BY = JACOB VANDERKAM
SCALE = AS SHOWN
REFERENCE = SHEET #

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
FAI ROUTE 55/70
SECTION 60-(7,8,9,10)I-2,60(1,2)I-3
MADISON COUNTY

SCALE: VERT.
DATE: HORIZ.

DRAWN BY
CHECKED BY