

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10	60-110.11185	MADISON	156	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	1000-2A 90% FED, 10% STATE RAODWAY	SFTY-2A 90% FED 10% STATE SN 060-0022	SFTY-2A 90% FED 10% STATE SN 060-0059	SFTY-2A 90% FED 10% STATE SN 060-0173	SFTY-2A 90% FED 10% STATE SN 060-0023	SFTY-2A 90% FED 10% STATE SN 060-0024	SFTY-2A 90% FED 10% STATE SN 060-0182	SFTY-2A 90% FED 10% STATE SN 060-0057	SFTY-2A 90% FED 10% STATE SN 060-0058	Y002-1C 100% STATE SIGNING	Y002-1C 90% FED 10% STATE SIGNING
CODE NO	ITEM	UNIT												
50104650	SLOPE WALL REMOVAL	SQ YD	4135					1940	2195					
50157300	PROTECTIVE SHIELD	SQ YD	520				289			231				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	41.2					21.6	19.6					
50300260	BRIDGE DECK GROOVING	SQ YD	1285					613	672					
50300300	PROTECTIVE COAT	SQ YD	2189				290	780	854	265				
50300530	FLOOR DRAIN EXTENSION	EACH	40				8		20	12				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	7140					3640	3500					
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	42					21	21					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7080					3680	3400					
50800515	BAR SPLICERS	EACH	64					36	28					
50901001	STEEL BRIDGE RAIL	FOOT	935				491			444				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	168					84	84					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	42					21	21					
58700300	CONCRETE SEALER	SQ FT	59411		19766	12735					13734	13176		
60100080	FRENCH DRAINS	CU YD	35	35										
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2100	2100										
* 60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ YD	285	285										
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	187.5	187.5										
* 63000015	STEEL PLATE BEAM GUARD RAIL, TYPE D	FOOT	275	275										
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	8	8										
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	5	5										
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8				4			4				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	14	14										
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	2	2										
63200310	GUARDRAIL REMOVAL	FOOT	2537.5	2537.5			200			200				
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	5187.5	5187.5										
63301215	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	150	150										
63500105	DELINEATORS	EACH	274	274										
63500120	DELINEATOR REMOVAL	EACH	274	274										
64200105	SHOULDER RUMBLE STRIP	FOOT	84,476	84,476										
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	14			1	1	1	1				
67100100	MOBILIZATION	L SUM	1	0.6			0.1	0.1	0.1	0.1				
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	2				1			1				
X0325701	STEEL RAILING, TYPE 2399	FOOT	935				491			444				
X0301199	ANCHOR BOLTS	EACH	86					42	44					

* SPECIALTY ITEMS

PLOT DATE = 12/14/2006
 FILE NAME = c:\pwork\sect\459999\1\IN\00705.dgn
 PLOT SCALE = 45.9999 / IN.
 REFERENCE = #REF#

Rev.