

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
IQ	60-(10,11)RS	MADISON	154	14
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS				PREFORMED PLASTIC PAVEMENT MARKING WET REFLECTIVE, TYPE B	POLYUREA PAVEMENT MARKING - LINE 4"			RAISED REFLECTIVE PAVEMENT MARKERS				PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL	DELINATOR REMOVAL	DELINATORS				
	LINE 4"		LINE 8" LINE 12"		LINE 4"	LINE 4"		SKIP-DASH	ONE-WAY AMBER @ 40' CENTERS	ONE-WAY CRYSTAL @ 40' CENTERS	ONE-WAY CRYSTAL @ 20' CENTERS	DOUBLE ONE-WAY CRYSTAL @ 80' CENTERS									
	WHITE	YELLOW	WHITE	WHITE	SKIP-DASH	WHITE	YELLOW	WHITE	EACH	EACH	EACH	EACH									
STA.	TO	STA.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	SO FT	EACH	EACH	EACH	EACH		
EASTBOUND TO																					
891+26	TO	899+32	806																		
899+32	TO	902+00	268		268									7					40		
902+00	TO	903+26	126		126									13					20		
903+26	TO	903+60	34		34									3					6		
903+60	TO	917+00	1340	1340										1					5		
917+00	TO	932+00	1500	1500										2					2		
932+00	TO	939+12	712	712										38					34		
939+12	TO	947+00	788		788														38		
947+00	TO	949+70	270	270	540														18		
949+70	TO	957+37	767	767										20					40		
957+37	TO	962+00	463	463										14					28		
962+00	TO	965+00	300	300															38		
WESTBOUND TO																					
901+06	TO	902+00	94		94														12		
902+00	TO	905+46	346		346									3					5		
905+46	TO	911+00	554	554										9					18		
911+00	TO	915+13	187	187															14		
915+13	TO	917+00	1500	1500															11		
917+00	TO	932+00	1356	1356															5		
932+00	TO	945+56	144		144														38		
945+56	TO	947+00	676	676	1352	255								4					34		
947+00	TO	953+76	487	487										34					8		
953+76	TO	958+63	337	337															68		
958+63	TO	962+00	294	294															24		
962+00	TO	964+94	75		75														8		
FAI TO																					
965+00	TO	980+00	3000	3000															75		
980+00	TO	995+00	750		750														75		
EB FAI TO																					
995+00	TO	995+85	85	85															2		
995+85	TO	997+48	20		20														4		
WB FAI TO																					
995+00	TO	995+99	99	99															3		
995+99	TO	997+48	30		30														4		
FAI TO																					
997+48	TO	1010+00	2504	2504															63		
1010+00	TO	1025+00	750		750														75		
1025+00	TO	103+65	1130	1130															28		
WESTBOUND 270																					
861+44	TO	863+49	205		205														6		
863+49	TO	872+89	940		940														5		
872+89	TO	874+03	114		114														24		
874+03	TO	875+00	97		97														3		
875+00	TO	878+95	395		395														2		
878+95	TO	885+89	694		694														10		
885+89	TO	887+27	138		138														18		
EASTBOUND 270																					
861+08	TO	861+74	66	66															2		
861+74	TO	862+71	97		97														3		
862+71	TO	864+37	166		166														4		
864+37	TO	871+97	760	760															19		
871+97	TO	874+61	78		78														7		
874+61	TO	875+00	534		534														1		
875+00	TO	880+34	787		787														14		
880+34	TO	888+21	200		200														20		
RAMP G1																					
2+72	TO	4+96	224		224														6		
4+96	TO	7+00	204		204														11		
7+00	TO	8+93	193		193														5		
8+93	TO	16+88	795		795														5		
RAMP G3																					
7+00	TO	8+56	156	156															4		
8+56	TO	20+50	1194	1194															4		
RAMP G4																					
8+20	TO	12+06	386	386															10		
12+06	TO	16+00	394	394															10		
16+00	TO	29+30	1330	1330															7		
29+30	TO	32+00	270		270														5		
32+00	TO	33+76	176		176														5		
RAMP G5																					
0+00	TO	3+00	300		300														15		
3+00	TO	4+90	190		190														10		
4+90	TO	6+04	114		114														9		
6+04	TO	12+02	598		598														15		
12+02	TO	20+00	798		798														4		
20+00	TO	24+25	425		425														4		
24+25	TO	25+55	130		130														4		
RAMP G6																					
1+78	TO	2+39	61		61														5		
2+39	TO	7+30	491		491														13		
7+30	TO	11+14	384		384														6		
11+14	TO	13+15	201		201														6		
RAMP G7																					
0+00	TO	0+95	95		95														5		
0+95	TO	2+57	162		162														12		
2+57	TO	3+60	103		103														3		
3+60	TO	14+51	1091		1091														4		
14+51	TO	15+82	131		131														5		
SUBTOTAL			41834	35097	6433	381		7935	989	989	255		127	185	101	814	742	26	1253	274	274
TOTAL			76931	6433	381		7935		2233				1227			742	26	1253	274	274	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SCHEDULES</p> <p>FAI ROUTE 70 SECTION 60-(10,11)RS MADISON COUNTY</p> <p>SCALE: VERT. _____ HORIZ. _____</p> <p>DRAWN BY _____ CHECKED BY _____</p>

PLOT DATE = #DATE#
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
REFERENCE = #REF#