

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	S.N. 082-0087		S.N. 082-0212		
				BRIDGE CANAL NO. 1	RDWY CANAL NO. 1	BRIDGE HARDING DITCH	RDWY HARDING DITCH	RDWY HARDING DITCH
20200100	EARTH EXCAVATION	CU YD	30	30				
20400800	FURNISHED EXCAVATION	CU YD	12,830	12,830				
20700400	POROUS GRANULAR EMBANKMENT <i>SPECIAL</i>	CU YD	55		55			
25000200	SEEDING, CLASS 2	ACRE	1.25		1.25			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	113		113			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	113		113			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	113		113			
25100105	MULCH, METHOD 1	ACRE	1.25		1.25			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	625		625			
28000400	PERIMETER EROSION BARRIER	FOOT	1040		1040			
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	132		132			
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	16		12			4
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	80		80			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.2		1.1		0.1	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	446	446				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	112		77		35	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	13		13			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	223		223			
42001300	PROTECTIVE COAT	SQ YD	420		420			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	580		267		313	
44000100	PAVEMENT REMOVAL	SQ YD	223				223	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	296		229		67	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	296		229		67	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1			
50102400	CONCRETE REMOVAL	CU YD	12.5		12.5			
50200100	STRUCTURE EXCAVATION	CU YD	63		63			
50200300	COFFERDAM EXCAVATION	CU YD	1133	1133				
50200500	COFFERDAMS	EACH	1	1				
50300225	CONCRETE STRUCTURES	CU YD	15.3		15.3			
50300260	BRIDGE DECK GROOVING	SQ YD	420		420			
50300265	SEAL COAT CONCRETE	CU YD	852.3	852.3				
50301200	CONCRETE WEARING SURFACE	SQ YD	420		420			
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	3770		3770			
50800105	REINFORCEMENT BARS	POUND	50130	50130				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7430		7430			
50800515	BAR SPLICERS	EACH	68		68			
50901050	STEEL RAILING, TYPE SM	FOOT	229		229			
51500100	NAME PLATES	EACH	2	1		1		

PLOT DATE = 12/11/2006
 FILE NAME = c:\prow\meta\w84425\plan\p04485.dgn
 PLOT DEVICE = HPGL2
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = SHEET #

Rev. 2-26-07