

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
592	28BR-2,3	ST. CLAIR	51	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

X02B-2A
ACBHE

X080-2A
ACBHE

ILLINOIS DEPARTMENT OF TRANSPORTATION

CONSTRUCTION TYPE CODE

S.N. 082-0087 S.N. 082-0212

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	S.N. 082-0087			S.N. 082-0212		
				BRIDGE CANAL NO. 1	RDWY CANAL NO. 1	BRIDGE HARDING DITCH	RDWY HARDING DITCH	RDWY HARDING DITCH	
54003000	CONCRETE BOX CULVERTS	CU YD	212.1	212.1					
58700300	CONCRETE SEALER	SQ FT	48.2			48.2			
59000200	EPOXY CRACK INJECTION	FOOT	34			34			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	26			26			
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	2.1			2.1			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	112			112			
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1370	979		391			
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4			4			
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6	2		4			
63200310	GUARDRAIL REMOVAL	FOOT	1120	721		399			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4		4				
66700095	PERMANENT SURVEY MARKERS	EACH	2		2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	1.6	1.6	1.6	1.6	1.6	
67100100	MOBILIZATION	L SUM	1	0.5		0.5			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5		0.5			
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	0.5		0.5			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	1.6	1.6	1.6	1.6	1.6	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	9						
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	16			16			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1775			400			
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1444	976		468			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	4		4			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	16		16			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	2		4			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5	2		3			
* 88600100	DETECTOR LOOP, TYPE I	FOOT	26					26	
X0323491	SLOPEWALL CRACK SEALING	FOOT	130			130			
X0323557	BRIDGE JOINT SYSTEM (EXPANSION) 1"	FOOT	66			66			
X0325294	PREFORMED JOINT STRIP SEAL	L SUM	1	0.5		0.5			
X0324952	DETOUR SIGNING	SQ FT	193			193			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	193			193			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	66	66					
Z0065700	SLOPE WALL REPAIR	SQ YD	8			8			
⊙ Z0070600	TRAINEES	HOUR	1000	1000					

PLOT DATE = *DATE*
PLOT SCALE = *SCALE*
PLOT SCALE = *SCALE*
REFERENCE = *REF*

© 1980
*SPECIALTY ITEMS

△ Rev. 2-26-07

Rev.