

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	94-F3000-06-BT	COOK	105	2
STA.	TO STA.			
FED. ROAD DIST. NO.	STATE	83709	STPE-D001(479)	

INDEX OF SHEETS

1	TITLE SHEET
2	GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	TYPICAL SECTIONS AND HOT-MIX ASPHALT REQUIREMENTS
6-8	EARTHWORK SCHEDULE
9-15	ALIGNMENT, BENCHMARKS & TIES
16	LOCATION DRAWING
17-21	PLAN & PROFILE - CRABTREE TRAIL
22-39	PLAN & PROFILE - PAUL DOUGLAS TRAIL
40	PARKING LOT PLAN
41	STRUCTURAL NOTES
42	WETFOOT DAM RETAINING WALL PLANS
43	CONCRETE BLOCK WALL DETAIL
44	WINGWALL EXTENSION DETAILS
45	BICYCLE RAILING DETAILS
46	SHEET PILING DETAILS
47	ILL. RTE. 62 & ROSELLE RD. - TRAFFIC SIGNAL MODIFICATION PLAN
48	ILL. RTE. 62 & ROSELLE RD. - SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
49-55	EROSION CONTROL PLAN
56-62	PAVEMENT MARKING & SIGNING PLAN
63	FOREST PRESERVE CONSTRUCTION DETAILS
64	DETAIL OF PRIVATE DRIVE AND SUMMARY OF DRIVEWAY PAVEMENT
65	TRAIL HEAD SIGN DETAILS
66	DISTRICT ONE CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
67	BENCHING DETAIL FOR EMBANKMENT WIDENING
68	DROP MANHOLE DETAILS
69	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
70-73	DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS
74-80	CRABTREE TRAIL - CROSS-SECTIONS
81-105	PAUL DOUGLAS TRAIL - CROSS-SECTIONS

STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-03	TEMPORARY EROSION CONTROL SYSTEMS
424001-04	SIDEWALK RAMPS ACCESSIBLE TO THE DISABLED
542301-01	PRECAST REINFORCED CONCRETE FLARED END SECTION
542306-01	PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION
542401	METAL END SECTION FOR PIPE CULVERTS
604001-02	FRAME AND LIDS TYPE 1
606001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
664001-01	CHAIN LINK FENCE
701001-01	OFF-RD OPERATIONS, 2L, 2W, 4.5m (15') AWAY FOR SPEEDS \geq 45 MPH
701006-02	OFF-RD OPERATIONS, 2L, 2W, 4.5m (15') TO PAVEMENT EDGE FOR SPEEDS \geq 45 MPH
701101-01	OFF-RD OPERATIONS, MULTILANE, LESS THAN 4.5m (15') AWAY FOR SPEEDS \geq 45 MPH
701106-01	OFF-RD OPERATIONS, MULTILANE, MORE THAN 4.5m (15') AWAY FOR SPEEDS \geq 45 MPH
701301-02	LANE CLOSURE, 2L, 2W, SHORT TERM OPERATIONS
701501-03	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701601-04	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NON TRAVERSABLE MEDIUM
701606-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIUM
702001-06	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720011	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
729001	APPLICATIONS FOR TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

GENERAL NOTES

- ALL EXCESS MATERIAL SHALL BE WASTED OUTSIDE THE LIMITS OF THE COOK COUNTY FOREST PRESERVE DISTRICT UNLESS OTHERWISE SPECIFIED OR AS DIRECTED BY THE ENGINEER. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO SELECT DUMP SITES, OBTAIN PERMISSION TO USE SUCH DUMP SITES, AND UPON THE COMPLETION OF THE WORK, SUBMIT RELEASE FROM THE RESPECTIVE OWNERS OF THESE DUMP SITES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE OR DESTRUCTION OF PUBLIC OR PRIVATE PROPERTY, AND SHALL RESTORE SUCH PROPERTY AT HIS OWN EXPENSE.
- FINISHED GRADE: THE ELEVATION SHOWN ON THE PLANS ARE FINISHED GRADES OF PROPOSED TRAIL AND GROUND SURFACE UNLESS OTHERWISE INDICATED ON THE PLANS. THE PLACEMENT OF PIPE CULVERTS AND BLIND CONNECTIONS SHALL BE DETERMINED BY THE ENGINEER, IN THE FIELD, IN ORDER TO ACHIEVE POSITIVE DRAINAGE.
- THE EFFECTED FOREST PRESERVE DISTRICT SHALL BE NOTIFIED AT LEAST 48 HOURS PRIOR TO ANY TREE REMOVAL AFTER ALL TREES TO BE REMOVED HAVE BEEN MARKED.
- MINIMAL GRADING IS TO BE PERMITTED WITHIN AN APPROXIMATE RADIUS OF SIX FEET OF ALL TREES NOT TO BE REMOVED AND AS DETERMINED BY THE ENGINEER.
- ALL CONSTRUCTION PERSONNEL WILL BE REQUIRED TO WEAR FLUORESCENT ORANGE VESTS MEETING ANSI CLASS II REQUIREMENTS AT ALL TIMES WHILE ON THE CONSTRUCTION SITE. COMPLIANCE WITH THIS REQUIREMENT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED UTILITIES, INCLUDING ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- UNLESS OTHERWISE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS, ALL TRAFFIC SIGNING AND PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" AND THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- QUANTITIES SHOWN ON THE PLANS ARE BASED ON THE FIELD INSPECTION AT THE TIME OF PLAN PREPARATION AND ARE TO BE USED FOR PREPARATION PROPOSALS. HOWEVER, AS DETERMINED BY THE ENGINEER, QUANTITIES MAY CHANGE BASED UPON CONDITIONS UNCOVERED AT THE TIME OF CONSTRUCTION.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON FOREST PRESERVE DISTRICT PROPERTY WITHOUT WRITTEN PERMISSION FROM THE FOREST PRESERVE DISTRICT OF COOK COUNTY.
- WETLANDS HAVE BEEN IDENTIFIED ON THIS PROJECT AND IMPACTS TO THEM SHALL BE AVOIDED. THE CONTRACTOR SHALL LIMIT EQUIPMENT AND VEHICLES TO THE AREAS DEFINED BY THE TEMPORARY FENCING AND ALLOWED TURNAROUND AREAS SPECIFIED BY THE ENGINEER. THE LIMITS OF EROSION CONTROL INSTALLATION SHALL BE VERIFIED BY THE RESIDENT ENGINEER.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND ALL LOCAL AGENCIES.
- TEMPORARY EROSION CONTROL SHALL BE IN ACCORDANCE WITH IDOT SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (ADOPTED JANUARY 1, 2007), SECTION 280.
- ALL EMBANKMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH IDOT SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (ADOPTED JANUARY 1, 2007), SECTION 205. BENCHING SHALL BE INCLUDED IN THE UNIT PRICE OF EARTH EXCAVATION.
- ANY EXISTING BITUMINOUS SURFACE TO BE REMOVED ON STOVER ROAD SHALL BE MEASURED AND PAID FOR AS EARTH EXCAVATION.

17. LOCAL AGENCIES

VILLAGE OF HOFFMAN ESTATES
1900 HASSELL ROAD
HOFFMAN ESTATES, IL 60195
(847) 882-9100

COOK COUNTY HIGHWAY DEPARTMENT
69 W. WASHINGTON STREET, ROOM 2300
CHICAGO, IL 60602
(312) 603-1600

VILLAGE OF SOUTH BARRINGTON
30 SOUTH BARRINGTON ROAD
SOUTH BARRINGTON, IL 60010
(847) 381-7510

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

INDEX OF SHEETS, STANDARDS AND GENERAL NOTES

SCALE NONE
DATE 3/27/06
DRAWN BY RTA
CHECKED BY SMH