F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1389	99-00062-00-PV	DUPAGE	199	20
	CONTRACT NO. 83873			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCALE IN FEET 20 0 20 40

N

EXISTING CONDITIONS

MATCH LINE STA. 35+00

MATCH LINE STA. 41+00

"01 HAWTHORNE LANE" EX R.O.W. — 1701 — 1700 – 1860 — EX R.O.W.

℄ CONSTRUCTION & PGL

SECTION LINE

"NO PARKING" "STOP AHEAD" "NO PARKING"

GRAVEL SHOULDER GRAVEL SHOULDER

HAWTHORNE LANE

35+00 36 37 38 39 40+00

50' 6' 33'

"GAS" MULTIPLE BUSINESS SIGNS "TRUCKS"

37+90 38+00 38+40 38+50

35' 21'

1' (TYP.) BOLLARD REMOVAL

PROPOSED LEGEND

- TEMPORARY EASEMENT
- 1801 BUILDING ADDRESS
- TYPE A RAMP
- COMB CC&G (DEPRESSED)
- DETECTABLE WARNINGS
- HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70; 2" LEVELING BINDER (MACHINE METHOD), N50; 3/4"

EXISTING LEGEND

- PAVEMENT REMOVAL (HOT-MIX ASPHALT)
- HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"
- CURB AND GUTTER OR CURB REMOVAL
- FENCE REMOVAL
- DRIVEWAY REMOVAL
- SIDEWALK REMOVAL
- 18" TREE REMOVAL (OF SIZE SHOWN)
- TEMPORARY FENCE

PROPOSED CONDITIONS

EX R.O.W. — COMB CC&G TY B-6.24 (TYP.) — ℄ CONSTRUCTION & PGL — SECTION LINE

HAWTHORNE LANE

35+00 36 37 38 39 40+00

50' 6' 24' 12' 7' 10' 8' 33'

R=35' R=35' +07.5 34.3 RT. +45.9 34.3 RT. EX R.O.W.

35' 1' (TYP.) +27 BIT CE

SHARED USE PATH

EOP ELEV 752.54 EOP ELEV 752.79

R=35' R=35' R=35'

+37.3 41.4 RT +03.4 42.8 RT +20 BIT CE

37+90 38+00 38+40 38+50 21'

PR R.O.W.

CORRUGATED CONCRETE MEDIAN (TYP.) 44' +44 CONC CE

EX R.O.W. R=10' COMB CC&G TY B6.12 (TYP.) R=35' +19.5 36.2 LT. +69.8 35.5 LT. 20' 4' 20' R=10' R=35'

PROFILE

760 / 755 / 750 / 745

PROPOSED PGL

EXISTING PROFILE ALONG ℄

PATH PGL

VPI STA. 35+68.00 ELEVATION 754.69

+0.50% -0.50%

ex = -0.18' K = 140 140.00' V.C.

+38.00 EL. 754.34

ex = 0.18' K = 140 140.00' V.C.

+60.00 EL. 752.22

REMOVAL OF UNSUITABLE MATERIAL POROUS GRANULAR EMBANKMENT, SUBGRADE

EX. ELEV. ALONG PGL 754.25 754.25 754.00 753.80 753.55 753.41 753.29 753.09 753.01 752.87 752.62 752.45 752.24

PROP. ELEV. ALONG PGL 754.35 754.50 754.48 754.28 754.03 753.78 753.53 753.27 753.02 752.77 752.52 752.27 752.08

35+00 35+50 36+00 36+50 37+00 37+50 38+00 38+50 39+00 39+50 40+00 40+50 41+00

ILLINOIS DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE HAWTHORNE LANE STA. 35+00 TO STA. 41+00

SCALE: VERT.: 1"=5' HORIZ.: 1"=20' DATE 12/7/2006

DRAWN BY PMM DESIGN BY BLL CHECKED BY JGS

N:\WestChi\04479\04479.TBL

20'

N:\WestChi\04479\Civil\04479_03.rpp