

SUMMARY OF QUANTITIES					
CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A	
				75% FEDERAL 25% LOCAL	100% LOCAL
60500060	REMOVING INLETS	EACH	21	21	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,600	4,650	950
67000400	ENGINEER'S FIELD OFFICE - TYPE A	CALMO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SQFT	75	75	
72900100	METAL POST - TYPE A	FOOT	25	25	
72900200	METAL POST - TYPE B	FOOT	160	160	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,700	3,700	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	600	600	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50	
* A2000924	TREE, ACER PLATANOIDES EMERALD QUEEN (EMERALD QUEEN NORWAY MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
* A2001724	TREE, ACER SACCHARUM (SUGAR MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
* A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
* A2008124	TREE, TILIA CORDATA (GREENSPIRE LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
* K1003679	MULCH	CUYD	80	80	
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	23	19	4
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	1,400	1400	
X6020098	MANHOLES, TYPE A, 9' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	2	1
X0104800	CHANGEABLE MESSAGE SIGN	CAL-MO	1	1	
* XX000479	WATER MAIN REMOVAL, 6 INCH	FOOT	370	370	
XX000541	EXPLORATORY EXCAVATION	CUYD	50	50	
XX000836	PRESSURE TESTING AND DISINFECTION	L SUM	1		1
XX001386	SANITARY SEWERS, PVC, 8"	FOOT	180	180	
XX001464	SANITARY SEWERS, PVC, 6"	FOOT	1,000	946	54
XX001466	SANITARY SEWERS, PVC, 12"	FOOT	365	365	
XX001490	GATE VALVES, 8"	EACH	1		1
XX001672	STORM SEWERS, (POLYVINYL CHLORIDE) SDR 26, 12"	FOOT	260	112	147
* XX002907	WATER SERVICE CONNECTION (SHORT)	EACH	10		10
* XX004814	WATER SERVICE CONNECTION (LONG)	EACH	4	1	3
XX003036	STORM SEWERS, PVC, SDR 26, 10"	FOOT	386	336	50
XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	1,400	720	680
* XX003516	CONNECTION TO EXISTING WATER MAINS (NON-PRESSURE) - 8"	EACH	1		1
* XX003517	CONNECTION TO EXISTING WATER MAINS (NON-PRESSURE) - 6"	EACH	1		1
XX005197	BOX STRUCTURE	EACH	2	2	
XX005634	12" X 6" PVC SEWER SERVICE CONNECTIONS	EACH	17	14	3
XX005636	PIPE UNDERDRAINS, PERFORATED POLYVINYL CHLORIDE PIPE, 6"	FOOT	138	114	24
XX006203	STORM SEWERS, PVC, SDR 26, 8"	FOOT	25		25
XX006227	RESTRAINED JOINT, 8"	EACH	19	0	19
XX006228	RESTRAINED JOINT, 6"	EACH	40	28	12
XX006445	RESTRICTED DEPTH COMBINED SEWER MANHOLES, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	8	3
XX006449	12" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	131	66	65
XX006450	15" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	34	34	
XX006452	15" X 6" PVC SEWER SERVICE CONNECTIONS	EACH	6	6	
XX006453	6" PVC SEWER SERVICE PIPE REPAIR ACROSS TRENCH	FOOT	100	100	
* XX006454	WATER SERVICE RELOCATION	EACH	35	35	
Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHoles (HOT MIX)	TON	25	25	
Z0019600	DUST CONTROL WATERING	UNIT	100	100	
Δ Z0076600	TRAINEES	HOUR	1,000	1,000	
XX004815	8" X 6" PVC SEWER SERVICE CONNECTIONS	EACH	2	2	
XX004816	12" X 6" PVC SEWER SERVICE CONNECTIONS (SPECIAL)	EACH	9	9	
XX004817	15" X 6" PVC SEWER SERVICE CONNECTIONS (SPECIAL)	EACH	3	3	
* XX004818	WATER SERVICE RELOCATION (STORM SEWER)	EACH	38	38	

* DENOTES SPECIALTY ITEM
Δ Y080



◆ Civil Engineers
◆ Municipal Consultants
◆ Established 1911

9933 Roosevelt Road
Westchester, Illinois 60154-2780
Phone: 708/865-0300
Fax: 708/865-1212

**PRAIRIE AVENUE IMPROVEMENTS
PHASE II
VILLAGE OF BROOKFIELD, ILLINOIS**

SUMMARY OF QUANTITIES

SCALE:	NONE	SHEET	5
DRAWN BY:	MK/LEV	BOOK NO.:	#1475, #1504
DATE:	10-6-06	REVISION:	
E.H.E. NO.:	125-04-26301	OF	47