

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1700	05-00045-02-PV	COOK/DUPAGE	103	4
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003(544)				

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				1000-1A	Y030-1E	Y031-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	82	82		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	108	108		
20101000	TEMPORARY FENCE	FOOT	1080	1080		
20101100	TREE TRUNK PROTECTION	EACH	36	36		
20101200	TREE ROOT PRUNING	EACH	36	36		
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	11	11		
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	25	25		
20200100	EARTH EXCAVATION	CY YD	15618	15618		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CY YD	1200	1200		
20400800	FURNISHED EXCAVATION	CY YD	1327	1327		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CY YD	1200	1200		
20800150	TRENCH BACKFILL	CY YD	216	216		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SD YD	3600	3600		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SD YD	10275	10275		
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	500	500		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	128	128		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	128	128		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	128	128		
25200100	SODDING	SD YD	10275	10275		
25200200	SUPPLEMENTAL WATERING	UNIT	155	155		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	213	213		
28000400	PERIMETER EROSION BARRIER	FOOT	1000	1000		
28000510	INLET FILTERS	EACH	89	89		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SD YD	261	261		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25000	25000		
40600300	AGGREGATE (PRIME COAT)	TON	37	37		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	18	18		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SD YD	19	19		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SD YD	42	42		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	147	147		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	122	122		
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SD YD	32006	32006		
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SD YD	68	68		
42001300	PROTECTIVE COAT	SD YD	11010	11010		
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SD YD	3767	3767		
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SD FT	35500	35500		
42400460	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH, SPECIAL	SD FT	2577	2577		
42400800	DETECTABLE WARNING	SD FT	910	910		
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SD YD	606	606		
44000100	PAVEMENT REMOVAL	SD YD	29426	29426		
44000200	DRIVEWAY PAVEMENT REMOVAL	SD YD	3734	3734		
44000300	CURB REMOVAL	FOOT	90	90		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12610	12610		
44000600	SIDEWALK REMOVAL	SD FT	31680	31680		
44003100	MEDIAN REMOVAL	SD FT	60	60		
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SD YD	5	5		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SD YD	11	11		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SD YD	178	178		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	210	210		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	837	837		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	40	40		
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	8	8		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	24	24		
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	16	16		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	9	9		
55100500	STORM SEWER REMOVAL 12"	FOOT	185	185		
55100900	STORM SEWER REMOVAL 18"	FOOT	40	40		
55101100	STORM SEWER REMOVAL 21"	FOOT	8	8		
55101200	STORM SEWER REMOVAL 24"	FOOT	24	24		
55101300	STORM SEWER REMOVAL 27"	FOOT	16	16		
* 56100600	WATER MAIN 6"	FOOT	45	45		
* 56106300	ADJUSTING WATER MAIN 6"	FOOT	50	50		
* 56106500	ADJUSTING WATER MAIN 10"	FOOT	350	350		
* 56106600	ADJUSTING WATER MAIN 12"	FOOT	300	300		
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2		
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	6	6		
* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	6	6		
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	2		

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				1000-1A	Y030-1E	Y031-1F
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	1050	1050		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	9	9		
60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	22	22		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	11	11		
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	8	8		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60258100	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	3	3		
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	7	7		
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	12	12		
60500040	REMOVING MANHOLES	EACH	7	7		
60500060	REMOVING INLETS	EACH	11	11		
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	6	6		
60500305	FILLING INLETS	EACH	1	1		
60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	104	104		
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	12664	12664		
60624600	CORRUGATED MEDIAN	SD FT	14	14		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	950	950		
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SD FT	2300	2300		
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	52700	52700		
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	10800	10800		
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	1350	1350		
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	2370	2370		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SD FT	1540	1540		
72000100	SIGN PANEL - TYPE 1	SD FT	145	120	25	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	30	30		
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	82	82		
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1361	1361		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SD FT	822	822		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14924	14924		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4082	4082		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	674	674		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	669	669		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	100	100		
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	403	403		
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	98	98		
78300100	PAVEMENT MARKING REMOVAL	SD FT	3500	3500		
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	481		481	
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	182	96	86	
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	8		8	
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	145		145	
81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	197		197	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	214		214	
81018600	CONDUIT PUSHED, 2-1/2" DIA., GALVANIZED STEEL	FOOT	936	936		
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	140		140	
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	42		42	
81028040	CONDUIT BORED AND PULLED, COLLAPSE NON-METALLIC CONDUIT, 1-1/4"	FOOT	1050	1050		
81400100	HANDHOLE	EACH	5		5	
81400200	HEAVY-DUTY HANDHOLE	EACH	4		4	

* INDICATES SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

DRAWN BY DJK
CHECKED BY JRV

DATE 12/22/06