

| | | | | |
|--|----------------|-------------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | 06-00051-00-MS | COOK/DUPAGE | 14 | 4 |
| SUMMARY OF QUANTITIES | | | | |
| FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-80036581 | | | | |

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE |
|-----------------------|---|--------|------------------------|
| CODE NO. | PAY ITEM | UNIT | TOTAL |
| | | | Y108 |
| 20101000 | TEMPORARY FENCE | FOOT | 120 |
| 20101100 | TREE TRUNK PROTECTION | EACH | 4 |
| 20101200 | TREE ROOT PRUNING | EACH | 4 |
| 20101300 | TREE PRUNING (1 TO 10 INCH DIAMETER) | EACH | 4 |
| ● 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 1256 |
| ● 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 18 |
| ● 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 18 |
| ● 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 18 |
| ● 25200100 | SODDING | SQ YD | 770 |
| ● 25200110 | SODDING, SALT TOLERANT | SQ YD | 486 |
| 25200200 | SUPPLEMENTAL WATERING | UNIT | 25 |
| 28000510 | INLET FILTERS | EACH | 11 |
| 42001300 | PROTECTIVE COAT | SQ YD | 867 |
| 42400430 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL | SQ FT | 6667 |
| 42400800 | DETECTABLE WARNING | SQ FT | 30 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 27 |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 2837 |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 3 |
| 60207605 | CATCH BASINS, TYPE C, TYPE 8 GRATE | EACH | 1 |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 1 |
| 60604200 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL) | FOOT | 18 |
| 60605400 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL) | FOOT | 9 |
| 67100100 | MOBILIZATION | L. SUM | 1 |
| 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L. SUM | 1 |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L. SUM | 1 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L. SUM | 1 |
| ● 72400500 | RELOCATE SIGN PANEL ASSEMBLY - TYPE A | EACH | 1 |
| ● 72800100 | TELESCOPING STEEL SIGN SUPPORT | FOOT | 15 |
| XX000613 | MODULAR BLOCK RETAINING WALL | SQ FT | 152 |
| XX000810 | CONCRETE PAVERS | SQ FT | 830 |
| ● XX000959 | TRASH RECEPTACLES | EACH | 11 |
| XX003461 | EARTH EXCAVATION, SPECIAL | L. SUM | 1 |
| ● XX003689 | BUS SHELTER | EACH | 11 |
| ● XX005186 | HEMEROCALLIS "STELLA D'ORO" (1 GAL) | EACH | 28 |

● INDICATES SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 12/1/06

DRAWN BY JRR
CHECKED BY JRV