

SCHEDULE OF QUANTITIES

P&E NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
178	03-00287-00-BR	LEE	18	3
STA. 11+75		TO STA. 21+60		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE*

LOCATION	EARTH EXCAVATION (SPECIAL) 20200-410	EXCAVATION ADJUSTED FOR SHRINKAGE 25%	21100-005 TOPSOIL EXCAVATION AND PLACEMENT (4" DEPTH) (Proposed Seeding Area) 3,872 SQ YD	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR Shortage (-) (CU YD)
	CU YD	CU YD	CU YD	CU YD	CU YD
PERU ST. STA. 11+75 TO 21+60	758	568	301	287	281
PROJECT TOTALS	758	568	301	287	281

*NOTE: INCLUDES TOPSOIL EXCAVATION AND PLACEMENT

STATION	UNIT	REMARKS
37' R 19+63	14	2 @ 7"
38' R 19+70	12	
39' R 19+73	9	
45' R 19+76	7	
PROJECT TOTAL	42	

20100110

STATION	CU YD	REMARKS
CONTINGENCY ITEM	100	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	100	

20201200

STATION	ACRE	REMARKS
ENTIRE PROJECT	0.8	DISTURBED AREAS ONLY - SEE XSECTIONS
PROJECT TOTAL	0.80	

25000350

STATION	ACRE	REMARKS
ENTIRE PROJECT	0.8	DISTURBED AREAS ONLY - SEE XSECTIONS
PROJECT TOTAL	0.80	

25001000

STATION	SQ YD	REMARKS
L 19+70 - 19+86	23	SOUTH SIDE OF CULVERT
R 19+82 - 19+97	32	SOUTH SIDE OF CULVERT
L 19+95 - 20+09	38	NORTH SIDE OF CULVERT
R 20+09 - 20+22	39	NORTH SIDE OF CULVERT
PROJECT TOTAL	138	

25100630

STATION	SQ YD	REMARKS
R 11+70	6	
L 11+70	6	
PROJECT TOTAL	12	

28100703

STATION	TON	REMARKS
R 12+45	46	10" (CA6)
L 19+00 - 21+00	349	12" (CA6)
PROJECT TOTAL	395	

35101400

STATION	GALLON	REMARKS
L 14+75 - 21+60	881	0.35 GAL. / S.Y. OVER AGG.
R 14+75 - 21+60	252	.1 GAL. / S.Y. OVER BIT.
ROSENKRANS DRIVE	60	0.35 GAL. / S.Y. OVER AGG.
ROSENKRANS DRIVE	17	.1 GAL. / S.Y. OVER BIT.
BROOKSIDE DRIVE	37	0.35 GAL. / S.Y. OVER AGG.
BROOKSIDE DRIVE	11	.1 GAL. / S.Y. OVER BIT.
PROJECT TOTAL	1,258	

40600100

STATION	TON	REMARKS
L 11+75 - 21+60	4	3 LBS. / S.Y.
PROJECT TOTAL	4	

40600300

STATION	TON	REMARKS
L 11+75 - 21+60	680	4 1/2" COMPLETE
ROSENKRANS DRIVE	46	4 1/2" COMPLETE
BROOKSIDE DRIVE	28	4 1/2" COMPLETE
PROJECT TOTAL	754	

40603080

STATION	TON	REMARKS
L 11+75 - 21+60	300	2"
FER 12+45	14	3"
ROSENKRANS DRIVE	21	2"
BROOKSIDE DRIVE	13	2"
PROJECT TOTAL	350	

40603310

STATION	SQ YD	REMARKS
PEL 12+62	64.1	
PEL 14+52	73.1	
PEL 14+82	58.2	
PER 15+61	37.1	
PEL 16+34.5	64.3	
PEL 16+71.5	54.3	
PEL 18+64.5	35.1	
PEL 18+96	35.1	
PER 20+93	51.1	
PEL 21+10	68.6	
PROJECT TOTAL	541.0	

42300200

STATION	SQ FT	REMARKS
R 11+75 - 12+35	300	
R 12+55 - 14+13	940	
R 14+61 - 15+55	505	
R 15+67 - 17+02	671	
R 17+44.5 - 17+64	173	
L 17+56 - 18+46.5	512	
L 18+05	5	
L 18+60.5 - 18+90	147	
L 19+02 - 20+96	980	
L 21+24 - 22+00	380	
PROJECT TOTAL	4,613	

42400200

STATION	SQ FT	REMARKS
R 17+04	24	
R 17+43	15.5	
R 17+61	17.5	
L 17+61	19	
PROJECT TOTAL	79	

42400800

STATION	FOOT	REMARKS
L 11+82 - 13+84	202	
R 12+46 - 16+86	420	
ROSENKRANS DR.	39	SW CORNER
ROSENKRANS DR.	40	NW CORNER
L 14+72 - 21+60	686	
BROOKSIDE DR.	39	SE CORNER
BROOKSIDE DR.	37	NE CORNER
R 17+64 - 21+60	396	
PROJECT TOTAL	1,861	

44000500

STATION	FOOT	REMARKS
R 30+11 - 20+31	20	
PROJECT TOTAL	20	

550A0430

STATION	FOOT	REMARKS
L 19+84 - 19+86	3	
L 20+11.5 - 20+16.5	7	
PROJECT TOTAL	10	

55100400

STATION	FOOT	REMARKS
L & R 19+86	34	
L & R 20+18.5	33	
PROJECT TOTAL	67	

55100700

STATION	FOOT	REMARKS
R 20+11 - 20+31	20	
PROJECT TOTAL	20	

55101400

STATION	EACH	REMARKS
26.5' L 14+08.75	1	
21.6' L 14+42.50	1	
15.87' R 16+86	1	
22.87' R 17+45	1	
PROJECT TOTAL	4	

55100700

STATION	EACH	REMARKS
L 20+60	1	
R 20+09	1	
PROJECT TOTAL	2	

60242400

STATION	EACH	REMARKS
R 12+76	1	
R 14+27	1	
R 16+32	1	
R 17+47	1	
R 19+26	1	
R 19+75	1	
PROJECT TOTAL	6	

60255500

STATION	EACH	REMARKS
L 14+09	1	
L 14+42	1	
R 16+86	1	
R 17+45	1	
L 19+84	1	
L & R 19+86	2	
L & R 20+18	3	
PROJECT TOTAL	10	

60268300

STATION	EACH	REMARKS
L 16+82	1	
L 18+47	1	
L 20+75	1	
PROJECT TOTAL	3	

60268600

STATION	CU YD	REMARKS
L 11+18.8 - 12+03	2.60	
R 11+18.6 - 12+03	2.60	
PROJECT TOTAL	5.2	

60600095

STATION	FOOT	REMARKS
L 12+03 - 13+84	181	
R 12+03 - 16+86	483	
ROSENKRANS DR.	43.5	SW CORNER
ROSENKRANS DR.	50.5	NW CORNER
L 14+72 - 21+60	658	
BROOKSIDE DR.	39	SE CORNER
BROOKSIDE DR.	39	NE CORNER
R 17+64 - 21+60	396	
PROJECT TOTAL	1,919	

60604400

STATION	TON	REMARKS
CONTINGENCY ITEM	205	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	205	

70005400

SCHEDULES
 PERU STREET OVER BR. OF PAW PAW RUN
 SECTION 03-00287-00-BR
 STA. 19+96 (S.N. 052-6200)
 LEE COUNTY
 WHA # 1231D03