



SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
178 33-00287-00-BR	LEE	10	14
STA. 15+61 TO STA. 16+71.50			
FED. ROAD DIST. NO.	RLNOS	FED. AID PROJECT	

P.E. 925
920
915

16
71.50

919.33
- 3.1%
T.C. 919.58
R/W
STA 16+71.50 (Q ENTR. LT.)
ORIGINAL EL = 919.26
DESIGN EL = 919.53
DESIGN EARTHWORK
FILL AREA = 0.00
CUT AREA = 13.74

925
920
915

16
50

919.56
T.C. 919.81
R/W
STA 16+50
ORIGINAL EL = 919.43
DESIGN EL = 919.56
DESIGN EARTHWORK
FILL AREA = 1.03
CUT AREA = 17.96

925
920
915

16
34.50

919.66
- 2.3%
T.C. 919.91
R/W
STA 16+34.50 (Q ENTR. LT.)
ORIGINAL EL = 919.55
DESIGN EL = 919.66
DESIGN EARTHWORK
FILL AREA = 0.00
CUT AREA = 14.58

HIGH PT.
STA. 16+12.93
919.71

925
920
915

16
00

919.70
T.C. 919.95
R/W
STA 16+00
ORIGINAL EL = 919.53
DESIGN EL = 919.70
DESIGN EARTHWORK
FILL AREA = 1.18
CUT AREA = 12.46

925 P.E.
920
915

15
61

919.44
T.C. 919.69
R/W
STA 15+61 (Q ENTR. RT.)
ORIGINAL EL = 919.29
DESIGN EL = 919.44
DESIGN EARTHWORK
FILL AREA = 0.00
CUT AREA = 17.27