



BITUMINOUS MATERIALS (PRIME COAT)

BELVIDERE ROAD

STA	AREA (SY)	RATE (GAL/SY)	DENSITY (LB/GAL)	NUMBER APPLICATIONS	BIT MATLS PR CT (TONS)
101+36 - 173+74	19,310.60	0.06	8.40	2.00	9.7
177+62 - 351+42	46,537.91	0.06	8.40	2.00	23.5
DRIVES & STREETS	7,704.96	0.06	8.40	1.00	1.9
Total					35.1

AGGREGATE (PRIME COAT)

BELVIDERE ROAD

STA	AREA (SY)	RATE (LB/SY)	NUMBER APPLICATIONS	BIT MATLS PR CT (TONS)
101+36 - 173+74	19,310.60	3.00	2.00	57.9
177+62 - 351+42	46,537.91	3.00	2.00	139.6
Total				197.5

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SY)

BELVIDERE ROAD

STA	O/S	TYPE	BITUM SURF REMOV (SY)
101+36.14	N/A	MAINLINE	100.0
101+61	Rt	P.E.	11.1
102+71	Rt	P.E.	5.6
104+02	Rt	STREET	24.4
104+07	Lt	STREET	28.9
107+25	Lt	P.E.	10.0
108+12	Rt	STREET	17.8
110+16	Lt	STREET	24.4
111+24	Rt	STREET	25.6
127+21	Rt	P.E.	5.6
128+23	Rt	P.E.	6.7
144+80	Rt	P.E.	5.6
148+00	Lt	P.E.	5.6
152+41	Lt	P.E.	10.0
158+72	Rt	STREET	26.7
159+75	Lt	P.E.	11.1
162+16	Lt	P.E.	13.3
164+57	Rt	P.E.	8.9
173+74.40	N/A	MAINLINE	160.0
177+62.41	N/A	MAINLINE	160.0
186+38	Rt	P.E.	4.4
186+44	Lt	STREET	53.3
191+06	Rt	STREET	26.7
194+90	Lt	P.E.	5.6
196+76	Rt	STREET	26.7
200+66	Lt	P.E.	5.6
201+68	Lt	P.E.	21.7
205+25	Lt	P.E.	5.6
207+62	Lt	P.E.	5.6
217+25	Rt	P.E.	6.7

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SY)

BELVIDERE ROAD

STA	O/S	TYPE	BITUM SURF REMOV (SY)
241+73	Lt	P.E.	8.3
248+82	Lt	STREET	41.1
267+92	Rt	STREET	51.1
284+21	Rt	P.E.	6.7
286+97	Lt	P.E.	6.7
287+82	Lt	P.E.	6.7
292+84	Lt	P.E.	6.7
296+51	Rt	P.E.	6.7
297+29	Lt	STREET	28.9
299+40	Rt	P.E.	6.7
301+54	Lt	P.E.	6.7
303+05	Lt	P.E.	6.7
305+17	Lt	P.E.	6.7
306+91	Rt	P.E.	6.7
310+77	Lt	P.E.	6.7
315+25	Lt	P.E.	6.7
324+41	Lt	STREET	26.7
326+95	Rt	P.E.	6.7
329+89	Rt	P.E.	7.8
351+42.13	N/A	MAINLINE	333.3
Total			1,406.7

LEVELING BINDER (MACHINE METHOD), N50

BELVIDERE ROAD

STA	LEV BIND MM N50 (TON)
109+07.79 TO 116+04.67	587.7
123+17.33 TO 130+78.40	0.0
143+74.74 TO 152+44.11	0.0
182+86.99 TO 188+34.03	125.8
230+28.63 TO 239+48.41	0.0
292+86.71 TO 301+62.90	100.8
Total	814.3

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50

BELVIDERE ROAD

STA	HMA BC IL-19.0 N50 (TON)
101+36.14 TO 173+74.40	2,220.7
177+62.41 TO 351+42.13	5,351.9
Total	7,572.6

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50

BELVIDERE ROAD

STA	HMA SC "D" N50 (TON)
101+36.14 TO 173+74.40	1,892.4
177+62.41 TO 351+42.13	4,560.7
Total	6,453.2

TEMPORARY RAMP

BELVIDERE ROAD

STA	O/S	TYPE	TEMPORARY RAMP (SY)
101+36.14	N/A	MAINLINE	10.7
104+02	Rt	STREET	9.8
104+07	Lt	STREET	11.6
108+12	Rt	STREET	7.1
110+16	Lt	STREET	9.8
111+24	Rt	STREET	10.2
158+72	Rt	STREET	10.7
173+74.40	N/A	MAINLINE	21.4
177+62.41	N/A	MAINLINE	21.4
186+44	Lt	STREET	21.3
191+06	Rt	STREET	10.7
196+76	Rt	STREET	10.7
248+82	Lt	STREET	16.4
267+92	Rt	STREET	20.4
297+29	Lt	STREET	11.6
324+41	Lt	STREET	10.7
351+42.13	N/A	MAINLINE	65.3
Total			279.7

INCIDENTAL BITUMINOUS SURFACING (TONS)

BELVIDERE ROAD

STA	O/S	TYPE	INCIDENTAL BIT SURF (TONS)
101+61	Rt	P.E.	15.7
102+71	Rt	P.E.	6.1
104+02	Rt	STREET	12.9
104+07	Lt	STREET	16.3
105+90	Lt	P.E.	7.7
107+25	Lt	P.E.	10.8
108+12	Rt	STREET	11.8
110+16	Lt	STREET	15.3
110+24	Rt	P.E.	7.0
111+24	Rt	STREET	14.7
114+21	Rt	P.E.	7.5
115+70	Rt	P.E.	9.4
115+72	Lt	F.E.	8.6
116+32	Rt	P.E.	8.6
127+11	Lt	F.E.	10.4
127+21	Rt	P.E.	7.8
128+23	Rt	P.E.	7.0
130+66	Lt	P.E.	8.3
131+62	Lt	P.E.	11.1
135+47	Lt	F.E.	7.1
142+58	Rt	P.E.	7.2
143+27	Lt	P.E.	12.9
144+66	Lt	MAILBOX	6.6
144+80	Rt	P.E.	7.2
148+00	Lt	P.E.	10.4
151+15	Rt	F.E.	7.2
152+41	Lt	P.E.	19.7
158+72	Rt	STREET	18.4
158+76	Lt	P.E.	11.8
159+75	Lt	P.E.	10.0
162+16	Lt	P.E.	24.9
164+64	Lt	MAILBOX	7.2
164+57	Rt	P.E.	11.7
166+54	Lt	MAILBOX	7.1
186+38	Rt	P.E.	9.1
186+44	Lt	STREET	25.4
191+06	Rt	STREET	13.6

INCIDENTAL BITUMINOUS SURFACING (TONS)

BELVIDERE ROAD

STA	O/S	TYPE	INCIDENTAL BIT SURF (TONS)
194+90	Lt	P.E.	9.9
196+76	Rt	STREET	14.3
200+66	Lt	P.E.	11.0
201+68	Lt	P.E.	15.3
205+25	Lt	P.E.	12.0
207+62	Lt	P.E.	9.8
211+73	Rt	F.E.	8.6
213+67	Lt	P.E.	10.9
217+25	Rt	P.E.	10.5
224+09	Rt	F.E.	7.2
225+10	Lt	F.E.	7.2
241+73	Lt	P.E.	12.9
241+96	Rt	F.E.	7.2
247+18	Rt	P.E.	7.2
248+82	Lt	STREET	25.4
262+00	Rt	F.E.	7.2
263+42	Lt	F.E.	7.1
267+92	Rt	STREET	26.5
267+93	Lt	P.E.	7.2
275+32	Rt	F.E.	7.2
280+40	Rt	P.E.	13.6
282+80	Lt	P.E.	7.9
282+90	Rt	MAILBOX	6.6
284+21	Rt	P.E.	7.2
285+78	Rt	MAILBOX	6.6
286+97	Lt	P.E.	7.2
287+77	Rt	MAILBOX	6.6
287+82	Lt	P.E.	7.2
292+84	Rt	MAILBOX	6.6
296+51	Rt	P.E.	15.1
296+70	Lt	F.E.	7.2
297+29	Lt	STREET	16.3
299+40	Rt	P.E.	10.1
301+54	Lt	P.E.	7.2
302+89	Rt	MAILBOX	6.6
303+05	Lt	P.E.	7.2
304+99	Rt	MAILBOX	6.6
305+17	Lt	P.E.	7.2
306+88	Rt	MAILBOX	6.6
306+91	Rt	P.E.	7.2
309+75	Lt	F.E.	7.2
310+75	Rt	MAILBOX	6.6
310+77	Lt	P.E.	7.2
315+25	Lt	P.E.	7.2
315+27	Rt	MAILBOX	6.6
316+37	Rt	F.E.	7.2
324+41	Lt	STREET	13.7
326+95	Rt	P.E.	7.3
329+90	Rt	P.E.	10.7
340+29	Lt	F.E.	7.2
Total			893.6

AGGREGATE SHOULDERS, TYPE B

BELVIDERE ROAD

STA	AGGREGATE SHOULDERS, TYPE B (TON)
101+36.14 TO 104+02	51.7
104+02 TO 156+72 (Applegate Road)	2,049.4
156+72 TO 191+06 (Hawthorne Ridge)	1,335.4
191+06 TO 248+82 (Atwood Road)	2,246.2
248+82 TO 267+92 (Swanson Road)	742.8
267+92 TO 297+29 (Brown Road)	1,142.2
297+29 TO 351+42.13 (IL-RTE 173)	2,105.1
Total	9,672.9

K:\Users\perry\My Documents\04-00338-00-RS (Belvidere Road)\PilotSummary_Schedule_Items.dwg, 12/1/2008 11:37:06 AM, 1946
 11/15/2008 10:50:00 AM, 08/11/2008 11:37:06 AM, 11