

SCHEDULE OF QUANTITIES (CONT.)

(FOR ROAD AND STORM SEWER CONSTRUCTION ONLY. FOR WATER MAIN QUANTITIES, SEE SHEET 44)

SECTION #	TOTAL SHEETS	SHEET NO.
06-00447-12-PV	50	4

44000600 SIDEWALK REM (CONT.)		
STA. 16+75 RT	17.6	SQ FT
STA. 17+30 LT	22.0	SQ FT
STA. 17+38 RT	78.0	SQ FT
STA. 17+50 RT	20.4	SQ FT
STA. 17+81 RT	47.0	SQ FT
STA. 17+85 LT	21.1	SQ FT
STA. 18+10 RT	22.0	SQ FT
STA. 18+20 RT	22.6	SQ FT
STA. 18+42 RT	54.0	SQ FT
STA. 18+69 RT	69.5	SQ FT
STA. 18+75 RT	16.0	SQ FT
STA. 18+80 LT	19.0	SQ FT
STA. 18+91 LT	40.0	SQ FT
STA. 18+93 RT	69.5	SQ FT
STA. 19+12 LT	169.0	SQ FT
STA. 19+50 RT	11.6	SQ FT
STA. 19+50 LT	19.2	SQ FT
STA. 19+65 LT	98.0	SQ FT
STA. 19+70 RT	20.0	SQ FT
STA. 19+70 LT	20.0	SQ FT
STA. 20+24 LT	20.0	SQ FT
STA. 20+27 RT	20.0	SQ FT
STA. 20+55 LT	19.8	SQ FT
STA. 20+70 RT	20.0	SQ FT
STA. 21+20 LT	17.6	SQ FT
STA. 21+22 RT	20.3	SQ FT
STA. 21+31 RT	128.5	SQ FT
STA. 21+70 RT	19.4	SQ FT
STA. 21+71 LT	50.5	SQ FT
STA. 21+72 RT	75.0	SQ FT
STA. 21+80 LT	19.5	SQ FT
STA. 22+25 RT	20.0	SQ FT
STA. 22+36 RT	237.5	SQ FT
STA. 23+25 LT	21.5	SQ FT
STA. 23+29 RT	92.5	SQ FT
STA. 23+60 RT	18.0	SQ FT
STA. 24+04 LT	60.0	SQ FT
STA. 24+34 RT	93.0	SQ FT
STA. 24+65 LT	25.3	SQ FT
STA. 24+75 RT	20.4	SQ FT
STA. 24+79 RT	25.0	SQ FT
STA. 25+24 RT	69.5	SQ FT
STA. 25+25 RT	20.5	SQ FT
STA. 25+75 RT	21.0	SQ FT
STA. 25+85 LT	16.0	SQ FT
STA. 26+50 RT	16.8	SQ FT
STA. 26+60 LT	17.5	SQ FT
STA. 27+18 RT	18.0	SQ FT
STA. 27+20 LT	44.5	SQ FT
STA. 27+77 RT	14.0	SQ FT
STA. 27+77 LT	13.6	SQ FT
STA. 28+23 LT	19.3	SQ FT
STA. 28+36 LT	66.5	SQ FT
STA. 28+38 RT	17.0	SQ FT
STA. 28+46 RT	25.0	SQ FT
STA. 28+75 LT	24.7	SQ FT
STA. 29+12 RT	26.3	SQ FT
STA. 29+26 LT	20.0	SQ FT
STA. 29+80 RT	16.0	SQ FT
STA. 29+90 LT	15.2	SQ FT
STA. 30+23 RT	49.5	SQ FT
STA. 30+40 LT	33.0	SQ FT
STA. 30+52 LT	35.0	SQ FT
STA. 30+55 RT	18.0	SQ FT
STA. 30+72 LT	77.0	SQ FT
STA. 30+90 LT	27.2	SQ FT
STA. 31+12 RT	17.6	SQ FT
STA. 31+41 LT	41.0	SQ FT
STA. 31+48 LT	14.0	SQ FT
STA. 31+73 RT	15.6	SQ FT
STA. 31+90 LT	15.5	SQ FT
STA. 32+15 RT	15.6	SQ FT
STA. 32+48 LT	30.4	SQ FT
STA. 32+95 RT	20.0	SQ FT
STA. 32+95 LT	15.6	SQ FT
STA. 33+21 RT	65.0	SQ FT
STA. 33+45 RT	16.8	SQ FT
STA. 33+55 LT	26.0	SQ FT
STA. 33+97 RT	51.5	SQ FT
STA. 34+25 LT	12.0	SQ FT
STA. 34+30 RT	17.6	SQ FT
STA. 34+85 LT	28.4	SQ FT
STA. 34+95 RT	22.0	SQ FT
STA. 35+37 LT	12.8	SQ FT
STA. 35+50 RT	16.0	SQ FT
STA. 35+78 RT	40.0	SQ FT
TOTAL	5,316.0	SQ FT

44004400 PAVEMENT REM SPL		
STA. 10+00 - 35+35	9,295.0	SQ YD
STA. 13+32 - 13+79 LT	6.8	SQ YD
STA. 15+20 - 15+66 RT	35.6	SQ YD
STA. 19+80 - 20+20 LT	22.0	SQ YD
STA. 19+83 - 20+25 RT	20.3	SQ YD
TOTAL	9,380.0	SQ YD

55080050 STORM SEW CL B 1 12		
STA. 12+55 RT	23.6	FT
STA. 12+55 LT	7.8	FT
STA. 12+56 - 13+52 LT	95.8	FT
STA. 13+10 LT	20.0	FT
STA. 13+32 - 13+40 LT	7.8	FT
STA. 13+37 - 13+51 RT	13.6	FT
STA. 13+41 - 13+54 LT	17.4	FT
STA. 13+53 RT	24.2	FT
STA. 13+54 - 13+71 LT	20.5	FT
STA. 13+72 - 13+82 LT	10.4	FT
STA. 14+86 RT	23.6	FT
STA. 14+86 LT	8.0	FT
STA. 14+87 - 15+20 RT	34.3	FT
STA. 15+43 - 15+49 LT	9.2	FT
STA. 15+43 - 15+55 LT	11.4	FT
STA. 15+49 - 15+60 RT	13.9	FT
STA. 15+63 - 15+77 RT	16.8	FT
STA. 22+38 LT	8.1	FT
STA. 22+38 RT	23.3	FT
STA. 26+31 LT	9.7	FT
STA. 26+31 RT	21.1	FT
STA. 28+30 LT	10.1	FT
STA. 28+30 RT	21.2	FT
STA. 30+11 - 31+33 LT	120.2	FT
STA. 31+33 RT	22.0	FT
STA. 31+33 LT	8.9	FT
STA. 34+65 RT	19.7	FT
STA. 34+65 LT	11.3	FT
STA. 34+66 - 36+03 LT	136.5	FT
TOTAL	770.0	FT

55080090 STORM SEW CL B 1 18		
STA. 24+11 - 26+30 LT	218.6	FT
TOTAL	219.0	FT

55080120 STORM SEW CL B 1 24		
STA. 13+56 - 14+84 LT	127.8	FT
STA. 14+88 - 15+47 LT	60.2	FT
TOTAL	188.0	FT

60218400 MAN TA 4 DIA TIF CL		
STA. 12+55 LT	1.0	EACH
STA. 22+38 LT	1.0	EACH
STA. 26+31 LT	1.0	EACH
STA. 28+30 LT	1.0	EACH
STA. 31+34 LT	1.0	EACH
STA. 34+65 LT	1.0	EACH
TOTAL	6.0	EACH

60221100 MAN TA 5 DIA TIF CL		
STA. 14+86 LT	1.0	EACH
TOTAL	1.0	EACH

60223800 MAN TA 6 DIA TIF CL		
STA. 13+54 LT	1.0	EACH
TOTAL	1.0	EACH

60235700 INLETS TA T3F&G		
STA. 12+55 R&L	2.0	EACH
STA. 13+11 LT	1.0	EACH
STA. 13+32 LT	1.0	EACH
STA. 13+37 RT	1.0	EACH
STA. 13+83 LT	1.0	EACH
STA. 14+86 LT	1.0	EACH
STA. 15+22 RT	1.0	EACH
STA. 15+55 LT	1.0	EACH
STA. 15+79 RT	1.0	EACH
STA. 19+88 RT	1.0	EACH
STA. 20+14 LT	1.0	EACH
STA. 20+21 RT	1.0	EACH
STA. 22+38 R&L	2.0	EACH
STA. 24+19 R&L	2.0	EACH
STA. 26+31 R&L	2.0	EACH
STA. 30+17 R&L	2.0	EACH
STA. 31+34 R&L	2.0	EACH
STA. 34+65 R&L	2.0	EACH
TOTAL	25.0	EACH

60240220 INLETS TB T3F&G		
STA. 13+41 LT	1.0	EACH
STA. 13+55 RT	1.0	EACH
STA. 13+72 LT	1.0	EACH
STA. 14+86 RT	1.0	EACH
STA. 15+43 LT	1.0	EACH
STA. 15+61 RT	1.0	EACH
STA. 19+76 LT	1.0	EACH
TOTAL	7.0	EACH

60241800 INLETS TG-1		
STA. 28+30 R&L	2.0	EACH
TOTAL	2.0	EACH

60300305 FR & LIDS ADJUST		
STA. 15+50 RT	1.0	EACH
TOTAL	1.0	EACH

60300310 FR & LIDS ADJUST SPL		
NOTE: GSD TO PROVIDE CASTINGS		
STA. 15+51 LT (REPLACE)	1.0	EACH
STA. 15+53 CL (RE-USE)	1.0	EACH
STA. 19+91 LT (REPLACE)	1.0	EACH
STA. 19+96 CL (REPLACE)	1.0	EACH
STA. 24+10 LT (REPLACE)	1.0	EACH
STA. 24+18 CL (RE-USE)	1.0	EACH
STA. 27+15 LT (REPLACE)	1.0	EACH
STA. 30+11 LT (REPLACE)	1.0	EACH
TOTAL	8.0	EACH

60500040 REMOV MANHOLES		
STA. 13+54 LT	1.0	EACH
TOTAL	1.0	EACH

60500060 SDRM INLETS		
STA. 13+41 LT	1.0	EACH
STA. 13+55 RT	1.0	EACH
STA. 13+72 LT	1.0	EACH
STA. 15+62 RT	1.0	EACH
STA. 15+42 LT	1.0	EACH
STA. 19+87 RT	1.0	EACH
STA. 19+77 LT	1.0	EACH
STA. 20+14 LT	1.0	EACH
STA. 20+23 RT	1.0	EACH
STA. 24+19 RT	1.0	EACH
STA. 24+19 LT	1.0	EACH
STA. 30+18 RT	1.0	EACH
STA. 30+18 LT	1.0	EACH
TOTAL	13.0	EACH

67100100 MOBILIZATION		
ENTIRE PROJECT	1.0	L.SUM
TOTAL	1.0	L.SUM

60604400 COMB. CC&G TB6.18		
STA. 10+00 - 15+27 RT	536.8	FT
STA. 10+00 - 13+45 LT	352.4	FT
STA. 13+65 - 19+85 LT	630.8	FT
STA. 15+58 - 19+92 RT	446.2	FT
STA. 20+07 - 35+87 LT	1,583.2	FT
STA. 20+16 - 35+90 RT	1,578.0	FT
TOTAL	5,127.0	FT

70101700 TRAFFIC CONTROL & PROTECTION		
ENTIRE PROJECT	1.0	L.SUM
TOTAL	1.0	L.SUM

70300100 SHORT TERM PAVT MKING		
STA. 9+86	24.9	FT
STA. 9+86 - 11+00	228.0	FT
STA. 34+71 - 35+85	228.0	FT
STA. 35+85	23.8	FT
TOTAL	505.0	FT

70301000 WRK ZONE PAVT MK REM		
STA. 9+86	8.3	SQ FT
STA. 9+86 - 11+00	76.0	SQ FT
STA. 34+71 - 35+85	76.0	SQ FT
STA. 35+85	7.9	SQ FT
TOTAL	168.0	SQ FT

78000100 THPL PVT MK LTR & SYM		
STA. 35+50 CL	15.6	SQ FT
TOTAL	16.0	SQ FT

78000200 THPL PVT MK LINE 4		
STA. 9+86 - 10+00	28.0	FT
STA. 35+35 - 35+85	100.0	FT
TOTAL	128.0	FT

78000400 THPL PVT MK LINE 6		
STA. 9+75	51.0	FT
STA. 9+81	41.8	FT
STA. 35+89	36.4	FT
STA. 35+96	55.5	FT
TOTAL	185.0	FT

78000500 THPL PVT MK LINE 8		
STA. 9+86 - 10+00	14.0	FT
STA. 35+35 - 35+85	50.0	FT
TOTAL	64.0	FT

78000600 THPL PVT MK LINE 12		
STA. 9+86	24.5	FT
STA. 35+85	23.9	FT
TOTAL	48.0	FT

78001100 PT PVT MK LTRS & SYMB		
STA. 10+15 CL	15.6	SQ FT
STA. 10+73 CL	15.6	SQ FT
STA. 34+95 CL	15.6	SQ FT
TOTAL	47.0	SQ FT

78001110 PAINT PVT MK LINE 4		
STA. 10+00 - 12+29	691.2	FT
STA. 33+40 - 35+85	606.6	FT
TOTAL	1,298.0	FT

78001140 PAINT PVT MK LINE 8		
STA. 10+00 - 10+87	87.0	FT
STA. 34+84 - 35+34	50.0	FT
TOTAL	137.0	FT

88600100 DET LOOP T1		
STA. 35+37 - 35+87 CL	174.0	FT
STA. 35+37 - 35+87 RT	174.0	FT
TOTAL	348.0	FT

Z0013798 CONSTRUCTION LAYOUT		
ENTIRE PROJECT	1.0	L.SUM
TOTAL	1.0	L.SUM

Z0076600 TRAINEES		
ENTIRE PROJECT	500.0	HOURS
TOTAL	500.0	HOURS

K1005863 TREE ROOT PRUNING (CONT.)		
STA. 29+05 RT	1.0	EACH
STA. 33+30 RT	1.0	EACH
TOTAL	11.0	EACH

K1005881 TREE TRUNK PROTECTION		
STA. 13+08 LT	1.0	EACH
STA. 25+30 RT	1.0	EACH
TOTAL	2.0	EACH

XX006791 BRICK DRIVEWAY PAVT		
STA. 10+92 RT	15.3	SQ YD
STA. 11+68 RT	6.9	SQ YD
STA. 12+10 LT	6.7	SQ YD
STA. 16+95 LT	15.0	SQ YD
STA. 18+27 LT	14.3	SQ YD
STA. 29+97 LT	5.6	SQ YD
STA. 31+09 LT	19.8	