

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
473	05-00046-12-RP	McLEAN	32	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS' FED. AID PROJECT		
CONTRACT NO. 91370				

PIPE UNDERDRAINS		
LOCATION	PIPE UNDERDRAINS 6"	CONCRETE HEADWALL FOR PIPE DRAINS
	FOOT	EACH
WBL STA 40+33 LT.	25	1
WBL STA 44+50 LT.	33	1
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51		
WBL STA 55+85 LT.	29	1
WBL STA 62+50 LT.	24	1
EBL STA 40+33 RT.	25	1
EBL STA 44+50 RT.	28	1
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51		
EBL STA 55+94 RT.	51	1
EBL STA 62+48 RT.	25	1
TOTAL	240	8

PIPE UNDERDRAINS 6"	
LOCATION	FOOT
WBL STA 36+74.14 TO STA 42+36	562
WBL STA 44+50 TO STA 48+66.95	417
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 55+85	453
WBL STA 57+13 TO STA 62+50	537
EBL STA 36+74.14 TO STA 42.76	602
EBL STA 44+50 TO STA 48+66.95	417
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 55+94	461
EBL STA 57+67 TO STA 62+48	481
TOTAL	3930

GEOTECHNICAL FABRIC FOR FRENCH DRAINS	
LOCATION	SO.FT.
STA 40+25	88
STA 44+25	100
STA 55+50	95
STA 61+00	92
STA 63+90	60
TOTAL	435

PIPE UNDERDRAINS, 10"		
LOCATION	PIPE UNDERDRAINS 10"	END SECTIONS, 10"
	FOOT	EACH
STA 40+25 - 56' LT TO 57' RT	108	2
STA 44+25 - 63' LT TO 60' RT	124	2
STA 55+50 - 66' LT TO 50' RT	117	2
STA 61+00 - 53' LT TO 59' RT	113	2
STA 63+90 - 35' LT TO 38' RT	73	2
TOTAL	535	10

MANHOLES TO BE ADJUSTED	
LOCATION	EACH
STA 51+50/30' LT.	1
STA 51+32.5/30' RT.	1
TOTAL	2

CONCRETE MEDIAN SURFACE, 4"	
LOCATION	SO. FT.
STA +81 TO STA 42+25	3440
STA +25 TO STA 43+33	1728
STA 43+33 TO STA 43+82.65	497
STA 44+42.81 TO STA 46+59.81	868
STA 46+59.81 TO STA 48+66.95	2072
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
STA 51+32.51 TO STA 53+39.58	2071
STA 53+39.58 TO STA 53+56.58	868
STA 56+17.03 TO STA 56+65.93	489
STA 56+65.93 TO STA 57+72	1697
STA 57+72 TO STA 61+19	3470
TOTAL	17200

CORRUGATED MEDIAN	
LOCATION	SO.FT.
STA 37+72 TO STA 38+81	491
STA 38+81 TO STA 39+00	39
STA 61+00 TO STA 61+19	39
STA 61+19 TO STA 62+28	491
TOTAL	1060

GUARDRAIL TABLE			
LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1
	FOOT	FOOT	EACH
NE QUADRANT	87	112.5	1
NW QUADRANT	101		
SE QUADRANT	75		
SW QUADRANT	87	112.5	1
TOTAL	350	225	2

PERMANENT SURVEY MARKERS, TYPE 1	
LOCATION	EACH
P.O.T. STA 48+00	1
P.O.T. STA 52+00	1
TOTAL	2

TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH
EBL 42+20/RT.	1
EBL 44+10/RT.	1
EBL 56+00/RT.	1
EBL 56+90/RT.	1
WBL 43+05/LT.	1
WBL 43+90/LT.	1
WBL 56+00/LT.	1
WBL 57+50/LT.	1
TOTAL	8

PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	
LOCATION	SO.FT.
WBL LTL STA 44+62 LEFT TURN ARROW	15.6
WBL LTL STA 45+54 LEFT TURN ARROW	15.6
WBL LTL STA 46+45 LEFT TURN ARROW	15.6
EBL LTL STA 53+65 LEFT TURN ARROW	15.6
EBL LTL STA 54+52 LEFT TURN ARROW	15.6
EBL LTL STA 55+38 LEFT TURN ARROW	15.6
TOTAL	93.6

PAINT PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
WBL STA 36+74.14 TO STA 42+36	562
WBL STA 44+12 TO STA 48+66.95	456
WBL STA 51+32.51 TO STA 55+85	453
WBL STA 57+13 TO STA 63+99.57	688
EBL STA 36+74.14 TO STA 42+76	602
EBL STA 44+17 TO STA 48+66.95	451
EBL STA 51+32.51 TO STA 55+94	462
EBL STA 57+67 TO STA 62+48	482
CENTERLINE STA 36+74.14 TO STA 38+83	210
CENTERLINE STA 36+74.14 TO STA 39+00	225
CENTERLINE STA 61+00 TO STA 63+99.57	300
CENTERLINE STA 61+17 TO STA 63+99.57	284
TOTAL	5175

PAINT PAVEMENT MARKING-LINE 24"	
LOCATION	FOOT
WBL I-55 SBL RAMP EXIT STA 43+30	58
EBL I-55 NBL RAMP EXIT STA 56+74	62
TOTAL	120

PC CONCRETE PAVEMENT 9" (SPECIAL)	
LOCATION	SO.YD.
WBL STA 36+74.14 TO STA 48+66.95	1856
WBL STA 43+32.59 TO STA 43+79.65	32
WBL STA 43+79.65 TO STA 46+59.81	374
WBL STA 46+59.81 TO STA 48+66.95	138
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
WBL STA 51+32.51 TO STA 61+18	1533
WBL STA 61+18 TO STA 62+28	177
WBL STA 62+28 TO STA 63+99.57	277
EBL STA 36+74.14 TO STA 37+72	158
EBL STA 37+72 TO STA 38+81	176
EBL STA 38+81 TO STA 41+00	341
EBL STA 41+00 TO STA 48+66.95	1193
EBL STA 43+82.65 TO STA 44+42.61	40
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
EBL STA 51+32.51 TO STA 63+99.57	1971
EBL STA 51+32.51 TO STA 53+39.58	138
EBL STA 53+39.58 TO STA 56+20.03	374
EBL STA 56+20.03 TO STA 56+65.93	31
EBL STA 53+56.58 TO STA 56+18.03	41
TOTAL	8850

COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.06	
STATION TO STATION	FOOT
STA 38+40 TO STA 43+82.65	1005
STA 44+41.81 TO STA 48+66.95	850
BRIDGE OMISSION STA 48+66.95 TO STA 51+32.51	
STA 51+32.51 TO STA 55+57.58	850
STA 56+17.03 TO STA 61+50	1005
TOTAL	3710

McLEAN COUNTY, ILLINOIS
MFT SECTION 05-00046-12-RP

SCHEDULE OF QUANTITIES

DRAWN BY JJ	 3700 McGraw Drive Bloomington, Illinois 61706 309.888-8436 / fax 309.888-1071	FILE NO. 24-7687
DATE 12/06/06		BOOK NO. 2416
CHECKED BY RGD		SHEET NO. 6 OF 32