

CONTRACT NO. 95487

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	134
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	41938
40300500	COVER COAT AGGREGATE	TON	1047
40300600	SEAL COAT AGGREGATE	TON	1047
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	688
40600990	TEMPORARY RAMP	SQ YD	196
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4333
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
XX806187	BITUMINOUS MATERIALS (ROAD MIX)	TON	18690

* - SPECIAL PROVISIONS REQUIRED

ALIGNMENT COORDINATE TABLE

NORTHING	EASTING	ID	STATION
59148.23973	4467.86053	POT	210+00.000
58741.33729	4508.025875	PI	214+08.880
56606.26371	4721.810508	PI	235+54.630
52362.72299	5147.713116	PI	278+19.490
50132.77668	5132.238494	PI	300+49.392
49735.39872	5086.776917	PI	304+49.148
46545.6989	5085.701492	PI	336+38.731
46545.6989	5085.701492	PI	336+38.731
44545.94163	5064.509286	PI	356+38.601
43882.79325	5063.04341	PI	363+01.751
43152.2233	5062.792136	PI	370+32.321
39738.63185	5074.046815	PI	404+45.931
38591.35297	5075.649035	PI	415+93.211
38184.5647	5074.4619	POT	420+00.001
37402.64	5072.18	PI	427+78.656
36822.12	4802.3502	PI	434+12.367
35834.34	4795.48	PI	443+96.990
33291.58	4766.024	PI	469+39.921
31354.98	4761.94	PI	488+76.525
29630.89	4763.7402	PI	505+96.264
29044.1701	5065.9602	PI	512+47.638
27972.294	5070.752	PI	523+15.268
26849.24	5068.81	PI	534+38.324

GENERAL NOTES

- ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE STATE OF ILLINOIS "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007," THESE PLANS AND THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS.
- ROAD SHALL REMAIN OPEN TO TRAFFIC AT ALL TIMES.
- THE ELEVATION SHOWN ON THE PLANS ARE ON AN ASSUMED DATUM AND ARE NOT ON U.S.G.S. DATUM.
- WHERE SECTIONS OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER, AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
- THE LOCATIONS OF EXISTING GAS MAINS, ELECTRIC POWER LINES, TELEPHONE LINES AND OTHER UTILITIES AS SHOWN ON THE PLANS ARE BASED ON CAREFUL FIELD INVESTIGATION AND THE BEST INFORMATION AVAILABLE, BUT THE LOCATIONS ARE NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THEIR EXACT LOCATION FROM THE INDIVIDUAL UTILITY COMPANIES AND BY FIELD INSPECTION.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING THE PLAN QUANTITIES

AGGREGATE SURFACE COURSE, TYPE B	2.05 TON/CU.YD.
BITUMINOUS MATERIALS (ROAD MIX)	112 LBS/SQ.YD./INCH THICKNESS
BITUMINOUS MATERIALS (COVER COAT)	0.25 GAL/SQ.YD.
BITUMINOUS MATERIALS (SEAL COAT)	0.25 GAL/SQ.YD.
COVER COAT AGGREGATE	25 LBS/SQ.YD.
SEAL COAT AGGREGATE	25 LBS/SQ.YD.
AGGREGATE SHOULDERS, TYPE B	2.05 TON/CU.YD.

HAMPTON, LENZINI & RENWICK, INC.
CIVIL & STRUCTURAL ENGINEERS

HLR

3085 STEVENSON DRIVE, SUITE 201
SPRINGFIELD, ILLINOIS 62703
(217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 03-23-0007-1 DATE: 09/08/06
DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: W.J.S.

**SUMMARY OF QUANTITIES
AND GENERAL NOTES**
SECTION 08-00262-00-RS
F.A.S. 696
CLARK COUNTY