CONTRACT NO. 98944

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
132	(42XII-3	SALINE	46	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE J000-2A UNIT	URBAN TOTAL QUANTITIES 80% FED 20% STATE
54248510	CONCRETE COLLAR	CU YD	0.24
550B2320	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1, 12"	FOOT	46
550B2330	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1, 15"	FOOT	111
△1 550B2340	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1, 18"	FOOT	100
550B2350	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1, 21"	FOOT	150
550B2360	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1, 24"	FOOT	320
55100500	STORM SEWER REMOVAL, 12"	FOOT	143
55100700	STORM SEWER REMOVAL, 15"	FOOT	414
55100900	STORM SEWER REMOVAL, 18"	FOOT	180
60229200	MANHOLES SPECIAL, TYPE 3	EACH	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1
60243500	INLETS, SPECIAL, TYPE 3, 6'	EACH	13
60255500	MANHOLE TO BE ADJUSTED	EACH	2
60500040	REMOVING MANHOLES	EACH	1
60500050	REMOVING CATCH BASINS	EACH	5
60500060	REMOVING INLET	EACH	6
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1677
* 66800200	NON-SPECIAL WASTE DISPOSAL	CU YD	172
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70102622	TRAFFIC CONTROL AND PROTECTION STANDARD 701502	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2088
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	106
70300220	TEMPORARY PAVEMENT MARKING LINE, 4"	FOOT	3834
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	696
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	106
* 78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4"	FOOT	3834
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	75
78300505	PAINT PAVEMENT MARKING REMOVAL	FOOT	110
X0325151	REMOVE EXISTING LIGHT POLE	EACH	6
X0322939	RELOCATE EXISTING FLARED END SECTION	EACH	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1

* SPECIALTY ITEMS

△1 REV. 3-2-07

PLOT DATE = 12/19/2006
FILE NAME = c:\pw_pwin\d98944\d98944sch.sht
PLOT SCALE = 50.0000 ' / IN.
USER NAME = rosasjp