CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

			COUNTY:	WILLIAMSON									
			LOCATION:	URBAN									
			ROUTE:	F.A.I. 57						FAU 9629 (OLD IL 13)			
			FUNDING:	90% FEDERAL/ 10 % STATE - ACIM						90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY
			WORK TYPE:	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
				STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB I57 RAMPS ACIM	VA & NB I57 RAMPS	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
			CONSTRUCTION TYPE CODE:	I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
	CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY									
	72000100	SIGN PANEL - TYPE 1	SQ FT	18.0								18.0	
***	72000300	SIGN PANEL - TYPE 3	SQ FT	2,121.1	1,695.8							425.3	
■	72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	12,779.5	9,568.3							3,211.2	
	73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	80.0	80.0								
	73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	30.0	30.0								
	73400100	CONCRETE FOUNDATIONS	CU YD	17.2	17.2								
	73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.7	21.7								
*	73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.0	1.0								
	73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.0	1.0								
	73700200	REMOVE CONCRETE FOUNDATION-GROUND MOUNT	EACH	34.0	26.0							8.0	
	73700300	REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	3.0	3.0								
	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	421.0									421.0
	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,113.0	7,122.0								10,991.0
	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	478.0									478.0
	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	424.0	424.0								
	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	231.0									231.0
	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	242.0									242.0
	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	23,697.0	22,917.0								780.0
	78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	2,707.0	2,707.0								
	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	560.0	560.0								
*	78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS & SYMBOLS	SQ FT	178.0	178.0								
*	78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	6,048.0	6,048.0								48.0
*	78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	48.0									
*	78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	399.0	399.0								15.0
*	78008370	POLYUREA PAVEMENT MARKING TYPE II - LINE 24"	FOOT	131.0	116.0								
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1425	1249								176.0
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	92.0	92.0								
*	78200520	BARRIER WALL MARKERS, TYPE B	EACH	268.0	230.0		23.0	10.0				5.0	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6.0	6.0								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	35,477	34,961								516.0
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,204	1,124								80.0
*	80300100	LOCATING UNDERGROUND CABLE	FOOT	435.0					1.0			435.0	
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1.0						1.0	1.0		
*	80501000	SERVICE INSTALLATION (SPECIAL)	EACH	2.0									
*	81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	593.0						593.0			
*	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	557.0							557.0		
*	81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	287.0						218.0	69.0		
*	81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	325.0							325.0		
*	81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	58.0						58.0			
*	81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	152.0						30.0	122.0		

*** 100% STATE FUNDING FOR 625.5 SQ FT; 90% FED/10% STATE - Y002-1E FUNDING FOR 1495.6 SQ FT; SEE SCHEDULE FOR LOCATIONS
■ SFTY-3C

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

10 OF 12

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/14/2006
FILE NAME = c:\pwworking\d90\d92682\sld13\sld13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krentje