CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BITUMINOUS PAVEMENT

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90	BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4"	STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
	TON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
FAI 57													
STAGE 1	0.0	0.0	466.0	2,196.0	0.0	0.0	0.0	3,479.0	0.0	56.0	1,296.0	0.0	0.0
STAGE 1A	0.0	0.0	1,187.0	5,442.0	0.0	0.0	0.0	9,717.0	0.0	0.0	3,240.0	0.0	0.0
STAGE 2	0.0	0.0	320.0	1,487.0	0.0	0.0	0.0	2,540.0	0.0	0.0	819.0	0.0	0.0
STAGE 3	0.0	220.0	1,084.0	5,262.0	0.0	0.0	0.0	9,416.0	0.0	192.0	2,929.0	0.0	0.0
STAGE 4	0.0	0.0	1,975.0	7,855.0	0.0	0.0	1,523.0	10,969.0	1,640.0	251.0	3,975.0	0.0	0.0
STAGE 5	0.0	0.0	0.0	630.0	2,283.0	2,375.0	0.0	501.0	0.0	727.0	729.0	0.0	0.0
STAGE 6	0.0	0.0	95.0	409.0	3,048.0	2,476.0	0.0	44.0	82.0	772.0	1,739.0	0.0	0.0
STAGE 7	0.0	0.0	3,411.0	4,649.0	0.0	0.0	7,842.0	760.0	0.0	0.0	4,717.0	0.0	0.0
STAGE 7A	0.0	0.0	907.0	983.0	0.0	0.0	0.0	0.0	0.0	0.0	957.0	0.0	0.0
STAGE 7B	0.0	96.0	739.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
STAGE 8	0.0	2,889.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3,103.0	51.7	2,362.0
FAI 57 PROJECT TOTAL	**0.0**	**3,205.0**	**10,184.0**	**28,913.0**	**5,331.0**	**4,851.0**	**9,365.0**	**37,426.0**	**1,722.0**	**1,998.0**	**23,504.0**	**51.7**	**2,362.0**

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\pw_pw01\k0802\old13\old13sch.m52
PLOT SCALE = 50.000 / IN
USER NAME = kwang