CONTRACT NO. 98950

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| * | ** | WILLIAMSON | 917 | 31 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

# INLETS

| LOCATION | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 | DRAINAGE STRUCTURES TY 1 WITH TWO TYPE 20 FRAMES AND GRATES | INLETS, TYPE A, TYPE 8 GRATE | INLETS, TYPE A, TYPE 20 FRAME AND GRATE | INLETS, TYPE A, SPECIAL, TYPE 1 FRAME, OPEN LID | INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID | INLETS, TYPE B, TYPE 6 FRAME AND GRATE | INLETS, TYPE B, TYPE 8 GRATE | INLETS, SPECIAL, TYPE 3, 5' | INLETS, SPECIAL, TYPE 3, 6' | INLETS TO BE ADJUSTED |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH |
| FAU 9629 (OLD IL 13) CONT. | | | | | | | | | | | |
| RT STA 774+53 | | | | | | 1 | | | | | |
| RT STA 775+10 | | | | | | | | | 1 | | |
| RT STA 775+60 | | | | | | | | | | 1 | |
| RT STA 776+25 | | | | | | | | | 1 | | |
| RT STA 777+20 | | | | | | | | | 1 | | |
| RT STA 777+76 | | | | | | | | | | 1 | |
| LT STA 778+00 | | | | | | | | | | | 1 |
| RT STA 778+00 | | | | | | | | | | 1 | |
| RT STA 779+25 | | | | | | | | | 1 | | |
| RT STA 780+50 | | | | | | | | | 1 | | |
| RT STA 781+69 | | | | | | | | | 1 | | |
| RT STA 782+12 | | | | | | | | | 1 | | |
| LT STA 782+25 | | | | | | | | | | | 1 |
| RT STA 782+25 | | | | | | | | | 1 | | |
| LT STA 783+65 | | | | | | | | | | | 1 |
| RT STA 783+96 | | | | | | | | | 1 | | |
| CRISP DRIVE | | | | | | | | | | | |
| LT STA 11+00 | | | 1 | | | | | | | | |
| FAU 9629 (OLD IL 13) PROJECT TOTALS | 1 | 0 | 1 | 0 | 2 | 1 | 0 | 1 | 12 | 6 | 3 |
| SCHEDULE PROJECT SUB-TOTALS | 3 | 20 | 2 | 3 | 2 | 1 | 4 | 1 | 12 | 6 | 3 |
| PROJECT TOTALS | 3 | 20 | 2 | 3 | 2 | 1 | 4 | 1 | 12 | 6 | 3 |



| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE**

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/1/2006
FILE NAME = c:\pmcjobs\u92692\old13schd32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = Kevin2_P