CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	33
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

DRAINAGE REMOVAL

LOCATION STATION	PAVED DITCH REMOVAL	CONCRETE HEADWALL REMOVAL		PIPE CULVERT REMOVAL			REMOVING INLETS	FILLING MANHOLES	STORM SEWER REMOVAL						TRENCH BACKFILL	CONCRETE REMOVAL	CLASS B PATCHES, TYPE IV, 10 INCH
		INFO. ONLY		INFORMATION ONLY					12"	15"	18"	24"	30"	48"			
	FOOT	REMOVAL (CU YDS)	EACH	CULVERT SIZE (INCH)	CULVERT TYPE	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD	CU YD	SQ YD
FAI 57																	
NORTHBOUND																	
RT STA 1508+64		6.5	1	48	RCCP	6											
RT STA 1514+59		11.2	1	72	RCCP	6											
STA 1518+61.5							1										
RT STA 1537+62		3.7	1	36	RCCP	4											
RT STA 1545+16		3.7	1	36	RCCP	6											
SOUTHBOUND																	
RT STA 1505+17.5																3.0	
RT STA 1507+14		6.5	1	48	RCCP	6											
RT STA 1513+58		11.2	1	72	RCCP	6											
RT STA 1518+01												52					
RT STA 1535+97				12	CMP	33	1										
RT STA 1539+61		3.7	1	36	RCCP	7											
RT STA 1546+74		3.7	1	36	RCCP	7											
RT STA 1530+34 TO STA 1531+06	72																
RAMP E																	
STA. 1+80.6				24	RCCP	6	1										
RAMP EE																	
RT STA 11+71		1.0	1	30	RCCP	5											
RT STA 18+45		0.2	1	24	RCCP	60	1										
RAMP F																	
STA. 13+90.0				24	RCCP	73	1										
STA. 14+40.0							1										
RAMP FF																	
RT STA. 2+29		0.2	1	24	RCCP	56	1										
RT STA. 5+12		1.4	1	36	RCCP	5											
FAI 57 PROJECT TOTALS	72		12			286	7	0	0	0	0	52	0	0	0.0	3.0	0.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo