

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	59
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

CONCRETE BARRIER

LOCATION STATION TO STATION	CONCRETE BARRIER, DOUBLE FACE 42 INCH HEIGHT	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	PROTECTIVE COAT	REMARKS
	FOOT	FOOT	FOOT	SQ YD	
FAI 57					
PRE-STAGE 1					
NORTHBOUND					
LT STA 1489+62 TO STA 1493+37		375.0			
SOUTHBOUND					
RT STA 1488+53 TO STA 1492+16		362.5			
PRE-STAGE 2					
NORTHBOUND					
RT STA 1489+68 TO STA 1493+06			337.5		RELOCATE FROM PRESTAGE 1
RT STA 1493+06 TO STA 1493+68		62.5			
SOUTHBOUND					
LT STA 1488+20 TO STA 1492+20			400.0		RELOCATE FROM PRESTAGE 1
PRE-STAGE 3					
SOUTHBOUND					
RT STA 1526+52 TO STA 1530+77			425.0		RELOCATE FROM PRESTAGE 2
PRE-STAGE 4					
SOUTHBOUND					
RT STA 1528+14 TO STA 1530+77			262.5		RELOCATE FROM PRESTAGE 3
STAGE 1A	0.0	8,575.0	800.0	0.0	
STAGE 2	0.0	0.0	1,600.0	0.0	
STAGE 3	0.0	0.0	4,537.5	0.0	
STAGE 4	0.0	0.0	5,987.5	0.0	
STAGE 5	0.0	0.0	738.0	0.0	
STAGE 6	0.0	0.0	240.0	0.0	
STAGE 7	2,406.0	0.0	6,675.0	2,810.0	
STAGE 7C	710.0	0.0	1,901.0	993.0	
STAGE 8	0.0	0.0	88.0	0.0	
FAI 57 PROJECT TOTALS	3,116.0	9,375.0	23,992.0	3,803.0	
OLD IL 13					
LT STA 765+17.5 TO STA 768+62.5		375.0			
FAU 9629 (OLD IL 13) PROJECT TOTALS	0.0	375.0	0.0	0.0	
SCHEDULE PROJECT SUB-TOTALS	3,116.0	9,750.0	23,992.0	3,803.0	
FROM CONCRETE CURB & GUTTER SCHEDULE				2,415.0	
FROM CONCRETE PAVEMENT SCHEDULE				7,898.0	
FROM SIDEWALK SCHEDULE				1,188.0	
PROJECT TOTALS	3,116.0	9,750.0	23,992.0	15,304.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY JCK
CHECKED BY _____

PLOT DATE = 1/16/2007
 FILE NAME = c:\pwork\mva\022802\old\03\old\03shch32
 USER NAME = jck / IN