CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	167
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-21VB-2, (X1-6)HBK-2

PIPE UNDERDRAINS - FAI 57 STAGE 1A

LOCATION STATION TO STATION	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL) *SEE NOTE*	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	PIPE UNDERDRAIN REMOVAL	COMMENTS
	FOOT	FOOT	EACH	FOOT	FOOT	
FAI 57						
NORTHBOUND						
RT (MEDAIN SHOULDER)						
1506+90 TO 1515+60.11	871				871	
1507+00		19				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1508+25		19				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1509+50		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1510+00					11	EXSITING OUTLET
1511+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1513+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
GAP STRUCTURE #100-0086						
1517+56.11 TO 1528+80.23	1,125				1,125	
1517+55		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1518+01		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1518+61.5		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1519+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1521+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1522+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1524+00					14	EXISTING OUTLET
1524+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1526+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
GAP STRUCTURE #100-0084						
1531+14.23 TO 1542+33	1,119				1,119	
1534+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1535+50		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1537+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1538+70		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1539+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1540+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1541+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1542+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
SOUTHBOUND						
LT (MEDIAN SHOULDER)						
1500+00 TO 1509+43.5 BK	944				944	
1509+15.5 AH TO 1515+60.11	645				645	
1505+00		32	2			SAG LOCATION
1505+10					16	EXISTING OUTLET
1507+28		19				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1508+53		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1509+50		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1510+05					11	EXISTING OUTLET
1511+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1513+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
GAP STRUCTURE #100-0087						
1517+54.02 TO 1528+78	1,124				1,124	
1517+55		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1518+01		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1518+61.5		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1519+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1521+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1522+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1524+00					11	EXISTING OUTLET
1524+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1526+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
GAP STRUCTURE #100-0085						
1531+12 TO 1542+33	1,121				1,121	
1534+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1535+50		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1537+00		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1538+70		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1539+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1540+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1541+75		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
1542+25		17				OUTLET INTO DRAINAGE STRUCTURE TYPE 1
FAI 57 STAGE 1A PROJECT TOTALS	6,949	752	2	0	7,012	

NOTE: 1.) **PIPE UNDERDRAINS 4" (SPECIAL)** WILL BE ATTACHED TO INLETS IN STAGE 7 & 7A.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 11/2/2006
FILE NAME = c:\pw_work\X98295\d13\old13sch.h32
PLOT SCALE = 100.000 / In.
USER NAME = krenzje