CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	168
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 1A

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY					BORROW EXCAVATION	REMARKS
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR		
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
STA 1499+70 TO STA 1542+33 MEDIAN	1,321	23.3%	1,014	4,088	-3,074			
STA 1519+99 TO STA 1542+51 MEDIAN UNSUITABLE	4,276	0.0%	4,276	0				SOIL TO BE DRIED OUT AND PLACED IN FAI 57 STAGE 3 - SEE SPECIAL PROVISIONS
FAI 57 STAGE 1A PROJECT TOTAL	**5,597**	11.7%	5,290	4,088	-3,074	25.0%	**3,843**	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\c982802\old3\old3sch.n32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = k-ernejo