CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	196
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

PAVEMENT MARKING REMOVAL - FAI 57 STAGE 2

LOCATION STATION TO STATION	PAVEMENT MARKING REMOVAL DASH LINE SQ FT	PAVEMENT MARKING REMOVAL SOLID LINE SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
FAI 57				
NORTHBOUND				
STA. 1506+05 TO STA. 1506+90	0	57		
STA. 1506+90 TO STA. 1507+81	8	30		
STA. 1507+81 TO STA. 1510+48.26 BK	22	179		
STA. 1510+49.47 AH TO STA. 1510+95	4	31		
STA. 1510+95 TO STA. 1518+78	65	261		
STA. 1517+30 TO STA. 1518+78	12	0		LEFT DASH LINE ON RAMP E
STA. 1518+78 TO STA. 1526+85	67	538		
STA. 1526+85 TO STA. 1530+71	32	129		
STA. 1530+71 TO STA. 1542+33	97	775		
STA. 1542+33 TO STA. 1543+18	0	85		
SOUTHBOUND				
STA. 1499+15 TO STA. 1500+00	0	85		
STA. 1500+00 TO STA. 1504+00	33	267		
STA. 1503+10 TO STA. 1504+00	0	90		RIGHT AND LEFT EDGE LINES ON RAMP C
STA. 1504+00 TO STA. 1505+10.50	18	70		
STA. 1504+00 TO STA. 1505+10.50	18	70		RIGHT EDGE LINE AND LEFT DASH LINE ON RAMP C
STA. 1505+10.50 TO STA. 1509+43.50 BK	28	222		
STA. 1509+15.58 AH TO STA. 1517+34	68	546		
STA. 1517+34 TO STA. 1519+37	17	68		
STA. 1519+37 TO STA. 1526+25	57	459		
STA. 1526+25 TO STA. 1527+90	14	0		LEFT DASH LINE ON RAMP FF
STA. 1526+25 TO STA. 1535+56	78	310		
STA. 1535+56 TO STA. 1542+33	57	451		
STA. 1542+33 TO STA. 1543+18	0	85		
FAI STAGE 2 PROJECT SUBTOTAL	695	4,808	0	
FAI 57 STAGE 2 PROJECT TOTAL	5,503		0	

RAISED PAVEMENT MARKERS - FAI STAGE 2

LOCATION STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKER ONE-WAY AMBER EACH	TWO-WAY AMBER EACH	ONE-WAY CRYSTAL EACH
FAI 57				
NORTHBOUND				
STA. 1505+56 TO STA. 1515+56	26			26
STA. 1517+63 TO STA. 1528+73	28			28
STA. 1531+15 TO STA. 1543+18	31			31
STA. 1543+18 TO STA. 1550+85	10			20
SOUTHBOUND				
STA. 1499+15 TO STA. 1515+53	41			41
STA. 1517+61 TO STA. 1528+70	28			28
STA. 1531+19 TO STA. 1543+18	30			30
STA. 1543+18 TO STA. 1556+85	17			
STA. 1543+18 TO STA. 1556+85				35
FAI 57 STAGE 2 PROJECT SUBTOTALS		0	0	239
FAI 57 STAGE 2 PROJECT TOTALS	211	239		

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pwworking\d02\d0283\bdf3\d0283ech.h32
PLOT SCALE = 60.0000 / INL
USER NAME = kremnzjp