

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	**	WILLIAMSON	917	217
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 3

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105 TON	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105 TON	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105 TON	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4"			STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
				INFO. ONLY		FOR INFORMATION ONLY										
				THICKNESS (IN.)	TON	POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"								
FAI 57 NORTHBOUND																
STA 1506+90 TO STA 1509+35			65.0	11.00	328.0									54	229	
STA 1506+90 TO STA 1508+87			6.0	12.75	33.0										15	
STA 1509+35 TO STA 1510+48.26 BK			38.0	11.00	191.0						390.0			8	101	
STA 1510+49.47 AH TO STA 1511+62			32.0	11.00	158.0						337.0			8	84	
STA 1510+50 TO STA 1512+10			27.0	12.75	154.0						109.0			7	69	
STA 1511+62 TO STA 1513+00			26.0	9.75	117.0						308.0			10	70	
STA 1538+90 TO STA 1541+00			81.0	9.75	358.0						782.0			10	213	
STA 1541+00 TO STA 1542+33			51.0	9.75	227.0						495.0			6	135	
STA 1542+33 TO STA 1550+00			177.0	9.75	789.0						1,907.0			36	474	
SOUTHBOUND																
STA 1536+00 TO STA 1536+85			6.0	15.00	24.0										9	
STA 1536+00 TO STA 1536+85			30.0	11.00	152.0						298.0			5	80	
STA 1536+85 TO STA 1537+00			6.0	11.00	29.0						53.0			1	15	
STA 1537+00 TO STA 1541+00			155.0	11.00	771.0						1,405.0			24	407	
STA 1541+00 TO STA 1542+33			51.0	11.00	256.0						467.0			8	135	
STA 1542+33 TO STA 1544+96		56.0	85.0	11.00	423.0						715.0			21	224	
STA 1544+96 TO STA 1547+22.5 SEE NOTE 1		38.0	58.0	11.00	291.0						496.0			4	155	
STA 1547+22.5 TO STA 1550+46.5		55.0	83.0	11.00	416.0						710.0			4	222	
STA 1550+46.5 TO STA 1553+46.75		42.0	64.0	11.00	324.0						558.0			6	173	
STA 1553+46.75 TO STA 1556+00		29.0	43.0	11.00	221.0						386.0			4	119	
FAI 57 STAGE 3 PROJECT TOTALS																
	0	220	1,084		5,262				0	0	0	9,416	0	192	2,929	0

NOTE: 1.) SUB-BASE GRANULAR MATERIAL, TYPE C ENDS AT STA 1545+51.

PLOT DATE = 1/16/2007
 FILE NAME = c:\projects\98950\old\19\old\98950.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = mcrzjp

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE:	VERT. HORIZ.	DRAWN BY JCK CHECKED BY
DATE		

SCHEDULE