CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	223
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

LIME MODIFIED SOILS - FAI 57 STAGE 3

LOCATION STA TO STA	PROCESSING MODIFIED SOILS 12"	LIME	FOR INFO. ONLY WATER
	SQ YD	TON	UNIT
FAI 57			
NORTHBOUND			
LT. STA. 1506+90 TO STA. 1509+35	847.0	25.0	13.0
FAI 57 STAGE 3 PROJECT TOTALS	847.0	25.0	13.0

EARTHWORK - FAI 57 STAGE 3

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR	BORROW EXCAVATION	REMARKS
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
LT STA 1506+00 TO STA 1513+00	279	15.8%	235	8,784	-8,549			
LT STA 1538+90 TO STA 1550+50	3,531	24.5%	2,665	1,665	1,000			
RT STA 1530+67 TO STA 1556+20	8,610	23.0%	6,630	3,436	3,194			
STOCKPILE					4,270			SOIL FROM FAI 57 STAGE 1A - SEE SPECIAL PROVISIONS
FAI 57 STAGE 3 PROJECT TOTAL	12,420	21.1%	9,530	13,885	-85	25.0%	106	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_work\PW02082\old13\old13sch.h32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjo