CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	225
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EROSION CONTROL - FAI 57 STAGE 3

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL)	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	END SECTIONS 8"	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	CU YD	TON	EACH	EACH	EACH	
FAI 57										
NORTHBOUND										
LT STA 1506+10	10.0					2.0			1.0	
LT STA 1506+26	28.0					2.0			1.0	
LT STA 1505+95 TO STA 1513+00		4,671.0		742.0						APPROXIMATE OFFSET =100'
LT STA 1506+18 TO STA 1513+00				704.0						APPROXIMATE OFFSET =80'
LT STA 1508+85	29.0					2.0			1.0	
LT STA 1508+88	9.0					2.0			1.0	
LT STA 1510+85	13.0					2.0			1.0	
LT STA 1510+88	36.0					2.0			1.0	
LT STA 1512+87	14.0					2.0			1.0	
LT STA 1512+90	34.0					2.0			1.0	
LT STA 1538+90 TO STA 1550+00		4,578.0								
LT STA 1539+50							1.0			
LT STA 1542+35							1.0			
LT STA 1542+50					11.0	1.0				
LT STA 1545+20							1.0			
LT STA 1546+15							1.0			
LT STA 1547+15							1.0			
LT STA 1548+15							1.0			
LT STA 1549+15							1.0			
SOUTHBOUND										
RT STA 1536+00 TO STA 1555+97		4,381.0								
RT STA 1530+90								1.0		
RT STA 1530+24					11.0	1.0				
RT STA 1532+00							1.0			
RT STA 1535+00							1.0			
RT STA 1537+00							1.0			
RT STA 1538+90							1.0			
RT STA 1539+62								1.0		
RT STA 1541+00							1.0			
RT STA 1542+00							1.0			
RT STA 1544+00							1.0			
RT STA 1545+00							1.0			
RT STA 1546+00							1.0			
RT STA 1546+76								1.0		
RT STA 1549+05							1.0			
RT STA 1551+35							1.0			
RT STA 1553+65							1.0			
FAI 57 STAGE 3 PROJECT TOTAL	**173.0**	**13,630.0**	**0.0**	**1,446.0**	**22.0**	**18.0**	**19.0**	**3.0**	**8.0**	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/14/2006
PLOT NAME = c:\pw_work\pw_49\d0282822\ild13ch0m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kremzjp