

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	309

STA. TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** CX1-6-2WB-2, CX1-6HBK-2

SHOULDERS - FAI 57 STAGE 4

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	BITUMINOUS SHOULDERS, SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 8"	BITUMINOUS SHOULDERS SUPERPAVE 8 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 9 1/2"	AGGREGATE SHOULDERS, TYPE A 8"	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	SHOULDER RUMBLE STRIP	REMARKS
	SQ YD	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	GALLON	FOOT	
FAI 57 NORTHBOUND											
LT (OUTSIDE SHOULDER)											
STA. 1513+00 TO STA. 1514+95	189.0			47.0							
STA. 1514+95 TO STA. 1515+83	44.0			19.0							
STA. 1515+86 TO STA. 1515+84.5	16.0										
STA. 1517+35 TO STA. 1519+58	170.0										
STA. 1517+56 TO STA. 1519+58				57.0							
STA. 1518+77 TO STA. 1523+45	52.0										
STA. 1519+58 TO STA. 1523+45				86.0							
STA. 1525+86 TO STA. 1527+50	169.0			109.0			37				
STA. 1527+50 TO STA. 1528+80	82.0			87.0			29				
STA. 1528+73 TO STA. 1529+17	20.0										
STA. 1530+71.3 TO STA. 1531+22	25.0										
STA. 1531+14 TO STA. 1536+40	58.0			117.0							
STA. 1536+40 TO STA. 1538+90	278.0			56.0							
SOUTHBOUND											
RT (OUTSIDE SHOULDER)											
STA. 1510+00 TO STA. 1511+11	123.0			25.0							
STA. 1511+11 TO STA. 1511+80	77.0			15.0							
STA. 1511+80 TO STA. 1515+61	41.0			85.0							
STA. 1515+53 TO STA. 1515+81.5	8.0										
STA. 1517+33 TO STA. 1519+25	139.0										
STA. 1517+54 TO STA. 1519+25				48.0							
STA. 1522+15 TO STA. 1526+00	43.0			86.0							
STA. 1526+00 TO STA. 1526+73				20.0							
STA. 1526+00 TO STA. 1528+78	283.0										
STA. 1526+73 TO STA. 1527+78				100.0							
STA. 1527+78 TO STA. 1528+78				62.0							
STA. 1528+78 TO STA. 1529+14	23.0										
STA. 1530+69 TO STA. 1531+19	37.0										
STA. 1531+12 TO STA. 1535+00	42.0			87.0							
STA. 1535+00 TO STA. 1536+00	11.0			22.0							
FAI 57 STAGE 4 PROJECT TOTALS	1930.0	0.0	0.0	1,128.0	0.0	0.0	66.0	0.0	0.0	0.0	

PLOT DATE = 12/5/2006
 PLOT SCALE = 500000 / IN.
 USER NAME = hrnzjg

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE SCALE: VERT. HORIZ. DATE: _____
		DRAWN BY JCK CHECKED BY _____