

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	374
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)VB-2, (X1-6)HBK-2

PIPE UNDERDRAINS - FAI 57 STAGE 5

LOCATION STATION TO STATION	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	PIPE UNDERDRAIN REMOVAL	COMMENTS
	FOOT	FOOT	EACH	FOOT	FOOT	
FAI 57						
SOUTHBOUND						
RT (OUTSIDE SHOULDER)						
1519+25 TO 1520+43	118				118	
RAMP F						
RT						
4+42 TO 14+20	978					SEE NOTE 1
						EXISTING STATION & HEADWALL - SEE NOTE 1
			14			REUSE HEADWALL FROM EXISTING STA 4+47
						EXISTING STATION & HEADWALL - SEE NOTE 1
			14	1		REUSE HEADWALL FROM EXISTING STA 10+32
LT						
4+42 TO 11+21	679					SEE NOTE 1
				1		
			12	1		
11+21.77 TO 15+53	394					
RAMP FF						
RT						
2+00 TO 8+00	600					SEE NOTE 1
			14	1		
			14			REUSE HEADWALL FROM EXISTING STA 6+05
						EXISTING STATION & OUTLET - SEE NOTE 1
LT						
4+55 TO 8+00	345					SEE NOTE 1
			12	1		
FAI 57 STAGE 5 PROJECT TOTALS	3,114	80	5	0	118	

NOTE: 1.) THE EXISTING PIPE UNDERDRAIN REMOVAL IS TO BE INCLUDED IN WITH THE PAY ITEM PAVEMENT REMOVAL

PLOT DATE = 1/16/2007
 FILE NAME = c:\p\project\98950\stage5\stage5.dwg
 PLOT SCALE = 50.0000 / IN.
 USER NAME = krenzjc

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. / HORIZ.		DRAWN BY JCK CHECKED BY
DATE		

SCHEDULE