CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	376
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 5

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY					BORROW EXCAVATION	REMARKS
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR		
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
STAGE 5								
STA 4+40 TO STA 8+78 RAMP F	0	15.4%	0	7,932	-7,932			
STA 10+00 TO STA 15+83 RAMP F	1,929	16.8%	1,604	3,970	-2,366			
STA 4+50 TO STA 7+96 RAMP FF	1,052	15.4%	890	7,736	-6,846			
STAGE 5A								
STA 7+18 TO STA 15+83 RAMP F	996	17.4%	822	4,905	-4,083			
STAGE 5B								
STA 1519+25 TO STA 1522+15 SOUTH BOUND	28	25.7%	21	359	-338			
FAI 57 STAGE 5 PROJECT TOTAL	**4,005**	18.1%	3,337	24,902	-21,565	25.0%	**26,956**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
PLOT NAME = c:\pwworking\d-\d92887\sdd3\sdd3sch.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenaup