CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	379
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 5

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SKIP-DASH WHITE FOOT	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SOLID WHITE FOOT	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 6" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 8" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 8" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 12" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 12" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 24" SOLID WHITE FOOT	TEMPORARY PAINT PAVEMENT MARKING LETTERS AND SYMBOLS SQ FT	SHORT TERM PAVEMENT MARKING WHITE FOOT	SHORT TERM PAVEMENT MARKING YELLOW FOOT
FAI 57															
RAMP F															
STA 4+40 TO STA 5+83					143										
STA 5+83 TO STA 6+62					79										
STA 5+83 TO STA 6+62 SEE NOTE 1									79						
STA 6+62 TO STA 7+23					61		61								
STA 7+23 TO STA 9+00					177										
STA 14+65 TO STA 15+82					215		250								
FAI 57 STAGE 5 PROJECT SUBTOTALS	0	0	0	0	675	0	311	0	79	0	0	0	0	0	0	0
FAI 57 STAGE 5 PROJECT TOTALS		0			986			0	79		0		0	0	0

NOTE: 1.) THE SOLID WHITE LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_pw1\k0902002\sdi13\sdi13schum32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kramajo