CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	430
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 6

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL) LINE 4" SKIP-DASH WHITE FOOT	LINE 4" SOLID WHITE FOOT	LINE 4" SOLID YELLOW FOOT	TEMPORARY PAINT PAVEMENT MARKING LINE 4" SKIP-DASH WHITE FOOT	LINE 4" SOLID WHITE FOOT	LINE 4" SKIP-DASH YELLOW FOOT	LINE 4" SOLID YELLOW FOOT	LINE 6" SOLID WHITE FOOT	LINE 8" SOLID WHITE FOOT	LINE 8" SOLID YELLOW FOOT	LINE 12" SOLID WHITE FOOT	LINE 12" SOLID YELLOW FOOT	LINE 24" SOLID WHITE FOOT	LETTERS AND SYMBOLS SQ FT	SHORT TERM PAVEMENT MARKING WHITE FOOT	SHORT TERM PAVEMENT MARKING YELLOW FOOT
FAI 57																
RAMP EE																
STA 8+92 TO STA 11+00 SEE NOTE 2					505											
FAI 57 STAGE 6 PROJECT SUBTOTALS	0	0	0	0	505	0	0	0	0	0	0	0	0	0	0	0
FAI 57 STAGE 6 PROJECT TOTALS		0			505			0	0	0	0		0	0	0	

NOTE: 1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.
2.) SEE CALCULATIONS AND/OR PLANS FOR CLARIFICATION OF QUANTITIES

PLOT DATE = 1/16/2007
FILE NAME = c:\pw_work\PW22082\sld3\sld3echa32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjo

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY