

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	539
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

STORM SEWERS - FAI 57 STAGE 7C

LOCATION	STORM SEWERS, CLASS A, TYPE 1								STORM SEWERS, CLASS A, TYPE 2			PRC FLARED END SECTIONS				TRENCH BACKFILL CU YD	CONCRETE COLLAR CU YD	REINFORCED CONCRETE PIPE ELBOW 24" EACH	REINFORCED CONCRETE PIPE TEE 12" W/12" RISER EACH	CONCRETE THRUST BLOCKS EACH	
	12"	15"	18"	21"	24"	27"	36"	42"	12"	21"	24"	12"	18"	21"	24"						
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH						
FAI 57																					
NORTHBOUND																					
STA 1506+75																		0.5			
STA 1506+75 TO STA 1507+00					22													8.0			
STA 1507+00 TO STA 1508+25				122														48.0			
STA 1508+25 TO STA 1509+50				122														115.0			
STA 1509+50 TO STA 1511+25			172															66.0			
STA 1511+25 TO STA 1513+00	172																	65.0			
FAI 57 STAGE 7C PROJECT TOTALS	172	172	244	22	0	0	0	0	0	0	0	0	0	0	0	0	0	302.0	0.5	0	0

INLETS - FAI 57 STAGE 7C

LOCATION	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 EACH	DRAINAGE STRUCTURES TY 4 WITH TWO TYPE 20 FRAMES AND GRATES EACH	INLETS, TYPE A, TYPE 8 GRATE EACH	INLETS, TYPE A, TYPE 20 FRAME AND GRATE EACH	INLETS, TYPE A, SPECIAL, TYPE 1 FRAME, OPEN LID EACH	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID EACH	INLETS, TYPE B, TYPE 6 FRAME AND GRATE EACH	INLETS, TYPE B, TYPE 8 GRATE EACH	INLETS, SPECIAL, TYPE 3, 5' EACH	INLETS, SPECIAL, TYPE 3, 6' EACH	INLETS TO BE ADJUSTED EACH
	FAI 57										
NORTHBOUND											
STA 1507+00			1								
STA 1508+25			1								
STA 1509+50			1								
STA 1511+25			1								
STA 1513+00			1								
FAI 57 STAGE 7C PROJECT TOTALS	0	0	5	0	0	0	0	0	0	0	0

PLOT DATE = 1/16/2007
 FILE NAME = c:\prowork\98950\stage7c\inlet\inlet.dwg
 USER NAME = krenz,p

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY JCK		CHECKED BY _____