

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	591
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
 ** CX1-6-2VB-2, CX1-6HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 8

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105 TON	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105 TON	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105 TON	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4"			STABILIZED SUB-BASE 4" SQ YD	STABILIZED SUB-BASE (VARIABLE DEPTH) TON	SUB-BASE GRANULAR MATERIAL, 6" SQ YD	SUB-BASE GRANULAR MATERIAL, 10" SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE C TON	BITUMINOUS MATERIAL (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	MATERIAL TRANSFER DEVICE TON	
				FOR INFORMATION ONLY		FOR INFORMATION ONLY											
				INFO. ONLY	THICKNESS (IN.)	POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"									SQ YD
				TON	TON	TON	TON	TON									TON
FAI 57 NORTHBOUND																	
STA 1505+94 TO STA 1506+90		31.0												33	0.5	22	
STA 1506+90 TO STA 1515+63		133.0												143	2.4		
STA 1506+90 TO STA 1510+48.26 BK		121.0												130	2.2	121	
STA 1510+49.47 AH TO STA 1515+63		173.0												186	3.1	173	
STA 1517+57 TO STA 1519+63		47.0												51	0.8		
STA 1517+56 TO STA 1528+80		379.0												408	6.8	379	
STA 1525+86 TO STA 1528+81		98.0												107	1.8		
STA 1531+15 TO STA 1534+86		40.0												43	0.7		
STA 1531+14 TO STA 1542+33		378.0												406	6.8	378	
STA 1542+33 TO STA 1543+08		17.0												18	0.3	17	
SOUTHBOUND																	
STA 1506+41 TO STA 1509+43.5 BK		136.0												146	2.4	136	
STA 1509+15.58 AH TO STA 1513+25		184.0												198	3.3	184	
STA 1513+25 TO STA 1515+62		109.0												117	1.9	80	
STA 1517+54 TO STA 1519+85		72.0												77	1.3		
STA 1517+54 TO STA 1528+79		380.0												408	6.8	380	
STA 1526+81 TO STA 1528+78		49.0												52	0.9		
STA 1531+12 TO STA 1534+47		49.0												53	0.9	113	
STA 1531+12 TO STA 1534+47		113.0												121	2.0		
STA 1534+47 TO STA 1542+33		353.0												379	6.3	353	
STA 1542+33 TO STA 1543+08		26.0												27	0.5	26	
FAI 57 STAGE 8 PROJECT TOTALS																	
	0	2,889	0	0	0	0	0	0	0	0	0	0	0	3,103	51.7	2,362	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. _____
 HORIZ. _____

DATE: _____

DRAWN BY JCK
 CHECKED BY _____

PLOT DATE = 10/25/2006
 FILE NAME = c:\p\projects\98950\98950.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = jck