CONTRACT NO. 98950

F.A. RTE.	*	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*		**	WILLIAMSON	917	592
STA.			TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SHOULDERS - FAI 57 STAGE 8

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	BITUMINOUS SHOULDERS, SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 8"	BITUMINOUS SHOULDERS SUPERPAVE 8 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 9 1/2"	AGGREGATE SHOULDERS, TYPE A 8"	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	SHOULDER RUMBLE STRIP	REMARKS
	SQ YD	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	GALLON	FOOT	
FAI 57											
NORTHBOUND											
RT (INSIDE SHOULDER)											
STA 1505+94 TO STA 1506+90		6								96	
STA 1506+90 TO STA 1510+48.2 BK		22							24	359	
STA 1510+49.4 AH TO STA 1515+62		31							34	513	
STA 1517+55 TO STA 1528+79		69							73	1,124	
STA 1531+13 TO STA 1543+08		73							78	1,195	
STA 1543+08 TO STA 1551+75										867	
LT (OUTSIDE SHOULDER)											
STA 1505+94 TO STA 1506+90		7							7	96	
STA 1506+90 TO STA 1513+25		58							61	635	
STA 1513+25 TO STA 1515+65		22							23	240	
STA 1517+58 TO STA 1519+05										147	
STA 1517+58 TO STA 1519+58		12							13		
STA 1519+05 TO STA 1519+63		3							3		
STA 1519+05 TO STA 1526+50		98							105	745	
STA 1519+56 TO STA 1523+45	87										
STA 1525+09 TO STA 1525+86	17										
STA 1525+92 TO STA 1528+82		17							18		
STA 1526+50 TO STA 1528+82										232	
STA 1531+16 TO STA 1534+86		25							26	370	
STA 1534+86 TO STA 1537+02		25							26	216	
STA 1537+02 TO STA 1543+08		80							85	606	
STA 1537+02 TO STA 1546+65	214										
STA 1543+08 TO STA 1550+00										692	
SOUTHBOUND											
RT (OUTSIDE SHOULDER)											
STA 1506+41 TO STA 1509+43.5 BK		34							37	303	
STA 1509+15.5 AH TO STA 1513+25		46							49	410	
STA 1513+25 TO STA 1515+60		28							30	235	
STA 1517+53 TO STA 1519+39										186	
STA 1517+53 TO STA 1519+83		15							16		
STA 1519+39 TO STA 1519+85		2							2		
STA 1519+39 TO STA 1527+11		101							108	772	
STA 1522+50 TO STA 1526+45	88										
STA 1526+81 TO STA 1528+77		12							13		
STA 1527+11 TO STA 1528+77										166	
STA 1531+11 TO STA 1534+47		28							24	336	
STA 1531+12 TO STA 1542+33	249										
STA 1534+47 TO STA 1543+08		65							69	861	
STA 1542+33 TO STA 1544+96	59										
STA 1543+08 TO STA 1556+00										1,292	
LT (INSIDE SHOULDER)											
STA 1507+18 TO STA 1509+43.5 BK		14							15	226	
STA 1509+15.59 AH TO STA 1515+62		39							42	647	
STA 1517+55 TO STA 1528+79		69							73	1,124	
STA 1531+13 TO STA 1543+08		73							78	1,195	
STA 1543+08 TO STA 1556+85										1,377	
FAI 57 STAGE 8 PROJECT TOTALS	**714.0**	**1,074.0**	**0.0**	**0.0**	**0.0**	**0.0**	**0.0**	**0.0**	**1,132.0**	**17,263.0**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 12/11/2006
FILE NAME = c:\pwworking\d02\d0202\sheet\d0202sch02.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzje