

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	**	WILLIAMSON	917	599A
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

PAVEMENT MARKING REMOVAL - FAI 57 STAGE 8

LOCATION STATION TO STATION	PAVEMENT MARKING REMOVAL		WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
	DASH LINE SQ FT	SOLID LINE SQ FT		
FAI 57				
NORTHBOUND				
STA 1506+90 TO STA 1510+48.26 BK	30	239		
STA 1510+49.47 AH TO STA 1510+93	3	29		
STA 1510+93 TO STA 1513+25	20	155		
STA 1513+25 TO STA 1514+10	7	57		
STA 1514+10 TO STA 1516+60	40	167		
STA 1516+60 TO STA 1517+63	10	137		
STA 1517+63 TO STA 1519+07	13	240		
STA 1519+07 TO STA 1525+87	57	453		
STA 1525+87 TO STA 1528+25	20	317		
STA 1528+25 TO STA 1531+88	30	726		
STA 1531+88 TO STA 1534+86	27	199		
STA 1534+86 TO STA 1542+00	0	476		
STA 1542+00 TO STA 1543+00	0	67		
STA 1543+00 TO STA 1550+00	60	467		
STA 1550+00 TO STA 1551+75	17	58		
SOUTHBOUND				
STA 1500+00 TO STA 1502+12	10	141		
STA 1502+12 TO STA 1503+12	0	133		
STA 1503+12 TO STA 1508+10	0	830		
STA 1508+10 TO STA 1509+43.5 BK	20	89		
STA 1509+15.58 AH TO STA 1513+00	67	256		
STA 1513+00 TO STA 1515+53	23	261		
STA 1515+53 TO STA 1519+39	33	703		
STA 1519+39 TO STA 1542+33	193	1529		
STA 1542+33 TO STA 1547+25	40	291		
STA 1547+25 TO STA 1556+00	73	583		
STA 1556+00 TO STA 1556+85	7	28		
FAI STAGE 8 PROJECT SUBTOTAL	800	8,631	0	
FAI 57 STAGE 8 PROJECT TOTAL	9,431		0	

PLOT DATE = 12/11/2006
 PLOT SCALE = 3/8" = 1' IN.
 USER NAME = hrenzju

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE
SCALE: VERT. HORIZ. DATE		DRAWN BY JCK CHECKED BY