

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	**	WILLIAMSON	917	601
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- \* FAI 57 & FAU 9629 (OLD IL 13)
- \*\* (X1-6-2)VB-2, (X1-6)BK-2

### GUARD RAIL - FAI 57 STAGE 8

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED)	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)	GUARDRAIL REMOVAL	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH		
<b>FAI 57</b>													
<b>NORTHBOUND</b>													
<b>LT (OUTSIDE SHOULDER)</b>													
STA. 1511+62 TO STA. 1514+95	64.0		333.0					333.0					
STA. 1531+14.9 TO STA. 1537+02	95.0		572.0				1	587.0					REMOVE & CONNECT PROPOSED TO TYPE 6 TERM. PLACED IN STAGE 4 - SEE NOTE 2
<b>SOUTHBOUND</b>													
<b>RT (OUTSIDE SHOULDER)</b>													
STA. 1502+24.5 TO STA. 1515+60.4	241.0		1,369.0					1,369.0					REMOVE & CONNECT PROPOSED TO TYPE 6 TERMINAL PLACED IN STAGE 4
<b>RAMP FF</b>													
<b>RT (OUTSIDE SHOULDER)</b>													
STA. 12+39.25 TO STA. 12+45.5				1				31.0					SEE NOTE 1 GUARDRAIL PLACED ON THE SHEET PILING IN STAGE 4
STA. 14+37.5 TO STA. 16+00								162.5					
<b>FAI 57 STAGE 8 PROJECT TOTALS</b>													
	400.0	0	2,274.0	1	0	0	1	2,482.5	0	0	0	0	

NOTE: 1.) REMOVAL OF THE TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 6 PLACED IN STAGE 4 AND REPLACE IT WITH A TRAFFIC BARRIER TERMINAL, TYPE 2.  
 2.) THE TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL USE A FLARE RATE OF 15:1.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

#### SCHEDULE

SCALE: VERT.  
DATE: HORIZ.

DRAWN BY JCK  
CHECKED BY