CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	784
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* I-57, & OLD IL 13 (FAU 9629)
** (X1-6-2)VB-2,(X1-6)HBK-2

BILL OF MATERIALS

PAY ITEM	DESCRIPTION	UNIT	QUANTITY TOTALS
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81020500	CONDUIT PUSHED, 2" DIA INTERMEDIATE METAL	FOOT	640
81020700	CONDUIT PUSHED, 3" DIA INTERMEDIATE METAL	FOOT	90
81100600	CONDUIT ATTACHED TO STRUCTURE , 2" DIA. GALV. STEEL	FOOT	445
81200230	CONDUIT EMBEDDED INSTRUCTURE , 2" DIA., PVC	FOOT	135
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18"X12"X6"	EACH	11
81600215	UD 2# 8 XLP, 1# 8 XLPG 3/4 " P	FOOT	2,530
81600315	UD 2# 6 XLP, 1# 6 XLPG 1" P	FOOT	3,950
81600415	UD 2# 4 XLP, 1# 4 XLPG 1" P	FOOT	4,135
81702410	ELECTRIC CABLE IN CONDUIT, 600 V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	190
81702420	ELECTRIC CABLE IN CONDUIT, 600 V (XLP-TYPE USE) 3-1/C NO. 8	FOOT	175
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	9,480
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 250 WATT	EACH	27
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 400 WATT	EACH	19
82107300	UNDERPASS LIGHTING UNIT, 150 WATT HPS	EACH	6
82500540	LIGHTING CONTROLLER CB-RCS-100-480	EACH	1
83003600	LIGHT POLE ALUMINUM 45' MH, 15' DAVIT ARM	EACH	27
83004100	LIGHT POLE ALUMINUM 50' MH, 4' DAVIT ARM	EACH	4
83004600	LIGHT POLE ALUMINUM 50' MH, 15' DAVIT ARM	EACH	15
83600355	LIGHT POLE FOUNDATION, METAL, 15" B.C., 8"X6'	EACH	27
83600357	LIGHT POLE FOUNDATION, METAL, 15" B.C., 8"X8'	EACH	15
83800650	BREAKWAY DEVICE, COUPLING, SS SVREEN	EACH	168

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS

SCALE: VERT. NONE HORIZ.
DATE

DRAWN BY CNH
CHECKED BY LA

PLOT DATE = 11/28/2006
FILE NAME = c:\projects\d902802\old13\old13pl2.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = headan