


CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	801

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* I-57, & OLD IL 13 (FAU 9629)
 ** (X1-6-2)VB-2,(X1-6)HBK-2



BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)
 BEFORE PLACING FINAL LIFT TO MAKE GORE
 REGION. EDGE OF PAVEMENT MILLING IS
 0 THEN GOES TO THE DEPTH SHOWN.


REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
MILLING DETAIL RAMP E
 SCALE: VERT. 10
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY

PLT DATE: 10/14/2006
 FILE NAME: c:\p\proj\98950\98950.dwg
 SCALE: 1/8" = 1'-0"
 USER: mason

CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	802
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				



DATE = 10/14/2006
 FILE NAME = \\s02002\old\13\old\13\13.dgn
 PLOT SCALE = 10.0000 / IN
 USER NAME = headen

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MILLING DETAIL RAMP EE

SCALE: VERT. 10
HORIZ.

DATE

DRAWN BY CNH
CHECKED BY

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	803
STA.		TO STA.		
ILL. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

PHASE DESIGNATION DIAGRAM


NAME OF INTERSECTION: OLD IL 13 AT I-57 WEST
 CONTROLLER SPECIFIED: FULL ACTUATED CONTROLLER, STANDARD SEQUENCE IV,
 8 PHASE TYPE IV CONTROLLER CABINET

REFERRING TO STANDARD 857001, THE
 VEHICULAR AND PEDESTRIAN PHASES
 USED ARE DESIGNATED AS SHOWN.

N

9

INDICATE NORTH BY ARROW




LEGEND	
← *	VEHICULAR MOVEMENT
← *	PEDESTRIAN MOVEMENT
* NUMBER REFERS TO ASSOCIATED PHASE	

REVISIONS	
DATE	DESCRIPTION
1-31-90	DRAWN
5-30-90	REVISED
12-18-01	REVISED
	REVISED

STD. 9-66

SIGN PANEL - TYPE 1



TO BE USED:

RT. STA. 771+77 (OLD IL 13) MAST ARM
 LT. STA. 772+67 (OLD IL 13) MAST ARM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DETAIL:
PHASE DESIGNATION DIAGRAM;
SIGN PANEL - TYPE 1

SCALE: VERT. NONE
 HORIZ. DATE

DRAWN BY CNH
 CHECKED BY JCK

PLOT DATE = 10/14/2006
 FILE NAME = c:\p\projects\982822\old13\old13.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = hresch

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	804

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* I-57, & OLD IL 13 (FAU 9629)
 ** (X1-6-2)VB-2,(X1-6)HBK-2

DETAIL OF DETECTOR LOOPS


NOTES

(APPLIES TO 6' x 6' LOOPS ONLY)

- THE DETECTOR LOOPS SHALL BE TYPE I. EACH DETECTOR LOOP SHALL HAVE 3 TURNS OF LOOP WIRE AND BE INSTALLED IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF SECTION 886 OF THE STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL ITEMS.
- BEGINNING LEAD WIRES SHALL BE CONNECTED TO THE BLACK LEAD AND THE ENDING LEAD WIRES SHALL BE CONNECTED TO THE WHITE LEAD OF THE TWIN TWISTED FEED CABLES AT THE SPLICE POINT.
- WHERE THE LOOPS ARE INSTALLED PRIOR TO RESURFACING, THE LOOP CORNERS SHALL BE DIAGONALLY CUT.

LOOP LEGEND

- () CLOCKWISE ROTATION FOR LOOP WIRES
- S INDICATES SPLICE POINT FOR DETECTOR LOOP LEAD
- INDICATES 2" CORE-DRILL




DETAIL 6' x 6' DETECTOR LOOPS

STD. 9-92

REVISIONS
DRAWN 5-13-02
REVISED 10-26-05
REVISED
REVISED


CONTROL INSTALLATION SIGNAL CABINET MOUNTED



STD. 9-113

REVISIONS
DRAWN 5-13-02
REVISED
REVISED

SERVICE INSTALLATION DETAILS



NOTE:
 MATERIAL AND SIZE OF CONDUIT
 AND CABLE AS REQUIRED BY
 UTILITY COMPANY

STD. 9-68

REVISIONS
DRAWN 1-31-90
REVISED 2-24-92
REVISED
REVISED

REVISIONS
NAME
DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DETAILS:
DETECTOR LOOPS; CONTROL INSTALLATION
SIGNAL CABINET MOUNTED; SERVICE
INSTALLATION

SCALE: VERT. NONE
 HORIZ. DATE


DRAWN BY CNH
 CHECKED BY JCK

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	805
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 1-57, & OLD IL 13 (FAU 9629)				
* * (X1-6-2)VB-2,(X1-6)HBK-2				

DETAILS OF COMBINATION STEEL MAST ARM ASSEMBLY AND POLE

GENERAL NOTES

1. THE COMBINATION MAST ARM ASSEMBLY AND POLE SHALL BE CONSTRUCTED WITH ONE PIECE MAST ARMS AND POLE OR OTHER EQUIVALENT SECTIONAL DESIGN.
2. THE CONTRACTOR SHALL SUBMIT DETAILED DRAWINGS SHOWING DESIGN MATERIALS, THICKNESS OF SECTIONS, WELD SIZES, AND ANCHOR BOLTS TO THE ENGINEER FOR APPROVAL PRIOR TO FABRICATION. THESE DRAWINGS SHALL BE AT LEAST 17" BY 22" IN SIZE AND OF ADEQUATE QUALITY FOR MICROFILMING.
3. THE TYPE OF SIGNAL HEAD MOUNTING BRACKET TO BE USED SHALL BE APPROVED BY THE ENGINEER.
4. THE SIGNAL HEAD (INCLUDING BACKPLATE WHEN USED) SHALL NOT BE LESS THAN 16' OR MORE THAN 18' ABOVE THE CROWN OF PAVEMENT.
5. THE MANUFACTURER WILL BE ALLOWED TO SLOT THE BASE PLATE IN WHICH OTHER BOLT CIRCLES MAY FIT, PROVIDING THAT THESE SLOTS DO NOT OFFSET THE INTEGRITY OF THE POLE.
6. COMBINATION MAST ARM ASSEMBLIES AND POLES SHALL NOT BE INSTALLED WITHOUT THE LUMINAIRE.
7. THE ANCHOR BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ARTICLE 1006.09 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
8. FOR MAST ARMS LESS THAN 32', THE 72" X 30" SIGN S BE MOUNTED ON THE MAST ARM POLE INSTEAD OF THE ARM.



MAST ARM LENGTH	BOLT CIRCLE	ANCHOR BOLT SIZE
16' THRU 28'	15"	1 1/2" X 60"
30' THRU 42'	18"	1 1/2" X 60"
44'	18"	1 3/4" X 90"

REVISIONS

DRAWN	2-13-90	REVISED	5-14-02
REVISED	8-16-94	REVISED	
REVISED	12-18-01	REVISED	
REVISED	2-19-02	REVISED	

STD. 9-70

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		DETAIL: COMBINATION STEEL MAST ARM ASSEMBLY AND POLE
		SCALE: VERT. NO SCALE HORIZ. DATE
		DRAWN BY CNH CHECKED BY

PLOT DATE = 10/13/2005
 FILE NAME = c:\p\proj\98950\2692\cd13\cd13a3.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 USER NAME = heden


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	806
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* I-57, & OLD IL 13 (FAU 9629)
 ** (X1-6-2)VB-2,(X1-6)HBK-2

POLE STANDARDS


"INSTALL AND ORIENT ARM BRACKET OVER POLE TENON AND FIRMLY HAND TIGHTEN THE TWO SET SCREWS. USE THIRD HOLE IN ARM BRACKET AS A GUIDE TO DRILL A 3/4" DIAMETER HOLE THROUGH TENON. INSTALL AND TIGHTEN SELF-TAPPING SCREW. TIGHTEN SET SCREWS AN ADDITIONAL 1/4 TO 3/8 TURN WITH HEX KEY (NOT PROVIDED). INSTALL LOCKNUTS ON SET SCREWS IF THREADED PROJECTION ALLOWS."

POLE SHALL MEET AASHTO STANDARD SPECIFICATIONS FOR 80 MPH WIND LOADING AND 90 LB. 4.0 SO. FT E.P.A. LUMINAIRE.




THE CONTRACTOR SHALL FURNISH AND INSTALL A LIGHT POLE IDENTIFICATION OF EACH NEW LIGHT POLE, AS SHOWN ABOVE, INCIDENTAL TO THE RESPECTIVE LIGHT POLE PAY ITEM. THE NUMERALS SHALL BE 3", SERIES "D", BLACK, SCREENED ON SILVER-WHITE TYPE B PRESSURE SENSITIVE REFLECTIVE SHEETING CONFORMING TO THE REQUIREMENTS OF SECTION T602.01 OF THE STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL ITEMS. THE NUMERALS SHALL CONFORM TO THE FHWA "STANDARD ALPHABETS FOR HIGHWAY SIGNS".

THE LIGHT POLE IDENTIFICATION SHALL BE APPLIED TO SIGN BASE MATERIAL AS SPECIFIED IN SECTION 719.11 OF THE STANDARD SPECIFICATIONS, APPROXIMATELY 7" ABOVE THE ADJACENT PAVEMENT GRADE VISIBLE TO APPROACHING TRAFFIC IN ACCORDANCE WITH HIGHWAY STANDARD 2319.




TWIN TENON




TENON MOUNT BRACKET ARM

NOTE: SINGLE OR TWIN ARM ASSEMBLY SHALL BE TILTED 3° ABOVE HORIZONTAL.




DAVIT ARM (AND OR)


DAVIT ARM-TWIN



TENON




SHORT BRACKET




DETAILS FOR UNDERGROUND DISTRIBUTION IF REQUIRED

POLE, WOOD


POLE LENGTH	DEPTH IN GROUND
65'-0"	12'-0"
60'-0"	10'-0"
55'-0"	9'-0"
50'-0"	8'-0"
45'-0"	7'-0"
40'-0"	6'-6"
35'-0"	6'-0"
30'-0"	5'-6"




BENT # (LOOKING)




BRIDGE PIER MOUNT



SECTION A-A




MAST ARM




TENON

- ① LUMINAIRE
- ② WOOD POLE, CLASS 3 OR BETTER
- ③ 2 1/2" GALV. STEEL CONDUIT
- ④ SINGLE OFFSET POLE BAND
- ⑤ CONDUIT BUSHING
- ⑥ CABLE CLAMPS ON 2' CENTERS
- ⑦ 2/C #12 TYPE USE CABLE
- ⑧ 1" GALV. STEEL CONDUIT 10' IN LENGTH


- ⑨ 5/8" Ø HOT DIPPED GALVANIZED BOLT WITH FLAT WASHER & LOCKNUT (3 REQ'D)
- ⑩ CONDUIT CLAMPS ON 3' CENTERS
- ⑪ UNIT DUCT
- ⑫ THREADED REDUCER
- ⑬ "C" CONDULET, THREADED
- ⑭ 1 1/2" GALV. STEEL CONDUIT FOR 1 UNIT DUCT OR 3" GALV. STEEL CONDUIT FOR 2 OR 3 UNIT DUCTS.




STAINLESS STEEL FLAIR BASE




TRANSFORMER BASE
 FRANGIBLE



BREAKAWAY COUPLING



ANCHOR



BUTT BASE

REVISIONS

DRAWN	2-9-01
REVISED	4-14-02
REVISED	
REVISED	

STD. 9-115

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**DETAILS:
POLE STANDARDS**

SCALE: VERT. NONE
 HORIZ. DATE


DRAWN BY CNH
 CHECKED BY JCK

PLOT DATE = 10/13/2006
 FILE NAME = c:\p\projects\98950\std\std9-115.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = hmcgovern

CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	807
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* I-57, & OLD IL 13 (FAU 9629)
 * * (X1-6-2)VB-2,(X1-6)HKB-2



NOTES:

1. REMOVAL OF A PORTION OF THE EXISTING INLET SHALL BE IN ACCORDANCE WITH THESE DETAILS AND THE APPLICABLE PORTIONS OF SECTION 605 OF THE STANDARD SPECIFICATIONS. THE INTENT IS TO REMOVE THE ENTIRE TOP SLAB AND A PORTION OF ALL FOUR WALLS FROM THE EXISTING INLET. THE COST OF THE REMOVAL SHALL BE INCLUDED IN THE CONTRACT PRICE, EACH, FOR DRAINAGE STRUCTURES, TYPE 4.
2. SEE STANDARDS 602106 AND 637006 FOR ADDITIONAL DETAILS.
3. RETAIN THE RE-BARS EXPOSED WHEN THE WALLS OF THE EXISTING INLET ARE REMOVED. BEND THE BARS AS DIRECTED BY THE ENGINEER, AND INCORPORATE THEM INTO THE FLOOR OF THE NEW DRAINAGE STRUCTURE.
4. THE RE-BARS SHOWN ON STANDARD 602106 IN THE FLOOR OF THE DRAINAGE STRUCTURE MAY BE CUT TO FIT AS DIRECTED BY THE ENGINEER.

LEGEND

CONCRETE REMOVAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION



DETAIL OF DRAINAGE STRUCTURE, TYPE 4
 TO BE USED AT I-57 STA. 1518+01

SCALE: VERT. NONE
 HORIZ. DATE

DRAWN BY CNH
 CHECKED BY EES

PLOT DATE = 10/13/2006
 FILE NAME = C:\p\proj\mca\p982806\d1d3\d1d3a.dgn
 USER NAME = heugan

CONTRACT NO. 98950				
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	808
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				



LEGEND

	EXISTING INLET TO BE REMOVED
	CONCRETE REMOVAL

- NOTES:**
1. REMOVAL OF THE EXISTING INLET SHALL BE PERFORMED IN ACCORDANCE WITH THESE DETAILS AND THE APPLICABLE PORTIONS OF SECTION 605 OF THE STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL USE PRECAUTIONS TO AVOID DAMAGE TO THE EXISTING RISER PIPE THAT IS TO REMAIN IN PLACE.
 2. THE COST FOR REMOVING A PORTION OF THE EXISTING CONCRETE RISER PIPE, AS SHOWN IN THESE DETAILS, SHALL BE INCLUDED IN THE CONTRACT PRICE, EACH, FOR DRAINAGE STRUCTURES, TYPE 4.
 3. SEE STANDARD 602106 FOR ADDITIONAL DETAILS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DETAIL OF DRAINAGE STRUCTURE, TYPE 4
TO BE USED AT STA. 1538+70


SCALE: VERT. NONE
HORIZ. DATE

DRAWN BY CNH
CHECKED BY EES

PLOT DATE = 10/14/2006
 FILE NAME = c:\pca\pca\98950\282\1.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = heath


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	810
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				

DRAINAGE SYSTEM AT LT. STA. 1517+71 NB I-57



INLETS, TYPE A, TYPE 20 FRAME AND GRATE
 18' LT. STA. 1517+71 NB I-57
 TOP OF GRATE ELEV. = 467.42
 INVERT ELEV. = 462.37
 STORM SEWER, CLASS A, TYPE 2 12" (30')
 PRECAST REINFORCED CONCRETE FLARED END SECTION 12"
 DSFL = 461.84
 PLACE THE INLET, STORM SEWER, AND END SECTION IN I-57 STAGE 4 WITH 3'x3'x1" STEEL PLATE PLACED ON TOP OF THE INLET COST TO BE INCLUDED WITH INLET. IN I-57 STAGE 8 USE SAW CUTS AND PAVEMENT REMOVAL OF A 3'x3' AREA ABOVE THE INLET AND PLACE THE FRAME AND GRATE. PLACE BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N70 AROUND THE FRAME.

DRAINAGE SYSTEM AT RT. STA. 1518+01 SB I-57



INLETS, TYPE A, TYPE 20 FRAME AND GRATE
 29' RT. STA. 1518+01 SB I-57
 TOP OF GRATE ELEV. = 467.37
 INVERT ELEV. = 464.54
 STORM SEWER, CLASS A, TYPE 2 12" (5')
 CUT OPENING IN EXIST. 24" RCCP FOR PROPOSED 12" STORM SEWER AND GROUT THE PROPOSED STORM SEWER INTO EXIST. PIPE. COST TO BE INCLUDED WITH THE PROPOSED STORM SEWER.
 PLACE THE INLET, STORM SEWER IN I-57 STAGE 4 WITH A 3'x3'x1" STEEL PLATE PLACED ON TOP OF THE INLET COST TO BE INCLUDED WITH INLET. IN I-57 STAGE 8 USE SAW CUTS AND PAVEMENT REMOVAL OF A 3'x3' AREA ABOVE THE INLET AND PLACE THE FRAME AND GRATE. PLACE BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N70 AROUND THE FRAME.


CONCRETE COLLAR
 0.68 CU. YD.
 SEE I-57 MEDIAN STORM SEWER SHEETS FOR PROPOSED WORK

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
DRAINAGE SYSTEMS AT
LT. STA. 1517+71 NB I-57 AND
RT. STA. 1518+01 SB I-57
 SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY

PLOT DATE = 10/14/2005
 FILE NAME = c:\p\proj\1518+01\1518+01.dgn
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = hudson

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	811
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				



CASE 1
(NB AND SB LANES ARE AT SAME ELEVATION)



CASE 2
(NB AND SB LANES ARE AT DIFFERENT ELEVATIONS)

* INCREASE DIMENSION BY 1/2 INCH FOR EACH 6" INCREMENT OF ELEVATION DIFFERENCE BETWEEN "A" AND "B"

NOTES:

1. THE METHOD AND SEQUENCE OF CONSTRUCTION WILL BE THE CONTRACTOR'S OPTION, BUT SHALL BE APPROVED BY THE ENGINEER.
2. PAYMENT FOR BITUMINOUS SHOULDER, SUPERPAVE, 6 1/2" SHALL BE BASED ON THE NUMBER OF SQUARE YARDS ACTUALLY PLACED TO THE DIMENSIONS SHOWN, AND NO ADDITIONAL PAYMENT WILL BE MADE IF THE CONTRACTOR CHOOSES TO BUILD THE SHOULDER TO A GREATER THICKNESS.

PLOT DATE = 10/17/2006
 FILE NAME = e:\p\objects\98950\282a\g13\csl13.dgn
 PLOT SCALE = 1/8" = 1' IN.
 USER NAME = hudson

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION





DETAIL OF BITUMINOUS SHOULDER UNDER CONCRETE MEDIAN BARRIER

SCALE: VERT. NONE
HORIZ. DATE

DRAWN BY CNH
CHECKED BY EES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	NO.
*	**	WILLIAMSON	917	812
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* I-57, & OLD IL 13 (FAU 9629)
 ** (X1-6-2)VB-2,(X1-6)HBK-2



BILL OF MATERIAL

BAR	NUMBER	SIZE	LENGTH
a ₁	26 *	#7	10'-6"
a ₂	4	#4	8'-3"
a ₃	6 **	#5	8'-3"
a ₄	4	#6	10'-5"
h	7 **	#7	8'-10"
h ₁	14	#5	8'-3"
h ₂	22	#6	8'-10"
h ₃	7 **	#4	8'-10"
h ₄	6	#4	1'-9"
v	30	#4	7'-11"
v ₁	11	#4	3'-5"
v ₂	6	#4	6'-5"

CLASS	SI CONCRETE	CU. YDS.	8.98
REINFORCEMENT BARS	LBS.	990	
REINFORCEMENT BARS (EPOXY COATED)	LBS.	500	
CAST IRON FRAME, SPECIAL, TY. 1 WITH TY. 1 CLOSED LID	EACH	1	

* 13 OF THE a₁ BARS ARE TO BE EPOXY COATED.
 ** EPOXY COATED

NOTES

- BECAUSE OF THE CAST IRON FRAME AND CONCRETE PIPES CONNECTING TO THE PROPOSED JUNCTION BOX, IT WILL BE NECESSARY FOR THE CONTRACTOR TO CUT SOME OF THE a₁, a₃, h, h₂, h₃, and v BARS IN THE FIELD TO FIT. PIECES CUT FROM THESE BARS SHALL BE USED TO COMPLETE THE LINES OF REINFORCEMENT BARS AS SHOWN ON THESE DETAILS AND AS DIRECTED BY THE ENGINEER.
- ALL REINFORCEMENT BARS TOTALLY WITHIN THE TOP SLAB SHALL BE EPOXY COATED.
- THE HOOKS OF THE a₁ BARS MAY BE TILTED IF NECESSARY TO PROVIDE THE SPECIFIED CLEARANCE.
- THREE V BARS ARE TO BE PLACED VERTICALLY, AS DIRECTED BY THE ENGINEER, IN THE COLLAR AT EACH SIDE OF THE 8' x 4' BOX CULVERT.
- SEE DISTRICT STANDARD 9-18 (SHEET 815) FOR DETAILS OF THE CAST IRON FRAME, SPECIAL, TYPE 1, WITH TYPE 1 CLOSED LID.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION



DETAILS OF JUNCTION BOX
 RIGHT OF STATION 773+75 (OLD ROUTE 13)

SCALE: VERT. NONE
 HORIZ. DATE

DRAWN BY CNH
 CHECKED BY EES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	813
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		* 1-57, & OLD IL 13 (FAU 9629)		
		** (X1-6-2)VB-2,(X1-6)HBK-2		

DETAILS OF INLET SPECIAL, TYPE 3, 5 FEET AND 6 FEET



DESIGN	PIPE DIA	"D"
A	18"BLESS	2'-6"
B	21"X24"	3'-0"
C	27"X30"	3'-7"
D	33"X36"	4'-2"
E	42"	4'-9"
F	48"	5'-0"
G	54"	6'-1"

NOTES:

PROVIDE 1/2" CLEARANCE TYP. ALL REINFORCEMENT UNLESS OTHERWISE SPECIFIED.


CLASS S1 CONCRETE SHALL BE USED THROUGHOUT. SET FACE OF INLET 1" BEHIND FACE OF CURB. DEPRESS GUTTER FLOWLINE AT INLET 2 1/2" BELOW NORMAL GUTTER FLOWLINE. CONSTRUCT TRANSITION IN FLOWLINE IN 10 FEET EACH SIDE OF INLET. PIPES TO BE CONNECTED TO INLET AS SHOWN ON STORM SEWER LAYOUT.

INLETS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR INLET, SPECIAL, TYPE 3, 5 FEET OR INLET, SPECIAL, TYPE 3, 6 FEET WHICH PRICE SHALL INCLUDE THE CAST IRON FRAME, SPECIAL, TYPE 1 WITH TYPE 1 CLOSED LID, THE REINFORCEMENT BARS, METAL STEPS AND JOINT FILLER.

**THE GALVANIZED IRON STEPS AS DETAILED HEREON ARE TYPICAL. STEPS OF OTHER DESIGN AND MATERIAL THAT WILL CONFORM TO THE MINIMUM REQUIREMENTS OF THE STEPS SHOWN, MAY BE USED WHEN APPROVED BY THE ENGINEER.

IF THE INLET IS NOT CAST IN PLACE THEN THE INLET SHALL BE PRODUCED ACCORDING TO THE DEPARTMENT'S CURRENT POLICY MEMORANDUM, "QUALITY CONTROL/QUALITY ASSURANCE PROGRAM FOR PRECAST CONCRETE PRODUCTS".


DETAILS OF INLET SPECIAL, TYPE 3, WITH OPENING BEHIND CURB



TO BE USED:

RT. STA. 775+60
RT. STA. 776+25
RT. STA. 778+00
RT. STA. 779+25
RT. STA. 780+50

DETAIL OF CONCRETE THRUST BLOCK FOR CONCRETE PIPE CULVERT



CONCRETE THRUST BLOCKS SHALL BE CONSTRUCTED AND PAID FOR IN ACCORDANCE WITH ARTICLES 609.06 AND 609.07 OF THE STANDARD SPECIFICATIONS. CLASS S1 CONCRETE SHALL BE USED THROUGHOUT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
**INLET SPECIAL, TYPE 3, 5 FEET AND 6 FEET;
INLET SPECIAL, TYPE 3, WITH OPENING
BEHIND CURB; CONCRETE THRUST BLOCK
FOR CONCRETE PIPE CULVERT**


SCALE: VERT. NONE
HORIZ. DATE DRAWN BY CNH
CHECKED BY EES

PLOT DATE = 10/14/2006
 FILE NAME = c:\pwworkspace\10102882\10102882.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = f.hudson

REVISIONS
 REDRAWN 2-15-89
 REVISED 8-15-94
 REVISED 1-19-99
 REVISED 5-6-04
 STD. 9-1

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	814
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

TYPICAL SECTIONS OF TRANSITIONS OF SLOPES AND INCIDENTAL GRADING




LENGTH OF ROUNDING AT TOP OF SLOPE 1/2 TIMES HEIGHT "H" (CUT IN FEET) OR TO R.O.W. LINE


SECTION SHOWING TRANSITIONS OF PROPOSED SLOPES

NOTE:

DITCH PLUG TO BE CONSTRUCTED AS DIRECTED BY THE ENGINEER, INCLUDED IN THE EARTH EXCAVATION




SECTION A-A



DITCH PLUG DETAIL

EARTH DITCH PLUG TO BE CONSTRUCTED AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER, AND TO BE CONSIDERED INCLUDED IN THE EARTH EXCAVATION.



DETAIL OF SLOPE TO NATURAL GROUND TRANSITION


TRANSITION GRADING

TRANSITION GRADING BETWEEN CUT AND FILL SLOPES AND BETWEEN CUT SLOPES AND NATURAL GROUND WILL BE REQUIRED ON THIS IMPROVEMENT. THE TRANSITION SHALL BE ROUNDED AND STREAMLINED IN ORDER TO BLEND THE CUT SLOPES AND THE FILL SLOPES INTO EACH OTHER AND INTO THE ADJACENT TERRAIN. THE SLOPES AS SHOWN ON THE CROSS SECTIONS IN THESE PLANS MAY BE VARIED SOMEWHAT IN THE TRANSITION AREAS AS DIRECTED BY THE ENGINEER IN ORDER TO MEET THIS GRADING REQUIREMENT. THE QUANTITIES OF EARTH EXCAVATION INVOLVED ARE INCLUDED IN THE BALANCE QUANTITIES SHOWN ON THE PLANS AND NO OTHER COMPENSATION WILL BE ALLOWED.


REVISIONS	DATE
REDRAWN	2-15-99
REVISION	
REVISION	
REVISION	

STD. 9-17

DETAILS OF CONCRETE COLLAR FOR PRECAST BOX CULVERT



SIDE VIEW



END VIEW

2 - #5 S BARS TYPICAL COST INCLUDED IN THE PROPOSED PRECAST BOX CULVERT.

REMOVE PORTION OF EXISTING HEADWALL DOWN TO 12" BELOW FINISHED GRADE

3/4" Ø X 18" EXPANSION BOLTS AT 18" CENTERS TYPICAL ALL FOUR SIDES. COST INCLUDED IN THE PROPOSED PRECAST BOX CULVERT. (SEE NOTE BELOW)

TABULATION

(FOR INFORMATION PURPOSES ONLY)

SPAN X RISE	CLASS S1 CONC. CU. YD. (EST.)
2' X 2'	0.26
3' X 2'	0.30
3' X 3'	0.34
4' X 2'	0.36
4' X 3'	0.39
4' X 4'	0.43
5' X 2'	0.41
5' X 3'	0.45
5' X 4'	0.49
6' X 2'	0.47
6' X 3'	0.51
6' X 4'	0.54


NOTE:

ANCHOR BOLTS, MEETING THE REQUIREMENTS OF ARTICLE 1006.09 OF THE STANDARD SPECIFICATIONS, SHALL EXTEND A MINIMUM OF 9 INCHES INTO THE NEW CONCRETE. EXPANSION SHIELDS SHALL PROVIDE A MINIMUM CERTIFIED PROOF LOAD OF 4080 POUNDS.

STD. 9-45

REVISIONS	DATE
DRAWN	8-15-89
REVISION	2-15-90
REVISION	8-10-90
REVISION	8-19-94
REVISION	12-17-01
REVISION	
REVISION	

TYPICAL CROSS SECTION SHOWING STEP CONSTRUCTION ON EXISTING FILL



MATERIAL TO BE REMOVED AND REPLACED IN THE EMBANKMENT IN ACCORDANCE WITH ART. 205.04 OF THE STANDARD SPECIFICATION. COST TO BE INCLUDED IN THE VARIOUS ITEMS OF EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED BECAUSE OF THIS WORK.

STD. 9-16

REVISIONS	DATE
REDRAWN	2-15-89
REVISION	8-15-94
CHECKED	6-3-99
REVISION	


REVISIONS	DATE
NAME	

ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
 SECTIONS OF TRANSITIONS OF SLOPES AND INCIDENTAL GRADING; CONCRETE COLLAR FOR PRECAST BOX CULVERT; CROSS SECTION SHOWING STEP CONSTRUCTION ON EXISTING FILL
 SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY

PLOT DATE: 10/14/2006
 PLOT SCALE: 9000000
 USER NAME: hrcason

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	815
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

DETAILS OF CONCRETE COLLAR FOR PIPE CULVERT



QUANTITY ONE COLLAR

DIA OF PIPE	CLASS SI CONC CU YD (EST)
12"	0.25
15"	0.29
24"	0.44
30"	
36"	

THE CONCRETE COLLAR SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR CONCRETE COLLAR, AS SHOWN ON THE PLANS. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.


TO BE USED:
 OLD ROUTE 13: RT. STA. 775+04
 RT. STA. 778+00
 RT. STA. 782+25
 I-57: RT. STA. 1518+01

REVISIONS


DRAWN	7-2-90
REVISED	8-22-96
REVISED	
REVISED	

MODIFIED STD. 9-77

DETAILS OF CAST IRON FRAMES SPECIAL TYPE 1 WITH TYPE 1 OPEN LID




DETAILS OF CAST IRON FRAMES SPECIAL TYPE 1 & TYPE 2 WITH TYPE 1 CLOSED LID



ANCHOR RING TO BE CAST INTEGRALLY AROUND FRAME
 WEIGHT OF FRAME: 200 LBS

THE FRAMES MAY BE MADE OF EITHER GRAY IRON CONFORMING TO THE STANDARD SPECIFICATIONS OR DUCTILE IRON CONFORMING TO THE SPECIFICATIONS FOR DUCTILE IRON CASTING, A.S.T.M. DESIGNATION: A536, GRADE 60-45-10.



WEIGHT OF FRAME: 90 LBS

STD. 9-18

REVISIONS

DRAWN	2-15-89
REVISED	12-14-91
REVISED	
REVISED	

REVISIONS

NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAIL:
 CONCRETE COLLAR FOR PIPE CULVERT;
 CAST IRON FRAMES SPECIAL TY. 1 & TY. 2
 WITH TY. 1 CLOSED LID; CAST IRON FRAMES
 SPECIAL TY. 1 WITH TY. 1 OPEN LID

SCALE: VERT. NONE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY EES


PLOT DATE = 10/14/2006
 FILE NAME = c:\p\proj\p06\98950\802\old\13\old\815.dgn
 PLOT SCALE = 50.0000 X 1 IN.
 USER NAME = hudson

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	816
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				

SIGN POST BLOCKOUT



PLAN VIEW




PROFILE VIEW

REVISIONS	
DRAWN	4-5-99
REVISED	
REVISED	
REVISED	

STD. 9-107

DETAILS OF SIGNING FOR TRAFFIC CONTROL AT RAMP



BACKGROUND: ORANGE REFLECTORIZED
LEGEND AND BORDER: BLACK
"D" SIZE LETTERS


SPECIAL SIGN DETAIL

REVISIONS	
DRAWN	9-7-90
REVISED	8-22-94
REVISED	
REVISED	

STD. 9-82

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3

FOR 55 MPH SPEED LIMIT




REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
SIGNING FOR TRAFFIC CONTROL AT RAMP;
SIGN POST BLOCKOUT
IMPACT ATTENUATORS, TEMPORARY
(NON-REDIRECTIVE) TEST LEVEL 3
SCALE: VERT. NONE
HORIZ. DATE
DRAWN BY CNH
CHECKED BY

PLOT DATE: 12/14/2006
FILE NAME: c:\puro\puro\98950\816\13\01\03.dgn
PLOT SCALE: 1/8\"/>


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	817
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

BUTT-JOINT STAGE 4




* TO BE USED:
STA. 1512+60 NB I-57

BUTT-JOINTS AT BRIDGES



BUTT-JOINT STAGE 7 AND 7A



* TO BE USED:

STAGE	SAW CUT LOCATION	TRANSITION LENGTH	PROFILE DIFFERENCE
7A	STA. 1506+24 I-57 NB	66'	0.275'
7A	STA. 1542+78 I-57 NB	45'	0.1875'
7A	STA. 1506+71 I-57 SB	45'	0.1875'
7	STA. 1542+78 I-57 SB	45'	0.1875'

TO BE USED	ACTUAL JOINT STATION
NORTHBOUND LANES:	
STAGE 4, 7, AND 8	
SN # 100-0086	1515+63.11
SN # 100-0086	1517+56.11
SN # 100-0084	1528+80.23
SN # 100 0084	1531+14.23
SOUTHBOUND LANES:	
STAGE 4, 7, AND 8	
SN # 100-0087	1515+61.02
SN # 100-0087	1517+54.02
SN # 100-0085	1528+78
SN # 100 0085	1531+12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION


DETAILS:
BUTT JOINT STAGE 4;
BUTT JOINT STAGE 7 AND 7A;
BUTT JOINTS AT BRIDGES

SCALE: VERT. NONE
HORIZ. DATE

DRAWN BY CNH
CHECKED BY


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	818
STA. ** TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

BITUMINOUS THICKNESS TRANSITION STAGE 7B




*** TO BE USED:**
STA. 1510+30 SB I-57

BITUMINOUS THICKNESS TRANSITION STAGE 7B




*** TO BE USED:**
STA. 1536+00 SB I-57

BITUMINOUS THICKNESS TRANSITION STAGE 7B



*** TO BE USED:**
STA. 1513+00 NB I-57

BITUMINOUS THICKNESS TRANSITION STAGE 7B



*** TO BE USED:**
STA. 1538+50 NB I-57


REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
BITUMINOUS THICKNESS TRANSITIONS
STAGE 7B

SCALE: VERT. NO SCALE
HORIZ. DATE
DRAWN BY CNH
CHECKED BY


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	819
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				

BUTT-JOINT STAGE 7B



*** TO BE USED:**
 STA. 1506+24 NB I-57
 STA. 1542+78 NB I-57
 STA. 1506+71 SB I-57


BUTT-JOINT STAGE 8



*** TO BE USED:**


SAW CUT LOCATION	TRANSITION LENGTH	PROFILE DIFFERENCE
STA. 1505+94 I-57 NB	96'	0.40'
STA. 1543+08 I-57 NB	75'	0.3125'
STA. 1506+41 I-57 SB	75'	0.3125'
STA. 1543+08 I-57 SB	75'	0.3125'

BUTT-JOINT STAGE 7B



*** TO BE USED:**
 STA. 1542+78 SB I-57

BUTT-JOINT AT RAMP



*** TO BE USED:**
 STA. 5+00 RAMP F
 STA. 8+97 RAMP EE

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAIL:
BUTT JOINTS STAGE 7B;
BUTT JOINT STAGE 8;
BUTT JOINT RAMP F AND EE
 SCALE: VERT. NO SCALE
 DATE: HORIZ.
 DRAWN BY CNH
 CHECKED BY

DATE = 10/19/2006
 FILE SCALE = 5/8" = 1' IN.
 USER NAME = hudson

CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	820
STA. TO STA.				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2, (X1-6)HBK-2				


DETAIL OF PCC SIDE ROADS WITH BUTT-JOINT



TO BE USED:
 OLD IL 13


COMFORT DRIVE STA. 764+65
 COMMANDER DRIVE STA. 774+92
 7TH STREET STA. 774+96
 5TH STREET STA. 784+61

BUTT-JOINT



*** TO BE USED:**
 STA. 4+70 RAMP F
 STA. 8+67 RAMP EE


DETAIL OF BITUMINOUS, PCC, OR OIL AND CHIP PRIVATE OR COMMERCIAL ENTRANCE



TO BE USED:

PREPARATION OF EXISTING SURFACE AND ANY EXCAVATION FOR ENTRANCES SHALL BE IN ACCORDANCE WITH ARTICLE 406.19 OF THE STANDARD SPECIFICATIONS.

BUTT-JOINT



*** TO BE USED:**
 STA. 753+20 (OLD IL 13)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DETAILS: BUTT JOINTS

SCALE: VERT. NONE
 HORIZ. DATE

DRAWN BY CNH
 CHECKED BY


CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	820A

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

* I-57, & OLD IL 13 (FAU 9629)
 ** (X1-6-2)VB-2,(X1-6)HBK-2

BUTT-JOINT



* TO BE USED:
 STA. 784+88 (OLD IL 13)

DATE = 11/20/2006
 FILE NAME = c:\p2\98950\98950.dgn
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = nesdon

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION

**DETAIL:
 BUTT JOINT**


SCALE: VERT. NONE
 HORIZ. DATE

DRAWN BY CNH
 CHECKED BY


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	821
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				




SECTION A-A: PROPOSED BOX CROSSING EXISTING ROAD
TRENCH DEPTH GREATER THAN 5'
SHORING REQUIRED




PROFILE SECTION THRU BOX CULVERT ACROSS ROADWAY



SECTION OF TRENCHES NEAR EDGE OF PAVEMENT



SECTION B-B: PROPOSED STORM SEWER CROSSES EXISTING ROAD
TRENCH DEPTH GREATER THAN 5'
SHORING REQUIRED



PROFILE SECTION THRU STORM SEWER ACROSS ROADWAY

NOTES:

THE CONSTRUCTION REQUIREMENTS OF THE TRENCHES FOR STORM SEWER SHALL BE IN ACCORDANCE WITH ARTICLE 550.04 AND 550.07 OF THE STANDARD SPECIFICATIONS.
TRENCH BACKFILL WILL BE MEASURED AND PAID FOR AS SPECIFIED IN ARTICLES 208.03 AND 208.04 OF THE STANDARD SPECIFICATIONS.


* 9" + PIPE OD + 9" WHEN TRENCH DEPTH < 5'.
18" + PIPE OD + 18" WHEN TRENCH DEPTH > 5'.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		DETAILS: TRENCH BACKFILL

SCALE: VERT. NO SCALE
HORIZ. DATE
DRAWN BY CNH
CHECKED BY


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	822
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

TEMPORARY BITUMINOUS CONCRETE TRANSITIONS




STEP I

1. PLACE BITUMINOUS MAT, LENGTH 36 TIMES THE THICKNESS OF THE MAT BEING PLACED PAST THE PROPOSED TRANSVERSE JOINT LOCATION USING NORMAL OPERATING PROCEDURES.
2. EXTREME CARE SHOULD BE TAKEN TO MAINTAIN ENOUGH MATERIAL IN FRONT OF THE SCREED TO MAINTAIN REQUIRED PAVING DEPTH.




STEP III

1. JOINT PAPER OR OTHER PRESELECTED JOINT MATERIAL IS THEN PLACED IN THE CLEARED AREA AND THE EXCESS ASPHALT USED TO HAND FORM A TRANSITION TO THE DIMENSIONS SHOWN ABOVE.
2. NOTE THAT IN CONSTRUCTING THE TRANSITION, THE MAT DEPTH IS CONTINUED AS PART OF THE TRANSITION BEFORE FORMING THE FEATHER.



STEP II

1. MOVE THE PAVER OUT OF THE WAY AND REMOVE THE ASPHALT FROM THE AREA OF THE PROPOSED TEMPORARY BITUMINOUS CONCRETE TRANSITION.
2. SQUARE UP THE END OF THE MAT WITH A RAKE OR LUTE.
3. NOTE THAT THE MAT WITHIN 4' OF THE END OF JOINT IS NOT TO BE ROLLED AT THIS TIME.



STEP IV


1. COMPLETE TEMPORARY TRANSITION BY ROLLING.
2. TO RESUME PAVING, AT THE JOINT, REMOVE TEMPORARY TRANSITION AND DISPOSE OF THE MATERIAL ACCORDING TO ART. 202.03 OF THE STD. SPECS. (COST INCLUDED IN THE CONTRACT).
3. CONSTRUCTING THE TEMPORARY TRANSITIONS WILL BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE BITUMINOUS MATERIAL BEING PLACED.

REVISIONS	DATE	BY

STD 9-26

ILLINOIS STANDARD

W21-1116




COLOR	LEGEND AND BORDER BACKGROUND	BLACK ORANGE	NON-REFLECTORIZED REFLECTORIZED
-------	------------------------------	--------------	---------------------------------

SIGN SIZE	DIMENSIONS															
	A	B	C	D	E	F	G	H	J	K	L	M	N	O	P	
60x48	60.00	48.00	3.00	48.80	42.60	5.10	31.50	50.00	28.90	15.80	6.90	15.20	16.80	12.00	10.00	

SIGN SIZE	SERIES BY LINE				MARGIN	BORDER
	1	2	3	4		
60x48	60	60	60	60	0.75	1.25

ALL DIMENSIONS IN INCHES. SIGN NOT TO SCALE.

PIPE CULVERT (EROSION CONTROL)



PLAN VIEW

END VIEW

PIPE FOR USE AS PIPE CULVERT (EROSION CONTROL) MAY BE EITHER A METAL OR PLASTIC CULVERT PIPE THAT CONFORMS TO SECTION 542.02 OF THE STANDARD SPECIFICATIONS AND SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR PIPE CULVERT (EROSION CONTROL). IN SOME CASES IT MAY BE NECESSARY TO SECURE PIPE TO THE FILL SLOPE TO OBTAIN PROPER ANCHORAGE. MATERIALS USED FOR THIS PURPOSE SHALL BE CONSIDERED INCLUDED IN THE COST OF THE PIPE.

END SECTIONS SHALL BE INSTALLED AT THE INLET END. THIS ITEM SHALL BE PERFORMED AND PAID FOR AS SPECIFIED FOR END SECTIONS IN ARTICLES 542.07 AND 542.11 OF THE STANDARD SPECIFICATIONS; EXCEPT, ONLY METAL END SECTIONS AS SHOWN ON STANDARD 542401 WILL BE PERMITTED, AND THE WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR METAL END SECTIONS OF THE DIAMETER SPECIFIED IN THE PLANS.

TEMPORARY RIPRAP AT THE OUTLET END MAY BE END DUMPED AND SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON FOR AGGREGATE (EROSION CONTROL).

NOTE: REMOVAL OF PIPE CULVERT (EROSION CONTROL), END SECTION, PERIMETER EROSION BARRIER, FENCE (EROSION CONTROL) IF NOTED IN PLANS, AND AGGREGATE (EROSION CONTROL), SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE EROSION CONTROL ITEMS.

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
TEMPORARY BITUMINOUS CONCRETE TRANSITIONS; PIPE CULVERT (EROSION CONTROL); ILLINOIS STANDARD W21-1116
 SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY

PLOT DATE = 10/14/2006
 FILE NAME = c:\p3\proj\p3\1116\1116.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = haecon


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	825
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* I-57, & OLD IL 13 (FAU 9629)
 ** (X1-6-2)VB-2,(X1-6)HBK-2

DETAIL OF TEMPORARY SEDIMENT BASIN



SECTION A-A




PLAN

NOTES

1. STONE RIPRAP CLASS A3 USED AS SHOWN WILL BE PAID FOR AS AGGREGATE (EROSION CONTROL), TON
2. THE AGGREGATE (EROSION CONTROL) MAY BE REUSED TO LINE DITCH AS DIRECTED BY THE ENGINEER AFTER ALL PERMANENT SEEDING IS IN PLACE.


TEMPORARY DITCH CHECKS

PLACEMENT OF TEMPORARY STRAW BALE DITCH CHECK IN DRAINAGEWAY



POINTS A SHOULD BE HIGHER THAN POINT B

SPACING BETWEEN TEMPORARY DITCH CHECKS




L = THE DISTANCE SUCH THAT POINTS A AND B ARE OF EQUAL ELEVATION
 B = THE LOW POINT IN CENTER OF CHECK

REVISIONS	DATE
DRAWN	9-01-99
REVISOR	10-3-01
REVISOR	
REVISOR	

STD. 9-108

TYPICAL DETAIL OF STONE RIPRAP DITCH LINING



NOTES

THIS WORK INCLUDES THE EARTH EXCAVATION REQUIRED TO PLACE THE RIPRAP AS SHOWN. THE MATERIAL RESULTING FROM THE EARTH EXCAVATION SHALL BE PLACED IN THE ROADWAY EMBANKMENT, OR WASTED AS DIRECTED BY THE ENGINEER. THE EARTHWORK SHALL BE CONSIDERED INCLUDED IN THE COST OF THE DITCH.

THE RIPRAP DITCH SHALL BE CONSTRUCTED AT THE LOCATIONS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION OF THE STONE RIPRAP DITCH SHALL CONFORM TO THE REQUIREMENTS FOR CLASS A4 RIPRAP AS INDICATED IN SECTION 281 OF STANDARD SPECIFICATIONS.

THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQ YD FOR STONE RIPRAP, CLASS A4, WHICH PRICE SHALL INCLUDE ALL MATERIAL, LABOR AND EQUIPMENT TO COMPLETE THE WORK IN PLACE AS SHOWN.


BEDDING MATERIAL AND FILTER FABRIC AS SPECIFIED IN SECTION 281 OF THE STANDARD SPECIFICATIONS WILL NOT BE REQUIRED.

THE WIDTH OF THE RIPRAP DITCH WILL BE AS SPECIFIED IN THE RIPRAP SCHEDULE OR AS DIRECTED BY THE ENGINEER.


NOT NEEDED

DETAILS OF CONCRETE COLLAR

PIPE TO PIPE



SIDE VIEW



END VIEW

TABULATION

DIAMETER OF PIPE	CL SI CONC CU YDS EST
12"	0.24
15"	0.29
18"	0.32
24"	0.44
30"	0.56
36"	0.66
42"	0.80
48"	0.93
54"	1.07
60"	1.22
72"	1.55

THE CONCRETE COLLAR SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR CONCRETE COLLAR, AS SHOWN ON THE PLANS, WHICH PRICE SHALL INCLUDE THE REMOVAL OF SUCH PORTIONS THE EXISTING HEADWALLS AS MAY BE REQUIRED.

CLASS SI CONCRETE SHALL BE USED THROUGHOUT.

REVISIONS	DATE
DRAWN	7-13-90
REVISOR	8-22-94
REVISOR	
REVISOR	

STD. 9-79

REVISIONS	DATE
NAME	

ILLINOIS DEPARTMENT OF TRANSPORTATION

DETAILS:
 TEMPORARY SEDIMENT BASIN; ~~TYPICAL OF STONE RIPRAP DITCH LINING;~~
 TEMPORARY DITCH CHECKS;
 CONCRETE COLLAR (PIPE TO PIPE)

SCALE: VERT. NO SCALE
 HORIZ. NO SCALE

DRAWN BY
 CHECKED BY

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	826
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				


PERIMETER EROSION BARRIER

SEE SCHEDULE FOR LOCATION

&

FENCE (EROSION CONTROL)


SEE PLAN SHEETS , AND SCHEDULE FOR LOCATION.



SECTIONAL VIEW OF INSTALLATION


THIS WORK SHALL COMPLY WITH ALL REQUIREMENTS OF SECTION 280 OF THE STANDARD SPECIFICATION FOR TEMPORARY EROSION CONTROL.

ENERGY DISSIPATOR



D= INSIDE DIAMETER OF PIPE CULVERT OR CLEAR HEIGHT OF BOX CULVERT

PLAN



SECTION A-A

EARTH EXCAVATION FOR ENERGY DISSIPATOR

THIS WORK INVOLVES THE EXCAVATION OF EARTH AS SHOWN IN THE SKETCH TO THE LENGTH, WIDTH, AND DEPTH AS SPECIFIED. THE EARTH EXCAVATION WILL BE UTILIZED IN THE ROADWAY EMBANKMENT OR WASTED AS DIRECTED BY THE ENGINEER.

EARTHWORK WILL BE CONSIDERED INCLUDED IN THE COST OF THE RIPRAP.

ENERGY DISSIPATOR IS TO BE CONSTRUCTED AT THE LOCATION INDICATED ON THE PLAN SHEETS.

RIPRAP FOR ENERGY DISSIPATOR

RIPRAP FOR ENERGY DISSIPATOR SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 281 OF THE STANDARD SPECIFICATIONS EXCEPT AS REVISED HEREIN.

THE LENGTH, WIDTH, AND DEPTH FOR RIPRAP PLACEMENT SHALL BE AS SPECIFIED IN THESE DETAILS, UNLESS OTHERWISE INDICATED IN THE PLANS.

THE RIPRAP FOR THE ENERGY DISSIPATOR SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD FOR **STONE DUMPED RIPRAP, CLASS A4**


FILTER FABRIC AND BEDDING MATERIAL AS SPECIFIED IN SECTION 281 OF THE STANDARD SPECIFICATIONS WILL NOT BE REQUIRED.

REVISIONS	
REB'D	2-15-89
REVISED	11-3-93
REVISED	8-15-94
STD 9-6	

NOT NEEDED

DETAIL STONE RIPRAP DITCH

(ON EXISTING PAVED DITCH)




TO BE USED:
SEE RIPRAP SCHEDULE

NOTE: THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON, FOR **STONE RIPRAP DITCH**, WHICH PRICE SHALL INCLUDE ALL MATERIAL LABOR AND EQUIPMENT TO COMPLETE THE WORK IN PLACE AS SHOWN.

THE FINISHED SIDESLOPES OF THE STONE RIPRAP DITCH SHALL MATCH THE EXISTING GRADE.

TYPICAL DETAIL OF STONE RIPRAP DITCH LINING



NOTES

THIS WORK INCLUDES THE EARTH EXCAVATION REQUIRED TO PLACE THE RIPRAP AS SHOWN. THE MATERIAL RESULTING FROM THE EARTH EXCAVATION SHALL BE PLACED IN THE ROADWAY EMBANKMENT, OR WASTED AS DIRECTED BY THE ENGINEER. THE EARTHWORK SHALL BE CONSIDERED INCLUDED IN THE COST OF THE DITCH.

THE RIPRAP DITCH SHALL BE CONSTRUCTED AT THE LOCATIONS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION OF THE STONE RIPRAP DITCH SHALL CONFORM TO THE REQUIREMENTS FOR CLASS A4 RIPRAP AS INDICATED IN SECTION 281 OF STANDARD SPECIFICATIONS.

THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON FOR **STONE RIPRAP, CLASS A4**, WHICH PRICE SHALL INCLUDE ALL MATERIAL, LABOR AND EQUIPMENT TO COMPLETE THE WORK IN PLACE AS SHOWN.

BEDDING MATERIAL AND FILTER FABRIC AS SPECIFIED IN SECTION 281 OF THE STANDARD SPECIFICATIONS WILL NOT BE REQUIRED.

THE WIDTH OF THE RIPRAP DITCH WILL BE AS SPECIFIED IN THE RIPRAP SCHEDULE OR AS DIRECTED BY THE ENGINEER.

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS:
PERIMETER EROSION BARRIER; STONE RIPRAP DITCH LINING;
~~ENERGY DISSIPATOR; STONE RIPRAP DITCH~~

SCALE: VERT. NONE
HORIZ.

DRAWN BY CNH
CHECKED BY

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	827
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)VB-2,(X1-6)HBK-2				

DETAILS OF PERMANENT SURVEY MARKERS




NOTES

- ACTUAL LOCATIONS TO BE DETERMINED BY THE ENGINEER AND A REPRESENTATIVE FROM THE BUREAU OF DESIGN AFTER GRADING IS COMPLETE AND SIGHT DISTANCE CAN BE DETERMINED BETWEEN SURVEY MARKER LOCATIONS.
- THE MARKERS SHALL BE PRECAST AND SHALL BE INSTALLED IN A WORKMANLIKE MANNER IN ORDER THAT THERE BE NO FUTURE SETTLEMENT OR HORIZONTAL SHIFTING. THE MONUMENT SHALL BE PLACED IN A WAY THAT THE SURVEY POINT WILL FALL WITHIN THE PORTION OF THE PLAQUE PROVIDED FOR THAT PURPOSE. A REPRESENTATIVE FROM THE BUREAU OF PROGRAM DEVELOPMENT WILL LOCATE AND ETCH THE SURVEY POINT ON THE TABLET.
- THE CONTRACT UNIT PRICE FOR PERMANENT SURVEY MARKERS WILL BE PAYMENT IN FULL FOR FURNISHING AND INSTALLING THE MARKER.

TOTAL QUANTITY FOR PERMANENT SURVEY MARKERS=


DESIGN NOTE: 2000' SPACING DESIRABLE FOR RURAL
1000' SPACING DESIRABLE FOR URBAN



REVISIONS	
REDRAWN	2-15-89
REVISED	5-11-89
REVISED	8-18-94
REVISED	10-3-94

STD. 9-10

EXPANSION BOLTS REQUIRED FOR CULVERT EXTENSIONS



EXPANSION BOLTS SHALL CONSIST OF SELF DRILLING EXPANSION SHIELDS AND 3/4" Ø HOOKED BOLTS. HOOKED BOLTS SHALL EXTEND A MINIMUM OF 9" INTO NEW CONCRETE.

MINIMUM CERTIFIED PROOF LOAD=7500 LBS.

BOLTS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR EXPANSION BOLTS, 3/4" INCH.

H OR S	EXTENSION < 15'		EXTENSION > 15'	
	NO.	SPACING	NO.	SPACING
2.0	*	*	*	*
2.5	2	18"	2	18"
3.0	2	24"	2	24"
4.0	3	18"	3	18"
5.0	4	16"	3	24"
6.0	5	15"	4	20"
7.0	5	18"	4	24"
8.0	6	17"	5	21"
9.0	6	19"	5	24"
10.0	7	18"	6	21"
11.0	8	17"	6	24"
12.0	8	19"	7	22"

* NOTE: USE MINIMUM OF 1 EXPANSION BOLT AT EACH CORNER.

CROSS SECTION THRU BARREL


FOR ANCHOR BOLT REQUIREMENTS, SEE ARTICLE 1006.09 OF THE STANDARD SPECIFICATIONS.

EXAMPLE:
6' X 4' BOX CULVERT TO BE EXTENDED 18' AT ONE END ONLY.
FROM TABLE FIND:
6' SIDE REQUIRES (4)-3/4" Ø EXPANSION BOLTS AT 20" CENTERS
4' SIDE REQUIRES (3)-3/4" Ø EXPANSION BOLTS AT 18" CENTERS
TOTAL NO. REQUIRED
(4+3)2 = (14)-3/4" Ø EXPLAN. BOLTS

REVISIONS	
REDRAWN	2-15-89
REVISED	8-15-94
REVISED	12-14-01

STD. 9-9

SEEDING & MULCHING



GENERAL NOTES

IN GENERAL, ALL EARTH SURFACES DISTURBED DURING CONSTRUCTION OPERATIONS SHALL BE SEEDED AND MULCHED UPON COMPLETION OF ALL GRADING OPERATIONS.

FERTILIZER NUTRIENTS AND LIMESTONE SHALL BE APPLIED TO ALL SEEDED AREAS.

THE RATES OF APPLICATION OF FERTILIZER, MULCH AND LIME-STONE SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS.

SECTIONS 250 AND 251 OF THE STANDARD SPECIFICATIONS SHALL GOVERN THIS WORK EXCEPT AS SPECIFIED HEREIN OR AS NOTED IN THE SPECIAL PROVISIONS.

STD. 9-12

REVISIONS	
REDRAWN	2-15-89
REVISED	8-15-94
REVISED	6-3-99
REVISED	


REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	DETAILS:	
		PERMANENT SURVEY MARKERS; EXPANSION BOLTS REQUIRED FOR CULVERT EXTENSIONS; SEEDING AND MULCHING	
		SCALE: VERT. NO SCALE	DRAWN BY
		DATE	CHECKED BY

PLOT DATE: 10/14/2006
 FILE NAME: c:\p\projects\98950\98950.dgn
 SCALE: 1/4" = 1'-0"
 USER: hnie

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	828
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HDK-2				


BRIDGE APPROACH SLAB ON RUBBLIZED PAVEMENT

FOR SN 100-0084 AND SN 100-0085 IN I-57 STAGE 7




BRIDGE APPROACH SLAB (MEDIAN PAVED SHOULDER)

FOR SN 100-0084 AND SN 100-0085 IN I-57 STAGE 7




**STAGE 4
BRIDGE APPROACH SLAB ON PROPOSED WIDENING**

FOR SN 100-0084 AND SN 100-0085
SIMILAR FOR SN 100-0086 AND SN 100-0087



BRIDGE APPROACH SLAB (MEDIAN PAVED SHOULDER)

FOR SN 100-0086 AND SN 100-0087 IN I-57 STAGE 4 AND 7



REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION

**DETAILS:
BRIDGE APPROACH SLAB**


SCALE: VERT. NO SCALE
HORIZ. NO SCALE

DRAWN BY CNH
CHECKED BY


CONTRACT NO. 98950				
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	829
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* I-57, & OLD IL 13 (FAU 9629)				
* (X1-6-2)VB-2,(X1-6)HBK-2				



PLAN



RESURFACING



NEW CONSTRUCTION

GENERAL NOTES
 See Standard 482001, 482006 or 483001 for details not shown.
 All dimensions are in millimeters (inches) unless otherwise shown.


REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PCC /BITUMINOUS STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
STANDARD 630201-03
 SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY

PLOT DATE = 10/14/2005
 FILE NAME = c:\pcc\pcc\std630201-03.dgn
 USER NAME = mason


CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	830
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* I-57, & OLD IL 13 (FAU 9629)				
** (X1-6-2)WB-2,(X1-6)HBK-2				



SECTION A-A

END VIEW



PLAN

GENERAL NOTES

Build tops of headwalls parallel to grade line.
 When lapping sheets of welded wire fabric, the overlap measured between the outermost cross wires of each fabric sheet shall not be less than 202 mm (8").
 All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).

WELDED WIRE FABRIC	59 SQ. YDS.
CONCRETE SUPERSTRUCTURE	9.5 CU. YDS.

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION
**CAST-IN-PLACE REINFORCED CONCRETE
 END SECTIONS 72"
 20° SKEWED WITH ROADWAY
 RT. & LT. STA. 1514+00**

SCALE: VERT. NONE
 HORIZ.
 DATE
 DRAWN BY CNH
 CHECKED BY


PLOT DATE = 12/14/2006
 FILE NAME = c:\pwork\c98\c98282c\c98282c.dwg
 SCALE = 1/8" = 1'-0"
 USER NAME = jason

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	*	WILLIAMSON	917	B30A
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		


I-57, OLD ILL. 13 (FAU 9629)
 ** (X1-6-2) VB-2, (X1-6) HBK-2




BEARING PLATE K




PLAN



WOOD POST




ELEVATION




YOKE

5 (3/8) thick steel



CABLE STRUT



STEEL TUBE




PLATE WASHER F

GENERAL NOTES

See Standard 630001 for details of guardrail not shown.

The bearing plate K shall be held in position by (2) two eight penny nails driven into the post and bent over the top of the plate.

All dimensions are in millimeters (inches) unless otherwise shown.


TRAFFIC BARRIER TERMINAL, TYPE 2

DETAIL

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	831

STA.	TO STA.
------	---------

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
* I-57, & OLD IL 13 (FAU 9629)
** (X1-6-2)VB-2, (X1-6)HBK-2



ON



PLT DATE = 12/07/2006
PLT SCALE = 1/8\"/>

PARCEL NO.	NAME	ACREAGE:	TE
8	VETERAN'S HOSPITAL	0.342±	
9	HARRY CRISP	0.364±	
9A	HARRY CRISP	0.099±	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

R.O.W.


SCALE: VERT. 1/8\"/>

DRAWN BY CNH
CHECKED BY LAND AC

STATE OF ILLINOIS
DEPARTMENT OF PUBLIC WORKS & BUILDINGS
DIVISION OF HIGHWAYS

F.A. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 1
*	**	WILLIAMSON	9/7	832	16 SHEETS
STA.	TO STA.				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT			

BM : Bolt Top in R.R. Bridge 4' Rt. Sta. 1516+71 E
Elev. 438.17
No Existing Highway Structure Culvert under R.R.
at \bar{C} of E. Lane to be filled in by others.



STATION 1516+58.58
BUILT 19 BY
STATE OF ILLINOIS
F.A. PROJ. 16-57-1(32)
LOADING H 20-S16 & ALT.

GENERAL NOTES



- Class X Concrete shall be used throughout except in handrail end posts.
- Handrail Concrete shall be used in handrail end posts.
- The Concrete floor slab shall be finished in accordance with Article 51.19 of the Standard Specifications.
- Slope wall shall be reinforced with welded wire fabric 6"x6" mesh, #4 wire, weighing 58# per 100 sq. ft.
- Rivets 3/4", Open holes 1 1/8", unless noted.
- Railings shall be adjusted to true alignment after curbs have been poured.
- All rockers, bolsters bearing plates, lead plates, pintles and anchor bolts shall be fabricated and set in accordance with Article 51.15 of the Standard Specifications and are included in quantity of structural steel.
- Anchor bolts shall be set before riveting diaphragms over supports.
- All steel handrail posts shall be vertical.
- Expansion guards shall be fabricated and erected in accordance with Article 51.13 (d) of the Standard Specifications.
- Expansion guards are included in quantity of structural steel. Est. weight 4800 lbs.
- The following surfaces of expansion guards shall be given two shop coats of red lead paint: Outside face of vertical legs and top face of horizontal legs of 4"x4"x 1/2" x 2". Except as otherwise provided, all structural steel shall receive one shop coat of red lead paint and two field coats of aluminum paint. See Articles 56.1 to 56.5 inclusive of the Standard Specifications.
- All paint shall be furnished and applied by the Contractor.
- Holes for concrete piles at all abutments shall be precored in accordance with Article 60.9 (c) of the Standard Specifications.
- The contractor shall drive one timber test pile near pier #1 of the east bridge and one concrete test pile of the south abutment of the west bridge.

NAME PLATE LETTERING
See Sid. 2113

APPROACH PILE DATA
Type : Creosoted
Capacity : 15 tons
Est. Length : 40'-0"
No. Required : 32

NOTE : 1/2" Prem. Jt. Filler shall be placed between Slope wall and Abutment caps.


ELEVATION




PROFILE OF NORTH R.R. DITCH

DESIGN STRESSES
fc = 1400 psi Super.
vc = 75 psi (Figs)
fs = 20,000 psi Reinf.
fs = 18,000 psi Struct.
n = 10



LOADING : H20-S16-44
And Alternate




SECTION A-A



SECTION B-B



LOCATION PLAN



SITE PLAN

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Class X Concrete	Cu.Yds.	378.2	618.0	996.2
Handrail Concrete	Cu.Yds.	5.0		5.0
Reinforcement Bars	Lbs.	73,300	49,240	122,540
Structural Steel	Lbs.	398,960		398,960
Borrow Excavation	Cu.Yds.		50,120	50,120
Class A Excavation for Str.	Cu.Yds.		240	240
Metal Handrail	Lin.Ft.	607		607
Slope wall (4")	Sq.Yds.	925		925
Name Plates	Each	2		2
Concrete Piles	Lin.Ft.		2,257	2,257
Test Piles (Concrete)	Each		1	1
Creosoted Piles	Lin.Ft.		3,170	3,170
Test Piles (Timber)	Each		1	1

FOR INFORMATION ONLY
GENERAL PLAN
I.C.R.R. OVERHEAD-WEST OF MARION
PROJECT 16-57-1(32) 52
F.A.I. RT. 57 - SEC. XI-6VB
WILLIAMSON COUNTY
STA. 1516+58.58

DESIGNED William R. Smith
CHECKED T. Tanaka
DRAWN Gabor Papp
CHECKED T. Tanaka
EXAMINED J. McComine
PASSED
APPROVED R. R. Bateman


NOTE : All transverse deck dimensions taken at backs of abuts. on plan view @ rt. +s to \bar{C} Rdwy.

Revised - 1/14/60 - WJM - At north Abut. (in ELEVATION) changed Embankment from 4250 to 2085 Cu.Yds. & Borrow Exc. from 4980 to 2950 Cu.Yds. at south Abut. changed Embankment from 1870 to 2080 Cu.Yds. & Borrow Exc. from 2100 to 2960 Cu.Yds. In APPROACH PILE DATA, changed estimated length from 20 to 40 Lin. Ft. In TOTAL BILL OF MATERIAL, changed quantity of Borrow Exc. from 41780 to 50120 Cu.Yds. & the quantity of Creosoted Piles from 2550 to 3170 Lin. Ft.
Revised - 1/12/60 R.D. Changed quantities of Class X Conc. on Bill of Material.
Quantity of Borrow Excavation Revised - 2/17/60 R.S.B.

R.M.: C Spikes in p.p. C.C.O. Rt. Sta. 1530+00 E.
Elev. 453.96.
No Existing Structure.

STATE OF ILLINOIS
DEPARTMENT OF PUBLIC WORKS & BUILDINGS
DIVISION OF HIGHWAYS

CONTRACT NO. 98950		TOTAL SHEETS	SHEET NO.
F.A. RTE.	SECTION	COUNTY	917 833
STA.	TO STA.	WILLIAMSON	
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	ROUTE NO.	SECTION
		1-2	45 25
		BLANKS	FED. AID PROJECT



GENERAL NOTES



Class X Concrete shall be used throughout except in End Posts.
Handrail Concrete shall be used in End Posts.
The concrete floor slab shall be finished in accordance with Article 5113 of the Standard Specifications.
Slope Wall shall be reinforced with welded wire fabric 6x6 mesh, #4 wires, weighing 53 per 100 sq.ft.
Elevts 3/8, Open holes 3/8, unless noted.
All rollers, rockers, bearing plates, lead plates, pintles, and anchor bolts shall be fabricated and set in accordance with Article 5115 of the Standard Specifications and are included in quantity of Structural Steel. Est'd Weight 20110 lbs.
Anchor bolts shall be set before riveting diaphragms over supports.
The following surfaces of expansion guards shall be given two shop coats of red lead paint; All surfaces inaccessible after erection. The 3/8 welded studs shall not be painted.
Expansion guards and all studs are included in quantity of Structural Steel. Est'd Weight 4990 lbs.
Except as otherwise provided all Structural Steel shall receive one shop coat of red lead paint and two field coats of aluminum paint. See Articles 55.1 to 55.5 inclusive of the Standard Specifications.
All paint shall be furnished and applied by the Contractor.
The Contractor shall drive 4-Steel Test Piles in permanent locations as directed by the Engineer before ordering remainder of piles; test piles shall be driven in the following locations:
East Lanes - One at N. Abut. and one at Pier C.
West Lanes - One at Pier I and one at S. Abut.

TOTAL BILL OF MATERIALS - SEC. XI-6HF-E

Furnishing Structural Steel	Lbs.	427160	427160
-----------------------------	------	--------	--------


TOTAL BILL OF MATERIALS - SEC. XI-6HB-E

Item	Super	Sub	Total
Class X Concrete	Cu. Yds.	365.8	783.2
Handrail Concrete	Cu. Yds.	5.8	5.8
Reinforcement Bars	Lbs.	71790	110000
Erecting Structural Steel	Lbs.	427160	427160
Steel Piles	Lin. Ft.		2916
Test Piles (Steel)	Each		4
Crossed Timber Piles	Lin. Ft.		620
Furnishing Erecting Metal Handrail	Lin. Ft.	607	607
Name Plates	Each	2	2
Borrow Excavation	Cu. Yds.		3800
Earth Excavation	Cu. Yds.		8840
Slope Wall	Sq. Yds.		820
Class A Excavation for Structures	Cu. Yds.		264



1530+00.00 (E. Lanes)
1529+97.69 (W. Lanes)

STATION (See Above)
BUILT 19 BY
STATE OF ILLINOIS
FAI. RT. 57 - SEC. XI-6HB-E
FA. PROJECT I-57-1(18)
LOADING HCO-316-44 & ALT.




DESIGNED: *abnall*
CHECKED: *Mario S. Revilla*
DRAWN: *W.L. Jacobs*
CHECKED: *MPC.*

APRIL 29 19 59
EXAMINED: *M. R. ...*
PASSED: *...*
APPROVED: *R. ...*

Note: All transverse deck dimensions taken at backs of abutments on plan view.

DESIGN STRESSES
f_c = 1400 psi Super
f_s = 20,000 psi Reinf.
f_s = 18,000 psi Struct.
v_c = 75 psi Ftg.
n = 10
LOADING HCO-316-44 & ALT.

Revised: 1-8-60. Quantity of Class-X concrete from 772.7 to 783.2 cu. yds. due to change in curb height to 11" W.B.




FOR INFORMATION ONLY

GENERAL PLAN & ELEVATION
FAI. RT. 57 OVER S.B.I.R. 13
PROJECT I-57-1(18)52
WILLIAMSON COUNTY
STA. 1529+91.00(E)

Benchmark: Painted mark on top of West corner of South Abutment, existing S.N. 100-0007 (S.B.) Sta. 1517+35.43, 55.5' Rt. @ F.A.I. 57, Elev. 469.42

Exist. Struct.: S.N. 100-0006 (N.B.) and S.N. 100-0007 (S.B.)
 The existing structures were built in 1961 under F.A.I. Route 57 Section XI-6VB. Both structures consist of three continuous spans (47'-3", 55'-4", 47'-3") for a total length of 153'-6" measured back to back of abutments. The superstructures have a 7" reinforced concrete deck on non-composite wide flange beams. The superstructures are supported by hammerhead piers on pile supported footings and pile bent abutments. The out to out deck width of the Northbound structure varies from 53'-4 1/4" to 55'-7". The out to out deck width of the Southbound structure varies from 37'-9 5/8" to 42'-10 7/8".
 The existing structures shall be removed and replaced using stage construction to maintain traffic.

Salvage: See Special Provisions for salvage information.



ROUTE NO.	SECTION	COUNTY	DATE	SHEET NO.
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	917	334
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT-				


Contract #98950

DESIGN SPECIFICATIONS
 2004 AASHTO LRFD Bridge Design Specifications with 2005-2006 Interims

DESIGN STRESSES
FIELD UNITS
 f'c = 3,500 psi
 fy = 60,000 psi (reinf.)
 fy = 50,000 psi (M270 Grade 50)
 fy = 36,000 psi (M270 Grade 36)

LOADING HL-93
 Allow 50 psf for future wearing surface.


SEISMIC DATA
 Seismic Performance Zone (SPZ): 2
 Bedrock Acceleration Coefficient (A): 12.2%
 Site Coefficient (S) = 1.5 (Type III)



INDEX OF SHEETS

1. General Plan & Elevation
2. General Data
- 3.-4. Stage Construction Details
5. Temporary Concrete Barrier
- 6.-11. Top of Slab Elevations
- 12.-17. Superstructure
18. Parapet Elevation
19. Superstructure Details
- 20.-24. Diaphragm Details
- 25.-26. Framing Plan
- 27.-28. Structural Steel Details
29. Bearing Details
30. Anchor Bolt
- 31.-34. North Abutments
- 35.-38. South Abutments
- 39.-42. Pier 1
- 43.-46. Pier 2
47. Pier Details
48. Bar Splicer Assembly Details
49. Pile Layout at Piers
- 50.-51. Boring Logs


* Ramp "E" baseline
 Note: The N.B. taper of the ramp baseline begins at Sta. 1511+69.48, offset 24.00' Lt. and ends at Sta. 1517+84.36, offset 36.30' Lt.



*Ramp gore varies: 4'-6 1/2" (N. Abut.) to 7'-2 1/2" (S. Abut.)

Baseline stations are based on geometrics established in October 2002 and adjusted to closely match existing plans

** Ramp gore varies: 3'-5 1/2" (N. Abut.) to 12'-8 1/2" (S. Abut.)



** Ramp "F" Baseline
 Note: The S.B. taper of the ramp baseline begins at Sta. 1514+84.32, offset 24.00' Rt. and ends at Sta. 1519+38.03, offset 55.73' Rt.

DESIGNED	Michael D. Conn
CHECKED	Fredrick J. K... ..
DRAWN	B.M.L.
CHECKED	MDC, FT

JANUARY 25, 2007
 EXAMINED: Thomas J.
 PASSED: Ralph E.
 ENGINEER OF BRIDGES AND STRUCTURES



EXPIRES 11-30-2008

GENERAL PLAN & ELEVATION
INTERSTATE 57 OVER
C.O. & E. R.R.
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

Note: See sheet 2 of 51 for Sections A-A and B-B.

GENERAL NOTES

Fasteners shall be AASHTO M164 Type 1, mechanically galvanized bolts. Bolts $\frac{7}{8}$ " ϕ , holes $\frac{5}{16}$ " ϕ , unless otherwise noted.
 Calculated weight of Structural Steel = AASHTO M270 Grade 50 = 326,560 lbs.
 AASHTO M270 Grade 36 = 45,810 lbs.

No field welding is permitted except as specified in the contract documents.
 Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60 (IL Modified). See Special Provisions

Reinforcement bars designated (E) shall be epoxy coated.
 Bearing seat surfaces shall be constructed or adjusted to their designated elevations within a tolerance of $\frac{1}{8}$ inch (0.01 ft.). Adjustment shall be made either by grinding the surface or by shimming the bearings.

The Inorganic Zinc Rich Primer / Acrylic / Acrylic Paint System shall be used for shop and field painting of new structural steel except where otherwise noted. The color of the final finish coat for all interior steel surfaces shall be gray, Munsell No. 5B 7/L. The color of the final finish coat for the exterior and bottom flange of the fascia beams shall be blue, Munsell No. 10B 3/6. See Special Provision for "Cleaning and Painting New Metal Structures".

The embankment configuration shown shall be the minimum that must be placed and compacted prior to construction of the abutments.

The Contractor shall drive test piles to 110% of the nominal required bearing specified in production locations at substructures specified or approved by the Engineer before ordering the remainder of piles.

The steel H-piles shall be according to AASHTO M270 Grade 50.

The main load carrying member components subject to tensile stress shall conform to the Supplemental Requirements for Notch Toughness Zone 2. These components are the wide flange beams and all splice plate material except fill plates.

The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.

The Contractor shall remove portions of the existing pier footings to allow driving of the new pier piles. See sheet 3 of 51 for removal details. Cost included with Removal of Existing Structures No. 3 and No. 4.


Cost of removal of the existing slopewall for each structure is included in the pay item Removal of Existing Structures No. 3 or No. 4 respectively.

In addition to all other requirements of Section 512 of the Standard Specifications, splices for HP14x73 piles shall develop the full capacity of the steel's cross sectional area of the pile for tension, shear and bending forces. One approved method of achieving this requirement is full penetration butt welding of the entire cross section. Other types of splices meeting the full capacity requirement may be allowed subject to the approval of the Engineer. Any proposal by the Contractor to use an alternate splice method must include adequate documentation demonstrating that the full tension, shear and bending capacities will be met. Appropriate welder qualifications will be required for the positions and processes used in splicing all piles. Nondestructive testing of completed welds will be limited to visual inspection.

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	835	51 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	

Contract #98950



STATION 1516+58.56
 BUILT 200 BY
 STATE OF ILLINOIS
 FAI ROUTE 57 - SEC (XI-6-2)VB-2
 LOADING HL-93
 STR. NO. 100-0086 (N.B.)


STATION 1516+58.56
 BUILT 200 BY
 STATE OF ILLINOIS
 FAI ROUTE 57 - SEC (XI-6-2)VB-2
 LOADING HL-93
 STR. NO. 100-0087 (S.B.)

NAME PLATES
 See Std. 515001

TOTAL BILL OF MATERIAL



ITEM	UNIT	SUPER	SUB	TOTAL
Porous Granular Embankment (Special)	Cu. Yd.			398
** Removal of Existing Structures No. 3	Each			1
** Removal of Existing Structures No. 4	Each			1
Structure Excavation	Cu. Yd.		1248	1248
Concrete Structures	Cu. Yd.		735.5	735.5
Concrete Superstructure	Cu. Yd.	645.6		645.6
Bridge Deck Grooving	Sq. Yd.	2155		2155
Protective Coat	Sq. Yd.	2450		2450
Furnishing and Erecting Structural Steel	LS	0.3		0.3
Stud Shear Connectors	Each	13,041		13,041
Reinforcement Bars, Epoxy Coated	Pound	157,020	60,110	217,130
Bituminous Coated Aggregate Slopewall, 6"	Sq. Yd.			2020
Furnishing Steel Piles HP14x73	Foot		5340	5340
Driving Piles	Foot		5340	5340
Test Pile Steel HP14x73	Each		3	3
Name Plates	Each	2		2
Geocomposite Wall Drain	Sq. Yd.			241
Pipe Underdrains for Structures, 4"	Foot		370	370
Bar Splicers	Each	1180	292	1472
Protective Shield	Sq. Yd.			565
Floor Drains	Each	16		16
Temporary Sheet Piling	Sq. Ft.		700	700
Slopewall, 4"	Sq. Yd.			225.0
Conduit Embedded in Structure, 2" ϕ PVC	Foot	133.0		133.0
Anchor Bolt, 1"	Each		184	184
Concrete Encasement	Cu. Yd.		20.4	20.4
Preformed Joint Seal, 2 1/2"	Foot	133.0		133.0

** Structure No. 3 is Northbound
 ** Structure No. 4 is Southbound



* Included in the cost of Pipe Underdrains for Structures, 4".

Notes:
 All drainage system components shall extend to 2'-0" from the end of each wingwall except an outlet pipe shall extend until intersecting with the side slopes. The pipes shall drain into concrete headwalls. (See Article 601.05 of the Standard Specifications and Highway Standard 601101).
 Slope wall, 4" shall be reinforced with welded wire fabric, 6" x 6" - W4.0 x W4.0, weighing 58 lbs. per 100 sq. ft.



GENERAL DATA
 F.A.I. RT. 57 SEC. (XI-6-2)VB-2
 WILLIAMSON COUNTY
 STA. 1516+58.56
 S.N. 100-0086 (N.B.)
 S.N. 100-0087 (S.B.)


DESIGNED	Michael D. Clima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
 EXAMINED *Thomas J. Donagabaki*
 PASSED *Ralph E. Anderson*

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	336
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		


Contract #98950



TEMPORARY SHEET PILING


(N. Abutment locations shown, S. Abutment similar except rotated 180°.)

Note:
If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.




EXISTING PIER FOOTING REMOVAL DETAIL (NB & SB PIERS)

(Pier 1 locations shown, Pier 2 similar except rotated 180°.)



PIER 1
Looking South



PIER 2
Looking North

EXISTING SB PIER REMOVAL

Removal lines for Existing NB Piers at same location as NB Deck Removal lines.

STAGE CONSTRUCTION DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2

WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.


EXAMINED	Thomas J. Damagala ENGINEER OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES

January 22, 2007


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 4 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	837	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		


Contract #98950




STAGE I REMOVAL



STAGE I CONSTRUCTION



STAGE II REMOVAL



STAGE II CONSTRUCTION

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Damagalki PROFESSOR OF BRIDGE DESIGN	January 22, 2007
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES	

Notes:
All sections are looking South.
Hatched area indicates Removal of Existing Structures No. 3 or No. 4.


STAGE CONSTRUCTION DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 5
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	833	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT			

Contract #98950


When "A" is 3'-6" or less, the temporary concrete barrier shall be anchored to the new slab according to Detail I or Detail II. No anchorage is required when "A" is greater than 3'-6".




SECTIONS THRU SLAB



DETAIL I



DETAIL II



STEEL RETAINER 1" x 7" x 10"

* Required only with Detail II

NOTES

- Detail I - With Bar Splicer or Couplers:
Connect one (1) 1"x7"x10" steel PL to the top layer of couplers with 2-5/8" φ bolts screwed to coupler at approximate C of each barrier panel.
- Detail II - With Extended Reinforcement Bars:
Connect one (1) 1"x7"x10" steel PL to the concrete slab with 2-5/8" φ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate C of each barrier panel.
- Cost of anchorage is included with Temporary Concrete Barrier. The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

** Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

DESIGNED Michael D. Cima	EXAMINED Thomas J. Domagalaki PRINCIPAL OF BRIDGE DESIGN
CHECKED Fess Teklehaimanot	PASSED Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES
DRAWN BECKY M. LEACH	
CHECKED M.D.C. & F.T.	




TEMPORARY CONCRETE BARRIER
FOR STAGE CONSTRUCTION
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	POST MILE	SHEET NO.
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	339
ILLINOIS FED. AID PROJECT-				


Contract #98950

SHEET NO. 6
51 SHEETS



To determine "t": After all structural steel has been erected, elevations of the top flanges of the beams shall be taken at intervals shown on this sheet. These elevations subtracted from the "Theoretical Grade Elevations Adjusted for Dead Load Deflection" shown on sheets 7 thru 11 of 51, minus slab thickness, equals the fillet heights "t" above top flange of beams.

FILLET HEIGHTS



DEAD LOAD DEFLECTION DIAGRAM

(Includes weight of concrete only.)

Note:
The above deflections are not to be used in the field if the engineer is working from the grade elevations adjusted for dead load deflections as shown on sheets 7 thru 11 of 51.

TOP OF SLAB ELEVATIONS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.) & S.N. 100-0087 (S.B.)

PLAN

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Demagala	January 22, 2007
PASSED	Ralph E. Anderson	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOWNSHIP	SHEET	SHEET NO. 7 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	840	
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950

BEAM 1

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151594.49	-41.833	465.23	465.23
⊕ Brg. N. Abut.	151595.74	-41.833	465.24	465.24
A	151605.74	-41.833	465.30	465.30
B	151615.74	-41.833	465.36	465.36
C	151625.74	-41.833	465.42	465.42
⊕ Brg. Pier 1	151630.82	-41.833	465.45	465.45
D	151640.82	-41.833	465.51	465.53
E	151650.82	-41.833	465.58	465.61
F	151660.82	-41.833	465.63	465.68
G	151670.82	-41.833	465.70	465.73
H	151680.82	-41.833	465.76	465.78
⊕ Brg. Pier 2	151691.15	-41.833	465.82	465.82
I	151701.15	-41.833	465.88	465.88
J	151711.15	-41.833	465.94	465.94
K	151721.15	-41.833	466.00	466.00
⊕ Brg. S. Abut.	151726.24	-41.833	466.03	466.03
Bk. S. Abut.	151727.49	-41.833	466.04	466.04

BEAM 2

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151594.25	-34.75	465.61	465.61
⊕ Brg. N. Abut.	151595.50	-34.75	465.62	465.62
A	151605.50	-34.75	465.68	465.68
B	151615.50	-34.75	465.75	465.75
C	151625.50	-34.75	465.80	465.80
⊕ Brg. Pier 1	151630.59	-34.75	465.84	465.84
D	151640.59	-34.75	465.89	465.91
E	151650.59	-34.75	465.96	465.99
F	151660.59	-34.75	466.02	466.07
G	151670.59	-34.75	466.08	466.11
H	151680.59	-34.75	466.14	466.16
⊕ Brg. Pier 2	151690.92	-34.75	466.21	466.21
I	151700.92	-34.75	466.26	466.26
J	151710.92	-34.75	466.32	466.32
K	151720.92	-34.75	466.39	466.39
⊕ Brg. S. Abut.	151726.00	-34.75	466.41	466.41
Bk. S. Abut.	151727.25	-34.75	466.42	466.42

BEAM 3

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151594.02	-27.67	465.99	465.99
⊕ Brg. N. Abut.	151595.27	-27.67	466.00	466.00
A	151605.27	-27.67	466.06	466.06
B	151615.27	-27.67	466.13	466.13
C	151625.27	-27.67	466.18	466.18
⊕ Brg. Pier 1	151630.35	-27.67	466.22	466.22
D	151640.35	-27.67	466.27	466.29
E	151650.35	-27.67	466.34	466.37
F	151660.35	-27.67	466.40	466.45
G	151670.35	-27.67	466.46	466.49
H	151680.35	-27.67	466.52	466.54
⊕ Brg. Pier 2	151690.69	-27.67	466.59	466.59
I	151700.69	-27.67	466.64	466.64
J	151710.69	-27.67	466.70	466.70
K	151720.69	-27.67	466.77	466.77
⊕ Brg. S. Abut.	151725.77	-27.67	466.79	466.79
Bk. S. Abut.	151727.02	-27.67	466.80	466.80

BEAM 4

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151593.79	-20.58	466.37	466.37
⊕ Brg. N. Abut.	151595.04	-20.58	466.38	466.38
A	151605.04	-20.58	466.44	466.44
B	151615.04	-20.58	466.51	466.51
C	151625.04	-20.58	466.56	466.56
⊕ Brg. Pier 1	151630.12	-20.58	466.60	466.60
D	151640.12	-20.58	466.65	466.67
E	151650.12	-20.58	466.72	466.75
F	151660.12	-20.58	466.78	466.83
G	151670.12	-20.58	466.84	466.87
H	151680.12	-20.58	466.90	466.92
⊕ Brg. Pier 2	151690.45	-20.58	466.97	466.97
I	151700.45	-20.58	467.02	467.02
J	151710.45	-20.58	467.08	467.08
K	151720.45	-20.58	467.15	467.15
⊕ Brg. S. Abut.	151725.54	-20.58	467.17	467.17
Bk. S. Abut.	151726.79	-20.58	467.18	467.18

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151593.55	-13.50	466.66	466.66
⊕ Brg. N. Abut.	151594.80	-13.50	466.66	466.66
A	151604.80	-13.50	466.72	466.72
B	151614.80	-13.50	466.77	466.77
C	151624.80	-13.50	466.83	466.82
⊕ Brg. Pier 1	151629.89	-13.50	466.85	466.85
D	151639.89	-13.50	466.91	466.93
E	151649.89	-13.50	466.96	467.00
F	151659.89	-13.50	467.02	467.06
G	151669.89	-13.50	467.07	467.10
H	151679.89	-13.50	467.12	467.14
⊕ Brg. Pier 2	151690.22	-13.50	467.18	467.18
I	151700.22	-13.50	467.23	467.23
J	151710.22	-13.50	467.29	467.29
K	151720.22	-13.50	467.34	467.34
⊕ Brg. S. Abut.	151725.30	-13.50	467.37	467.37
Bk. S. Abut.	151726.55	-13.50	467.38	467.38

EAST STAGE CONSTRUCTION JOINT

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151593.50	-12.00	466.69	466.69
⊕ Brg. N. Abut.	151594.75	-12.00	466.69	466.69
A	151604.75	-12.00	466.75	466.75
B	151614.75	-12.00	466.80	466.80
C	151624.75	-12.00	466.86	466.85
⊕ Brg. Pier 1	151629.84	-12.00	466.88	466.88
D	151639.84	-12.00	466.94	466.96
E	151649.84	-12.00	466.99	467.03
F	151659.84	-12.00	467.05	467.09
G	151669.84	-12.00	467.10	467.14
H	151679.84	-12.00	467.15	467.17
⊕ Brg. Pier 2	151690.17	-12.00	467.21	467.21
I	151700.17	-12.00	467.26	467.26
J	151710.17	-12.00	467.32	467.32
K	151720.17	-12.00	467.37	467.37
⊕ Brg. S. Abut.	151725.25	-12.00	467.40	467.40
Bk. S. Abut.	151726.50	-12.00	467.41	467.41

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
 EXAMINED *Thomas Demagalaki*
 ENGINEER OF BRIDGE DESIGN
 PASSED *Ralph E. Anderson*
 ENGINEER OF BRIDGES AND STRUCTURES

TOP OF SLAB ELEVATIONS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 8 51 SHEETS
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	917	841	
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950

BEAM 6

☉ NORTHBOUND ROADWAY & PROFILE GRADE

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151593.32	-6.42	466.77	466.77
☉ Brg. N. Abut.	151594.57	-6.42	466.78	466.78
A	151604.57	-6.42	466.83	466.84
B	151614.57	-6.42	466.89	466.89
C	151624.57	-6.42	466.94	466.94
☉ Brg. Pier 1	151629.65	-6.42	466.97	466.97
D	151639.65	-6.42	467.02	467.04
E	151649.65	-6.42	467.08	467.11
F	151659.65	-6.42	467.13	467.18
G	151669.65	-6.42	467.19	467.22
H	151679.65	-6.42	467.24	467.26
☉ Brg. Pier 2	151689.99	-6.42	467.30	467.30
I	151699.99	-6.42	467.35	467.35
J	151709.99	-6.42	467.40	467.40
K	151719.99	-6.42	467.46	467.46
☉ Brg. S. Abut.	151725.07	-6.42	467.49	467.49
Bk. S. Abut.	151726.32	-6.42	467.49	467.49

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151593.11	0.00	466.87	466.87
☉ Brg. N. Abut.	151594.36	0.00	466.88	466.88
A	151604.36	0.00	466.93	466.93
B	151614.36	0.00	466.99	466.99
C	151624.36	0.00	467.04	467.04
☉ Brg. Pier 1	151629.44	0.00	467.07	467.07
D	151639.44	0.00	467.12	467.14
E	151649.44	0.00	467.18	467.21
F	151659.44	0.00	467.23	467.28
G	151669.44	0.00	467.29	467.32
H	151679.44	0.00	467.34	467.36
☉ Brg. Pier 2	151689.78	0.00	467.40	467.40
I	151699.78	0.00	467.45	467.45
J	151709.78	0.00	467.50	467.50
K	151719.78	0.00	467.56	467.56
☉ Brg. S. Abut.	151724.86	0.00	467.58	467.58
Bk. S. Abut.	151726.11	0.00	467.59	467.59

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151593.09	0.67	466.86	466.86
☉ Brg. N. Abut.	151594.34	0.67	466.87	466.87
A	151604.34	0.67	466.92	466.92
B	151614.34	0.67	466.98	466.98
C	151624.34	0.67	467.03	467.03
☉ Brg. Pier 1	151629.42	0.67	467.06	467.06
D	151639.42	0.67	467.11	467.13
E	151649.42	0.67	467.17	467.20
F	151659.42	0.67	467.22	467.27
G	151669.42	0.67	467.27	467.31
H	151679.42	0.67	467.33	467.35
☉ Brg. Pier 2	151689.75	0.67	467.38	467.38
I	151699.75	0.67	467.44	467.44
J	151709.75	0.67	467.49	467.49
K	151719.75	0.67	467.55	467.55
☉ Brg. S. Abut.	151724.84	0.67	467.57	467.57
Bk. S. Abut.	151726.09	0.67	467.58	467.58

BEAM 8

BEAM 9

BEAM 10

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151592.86	7.75	466.75	466.75
☉ Brg. N. Abut.	151594.11	7.75	466.76	466.76
A	151604.11	7.75	466.81	466.81
B	151614.11	7.75	466.87	466.86
C	151624.11	7.75	466.92	466.92
☉ Brg. Pier 1	151629.19	7.75	466.95	466.95
D	151639.19	7.75	467.00	467.02
E	151649.19	7.75	467.05	467.09
F	151659.19	7.75	467.11	467.16
G	151669.19	7.75	467.16	467.20
H	151679.19	7.75	467.22	467.24
☉ Brg. Pier 2	151689.52	7.75	467.27	467.27
I	151699.52	7.75	467.33	467.32
J	151709.52	7.75	467.38	467.38
K	151719.52	7.75	467.43	467.44
☉ Brg. S. Abut.	151724.60	7.75	467.46	467.46
Bk. S. Abut.	151725.85	7.75	467.47	467.47

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151592.62	14.83	466.62	466.62
☉ Brg. N. Abut.	151593.87	14.83	466.63	466.63
A	151603.87	14.83	466.68	466.69
B	151613.87	14.83	466.74	466.74
C	151623.87	14.83	466.79	466.79
☉ Brg. Pier 1	151628.96	14.83	466.82	466.82
D	151638.96	14.83	466.87	466.89
E	151648.96	14.83	466.93	466.96
F	151658.96	14.83	466.98	467.03
G	151668.96	14.83	467.04	467.07
H	151678.96	14.83	467.09	467.11
☉ Brg. Pier 2	151689.29	14.83	467.15	467.15
I	151699.29	14.83	467.20	467.20
J	151709.29	14.83	467.25	467.25
K	151719.29	14.83	467.31	467.31
☉ Brg. S. Abut.	151724.37	14.83	467.34	467.34
Bk. S. Abut.	151725.62	14.83	467.34	467.34

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151592.39	21.92	466.48	466.48
☉ Brg. N. Abut.	151593.64	21.92	466.48	466.48
A	151603.64	21.92	466.54	466.54
B	151613.64	21.92	466.59	466.59
C	151623.64	21.92	466.64	466.64
☉ Brg. Pier 1	151628.72	21.92	466.67	466.67
D	151638.72	21.92	466.73	466.75
E	151648.72	21.92	466.78	466.82
F	151658.72	21.92	466.83	466.88
G	151668.72	21.92	466.89	466.92
H	151678.72	21.92	466.94	466.96
☉ Brg. Pier 2	151689.06	21.92	467.00	467.00
I	151699.06	21.92	467.05	467.05
J	151709.06	21.92	467.11	467.11
K	151719.06	21.92	467.16	467.16
☉ Brg. S. Abut.	151724.14	21.92	467.19	467.19
Bk. S. Abut.	151725.39	21.92	467.19	467.19

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	DECKY M. LEAGH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Domagala PROFESSOR OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES

TOP OF SLAB ELEVATIONS
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEETS	SHEET	SHEET NO. 9 51 SHEETS
F.A.I. 57	(XI-6-2) VB-2	WILLIAMSON	917	842	
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950

BEAM 11

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151592.16	29.00	466.33	466.33
⊙ Brg. N. Abut.	151593.41	29.00	466.33	466.33
A	151603.41	29.00	466.39	466.39
B	151613.41	29.00	466.44	466.44
C	151623.41	29.00	466.50	466.49
⊙ Brg. Pier 1	151628.49	29.00	466.52	466.52
D	151638.49	29.00	466.58	466.60
E	151648.49	29.00	466.63	466.67
F	151658.49	29.00	466.69	466.73
G	151668.49	29.00	466.74	466.77
H	151678.49	29.00	466.79	466.81
⊙ Brg. Pier 2	151688.82	29.00	466.85	466.85
I	151698.82	29.00	466.90	466.90
J	151708.82	29.00	466.96	466.96
K	151718.82	29.00	467.01	467.01
⊙ Brg. S. Abut.	151723.91	29.00	467.04	467.04
Bk. S. Abut.	151725.16	29.00	467.05	467.05

BEAM 12

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151591.96	-28.88	466.33	466.33
⊙ Brg. N. Abut.	151593.21	-28.88	466.34	466.34
A	151603.21	-28.88	466.39	466.39
B	151613.21	-28.88	466.44	466.44
C	151623.21	-28.88	466.50	466.50
⊙ Brg. Pier 1	151628.29	-28.88	466.52	466.52
D	151638.29	-28.88	466.58	466.60
E	151648.29	-28.88	466.63	466.67
F	151658.29	-28.88	466.69	466.73
G	151668.29	-28.88	466.74	466.78
H	151678.29	-28.88	466.79	466.82
⊙ Brg. Pier 2	151688.63	-28.88	466.85	466.85
I	151698.63	-28.88	466.90	466.90
J	151708.63	-28.88	466.96	466.96
K	151718.63	-28.88	467.01	467.01
⊙ Brg. S. Abut.	151723.71	-28.88	467.04	467.04
Bk. S. Abut.	151724.96	-28.88	467.05	467.05

BEAM 13

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151591.73	-21.96	466.47	466.47
⊙ Brg. N. Abut.	151592.98	-21.96	466.48	466.48
A	151602.98	-21.96	466.53	466.53
B	151612.98	-21.96	466.59	466.58
C	151622.98	-21.96	466.64	466.64
⊙ Brg. Pier 1	151628.07	-21.96	466.67	466.67
D	151638.07	-21.96	466.72	466.74
E	151648.07	-21.96	466.78	466.81
F	151658.07	-21.96	466.83	466.88
G	151668.07	-21.96	466.88	466.92
H	151678.07	-21.96	466.94	466.96
⊙ Brg. Pier 2	151688.40	-21.96	466.99	466.99
I	151698.40	-21.96	467.05	467.04
J	151708.40	-21.96	467.10	467.10
K	151718.40	-21.96	467.16	467.16
⊙ Brg. S. Abut.	151723.48	-21.96	467.18	467.18
Bk. S. Abut.	151724.73	-21.96	467.19	467.19

BEAM 14

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151591.50	-15.04	466.61	466.61
⊙ Brg. N. Abut.	151592.75	-15.04	466.62	466.62
A	151602.75	-15.04	466.67	466.68
B	151612.75	-15.04	466.73	466.73
C	151622.75	-15.04	466.78	466.78
⊙ Brg. Pier 1	151627.84	-15.04	466.81	466.81
D	151637.84	-15.04	466.86	466.88
E	151647.84	-15.04	466.92	466.95
F	151657.84	-15.04	466.97	467.02
G	151667.84	-15.04	467.03	467.06
H	151677.84	-15.04	467.08	467.10
⊙ Brg. Pier 2	151688.17	-15.04	467.14	467.14
I	151698.17	-15.04	467.19	467.19
J	151708.17	-15.04	467.24	467.24
K	151718.17	-15.04	467.30	467.30
⊙ Brg. S. Abut.	151723.25	-15.04	467.33	467.33
Bk. S. Abut.	151724.50	-15.04	467.33	467.33

BEAM 15

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151591.28	-8.12	466.74	466.74
⊙ Brg. N. Abut.	151592.53	-8.12	466.74	466.74
A	151602.53	-8.12	466.80	466.80
B	151612.53	-8.12	466.85	466.85
C	151622.53	-8.12	466.91	466.90
⊙ Brg. Pier 1	151627.61	-8.12	466.93	466.93
D	151637.61	-8.12	466.99	467.01
E	151647.61	-8.12	467.04	467.08
F	151657.61	-8.12	467.09	467.14
G	151667.61	-8.12	467.15	467.18
H	151677.61	-8.12	467.20	467.22
⊙ Brg. Pier 2	151687.94	-8.12	467.26	467.26
I	151697.94	-8.12	467.31	467.31
J	151707.94	-8.12	467.37	467.37
K	151717.94	-8.12	467.42	467.42
⊙ Brg. S. Abut.	151723.03	-8.12	467.45	467.45
Bk. S. Abut.	151724.28	-8.12	467.45	467.45

BEAM 16

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151591.05	-1.21	466.84	466.84
⊙ Brg. N. Abut.	151592.30	-1.21	466.85	466.85
A	151602.30	-1.21	466.90	466.90
B	151612.30	-1.21	466.96	466.96
C	151622.30	-1.21	467.01	467.01
⊙ Brg. Pier 1	151627.38	-1.21	467.04	467.04
D	151637.38	-1.21	467.09	467.11
E	151647.38	-1.21	467.15	467.18
F	151657.38	-1.21	467.20	467.25
G	151667.38	-1.21	467.26	467.29
H	151677.38	-1.21	467.31	467.33
⊙ Brg. Pier 2	151687.72	-1.21	467.37	467.37
I	151697.72	-1.21	467.42	467.42
J	151707.72	-1.21	467.47	467.47
K	151717.72	-1.21	467.53	467.53
⊙ Brg. S. Abut.	151722.80	-1.21	467.55	467.55
Bk. S. Abut.	151724.05	-1.21	467.56	467.56

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Damagala	January 22, 2007
PASSED	Ralph E. Anderson	ENGINEER OF BRIDGES AND STRUCTURES

TOP OF SLAB ELEVATIONS
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO. F.A.I. 57	SECTION (XI-6-2) VB-2	COUNTY WILLIAMSON	TOTAL SHEETS 917	SHEET NO. 843	SHEET NO. 10 51 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT-	

Contract #98950

☉ SOUTHBOUND ROADWAY & PROFILE GRADE

BEAM 17

BEAM 18

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151591.01	0.00	466.86	466.86
☉ Brg. N. Abut.	151592.26	0.00	466.87	466.87
A	151602.26	0.00	466.92	466.92
B	151612.26	0.00	466.98	466.98
C	151622.26	0.00	467.03	467.03
☉ Brg. Pier 1	151627.34	0.00	467.06	467.06
D	151637.34	0.00	467.11	467.13
E	151647.34	0.00	467.17	467.20
F	151657.34	0.00	467.22	467.27
G	151667.34	0.00	467.27	467.31
H	151677.34	0.00	467.33	467.35
☉ Brg. Pier 2	151687.68	0.00	467.38	467.38
I	151697.68	0.00	467.44	467.43
J	151707.68	0.00	467.49	467.49
K	151717.68	0.00	467.55	467.55
☉ Brg. S. Abut.	151722.76	0.00	467.57	467.57
Bk. S. Abut.	151724.01	0.00	467.58	467.58

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151590.82	5.71	466.77	466.77
☉ Brg. N. Abut.	151592.07	5.71	466.78	466.78
A	151602.07	5.71	466.83	466.83
B	151612.07	5.71	466.89	466.89
C	151622.07	5.71	466.94	466.94
☉ Brg. Pier 1	151627.16	5.71	466.97	466.97
D	151637.16	5.71	467.02	467.04
E	151647.16	5.71	467.08	467.11
F	151657.16	5.71	467.13	467.18
G	151667.16	5.71	467.18	467.22
H	151677.16	5.71	467.24	467.26
☉ Brg. Pier 2	151687.49	5.71	467.29	467.29
I	151697.49	5.71	467.35	467.34
J	151707.49	5.71	467.40	467.40
K	151717.49	5.71	467.46	467.46
☉ Brg. S. Abut.	151722.57	5.71	467.48	467.48
Bk. S. Abut.	151723.82	5.71	467.49	467.49

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151590.59	12.63	466.66	466.66
☉ Brg. N. Abut.	151591.84	12.63	466.67	466.67
A	151601.84	12.63	466.72	466.72
B	151611.84	12.63	466.77	466.77
C	151621.84	12.63	466.83	466.83
☉ Brg. Pier 1	151626.93	12.63	466.86	466.86
D	151636.93	12.63	466.91	466.93
E	151646.93	12.63	466.96	467.00
F	151656.93	12.63	467.02	467.06
G	151666.93	12.63	467.07	467.11
H	151676.93	12.63	467.13	467.15
☉ Brg. Pier 2	151687.26	12.63	467.18	467.18
I	151697.26	12.63	467.24	467.23
J	151707.26	12.63	467.29	467.29
K	151717.26	12.63	467.34	467.34
☉ Brg. S. Abut.	151722.34	12.63	467.37	467.37
Bk. S. Abut.	151723.59	12.63	467.38	467.38

WEST STAGE CONSTRUCTION JOINT

BEAM 19

BEAM 20

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151590.45	16.96	466.57	466.57
☉ Brg. N. Abut.	151591.70	16.96	466.57	466.57
A	151601.70	16.96	466.63	466.63
B	151611.70	16.96	466.68	466.68
C	151621.70	16.96	466.74	466.74
☉ Brg. Pier 1	151626.79	16.96	466.76	466.76
D	151636.79	16.96	466.82	466.84
E	151646.79	16.96	466.87	466.91
F	151656.79	16.96	466.93	466.97
G	151666.79	16.96	466.98	467.02
H	151676.79	16.96	467.03	467.05
☉ Brg. Pier 2	151687.12	16.96	467.09	467.09
I	151697.12	16.96	467.14	467.14
J	151707.12	16.96	467.20	467.20
K	151717.12	16.96	467.25	467.25
☉ Brg. S. Abut.	151722.20	16.96	467.28	467.28
Bk. S. Abut.	151723.45	16.96	467.29	467.29

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151590.37	19.54	466.51	466.51
☉ Brg. N. Abut.	151591.62	19.54	466.52	466.52
A	151601.62	19.54	466.57	466.58
B	151611.62	19.54	466.63	466.63
C	151621.62	19.54	466.68	466.68
☉ Brg. Pier 1	151626.70	19.54	466.71	466.71
D	151636.70	19.54	466.76	466.78
E	151646.70	19.54	466.82	466.85
F	151656.70	19.54	466.87	466.92
G	151666.70	19.54	466.93	466.96
H	151676.70	19.54	466.98	467.00
☉ Brg. Pier 2	151687.03	19.54	467.04	467.04
I	151697.03	19.54	467.09	467.09
J	151707.03	19.54	467.14	467.14
K	151717.03	19.54	467.20	467.20
☉ Brg. S. Abut.	151722.12	19.54	467.23	467.23
Bk. S. Abut.	151723.37	19.54	467.23	467.23

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151590.14	26.46	466.37	466.37
☉ Brg. N. Abut.	151591.39	26.46	466.38	466.38
A	151601.39	26.46	466.43	466.43
B	151611.39	26.46	466.48	466.48
C	151621.39	26.46	466.54	466.54
☉ Brg. Pier 1	151626.47	26.46	466.57	466.57
D	151636.47	26.46	466.62	466.64
E	151646.47	26.46	466.67	466.71
F	151656.47	26.46	466.73	466.77
G	151666.47	26.46	466.78	466.82
H	151676.47	26.46	466.84	466.86
☉ Brg. Pier 2	151686.81	26.46	466.89	466.89
I	151696.81	26.46	466.94	466.94
J	151706.81	26.46	467.00	467.00
K	151716.81	26.46	467.05	467.05
☉ Brg. S. Abut.	151721.89	26.46	467.08	467.08
Bk. S. Abut.	151723.14	26.46	467.09	467.09

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Damagala*
PASSED *Ralph E. Anderson*

TOP OF SLAB ELEVATIONS
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEET	SHEET	SHEET NO. 11
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	844	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950

BEAM 21

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151589.99	30.94	466.27	466.27
⊕ Brg. N. Abut.	151591.24	30.96	466.28	466.28
A	151601.24	31.14	466.33	466.33
B	151611.24	31.33	466.38	466.38
C	151621.24	31.51	466.43	466.43
⊕ Brg. Pier 1	151626.30	31.61	466.46	466.46
D	151636.30	31.79	466.51	466.53
E	151646.30	31.98	466.56	466.59
F	151656.30	32.16	466.61	466.66
G	151666.30	32.35	466.65	466.68
H	151676.30	32.53	466.71	466.73
⊕ Brg. Pier 2	151686.60	32.72	466.76	466.76
I	151696.60	32.91	466.81	466.81
J	151706.60	33.09	466.86	466.86
K	151716.60	33.28	466.91	466.91
⊕ Brg. S. Abut.	151721.66	33.38	466.93	466.93
Bk. S. Abut.	151722.91	33.40	466.94	466.94

BEAM 22

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151589.85	35.41	466.18	466.18
⊕ Brg. N. Abut.	151591.10	35.46	466.19	466.19
A	151601.10	35.83	466.23	466.23
B	151611.10	36.20	466.28	466.28
C	151621.10	36.57	466.32	466.32
⊕ Brg. Pier 1	151626.13	36.76	466.35	466.35
D	151636.13	37.13	466.39	466.41
E	151646.13	37.50	466.45	466.48
F	151656.13	37.87	466.49	466.54
G	151666.13	38.24	466.53	466.56
H	151676.13	38.61	466.58	466.60
⊕ Brg. Pier 2	151686.39	38.99	466.63	466.63
I	151696.39	39.36	466.68	466.67
J	151706.39	39.73	466.72	466.72
K	151716.39	40.10	466.77	466.77
⊕ Brg. S. Abut.	151721.43	40.29	466.79	466.79
Bk. S. Abut.	151722.68	40.34	466.80	466.80

BEAM 23

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	151589.70	39.89	466.08	466.08
⊕ Brg. N. Abut.	151590.95	39.96	466.09	466.09
A	151600.95	40.51	466.13	466.13
B	151610.95	41.07	466.18	466.18
C	151620.95	41.62	466.22	466.22
⊕ Brg. Pier 1	151625.97	41.90	466.24	466.24
D	151635.97	42.46	466.28	466.30
E	151645.97	43.01	466.33	466.36
F	151655.97	43.57	466.37	466.42
G	151665.97	44.13	466.41	466.44
H	151675.97	44.68	466.46	466.48
⊕ Brg. Pier 2	151686.19	45.25	466.49	466.49
I	151696.19	45.80	466.54	466.54
J	151706.19	46.36	466.58	466.58
K	151716.19	46.92	466.63	466.63
⊕ Brg. S. Abut.	151721.21	47.21	466.64	466.64
Bk. S. Abut.	151722.45	47.28	466.65	466.65

DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.



January 22, 2007
EXAMINED Thomas J. Domagalaki
PASSED Ralph E. Anderson
ENGINEER OF BRIDGES AND STRUCTURES

TOP OF SLAB ELEVATIONS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET	SHEET NO. 12 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	845	
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT-			

Contract #98950



PLAN

MIN. BAR LAP

#5 bars = 1'-8"

Notes:
See sheet 16, 19, and 24 of 51 for superstructure details and Bill of Material.
Bars indicated thus 29 x 5-#5 etc. indicates 29 lines of bars with 5 lengths per line.
See sheet 18 of 51 for parapet reinforcement.
See sheet 24 of 51 for Section A-A.
See sheet 48 of 51 for Bar Splicers Details.

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.



EXAMINED	January 22, 2007
THOMAS J. DOMAGALA	
PASSED	Ralph E. Anderson
	ENGINEER OF BRIDGES AND STRUCTURES

SUPERSTRUCTURE (STAGE I-NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO. F.A.I. 57	SECTION (X1-6-2) VB-2	COUNTY WILLIAMSON	TOTAL SHEETS 917	SHEET NO. 346	SHEET NO. 13 51 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		

Contract #98950



PLAN

Notes:
See sheet 16, 19, and 24 of 51 for superstructure details and Bill of Material.
Bars Indicated thus 32 x 4-#5 etc. indicates 32 lines of bars with 4 lengths per line.
See sheet 18 of 51 for parapet reinforcement.
See sheet 24 of 51 for Section A-A.
See sheet 48 of 51 for Bar Splicers Details.

MIN. BAR LAP
#5 bars = 1'-8"

SUPERSTRUCTURE (STAGE I-SB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Tektelaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Damagala*
ENGINEER OF BRIDGE DESIGN
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	STA. BEGIN	SHEET	SHEET NO. 14 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	847	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT		


Contract #98950

MIN. BAR LAPS

#5 bars = 1'-8"



PLAN



DETAIL A

Notes:
See sheet 17, 19, and 24 of 51 for superstructure details and Bill of Material.
Bars indicated thus 42 x 4-#5 etc. indicates 42 lines of bars with 4 lengths per line.
See sheet 18 of 51 for parapet reinforcement.
See sheet 24 of 51 for Section A-A.
See sheet 48 of 51 for Bar Splicers Details.


DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Damagala*
ENGINEER OF BRIDGE DESIGN
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES


SUPERSTRUCTURE (STAGE II-NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET NO.	SHEET NO. 15
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	843	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT	Contract #98950		



PLAN



DETAIL A

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED *Thomas J. Demagala*
MEMBER OF STRUCTURAL DESIGN
 PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

January 22, 2007

Notes:
 See sheet 17, 19, and 24 of 51 for superstructure details and Bill of Material.
 Bars indicated thus 47 x 4-#5 etc. indicates 47 lines of bars with 4 lengths per line.
 See sheet 18 of 51 for parapet reinforcement.
 See sheet 24 of 51 for Section A-A.
 See sheet 48 of 51 for Bar Splicers Details.


MIN. BAR LAPS
 #5 bars = 1'-8"

SUPERSTRUCTURE (STAGE II-SB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROUTE NO.	SECTION	COUNTY	DATE	SHEET	SHEET NO. 16
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	9/17	849	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS		FED. AID PROJECT-		

Contract #98950



CROSS SECTION - STAGE I NORTHBOUND
(Looking South)

NEAR PIER



CROSS SECTION - STAGE I SOUTHBOUND
(Looking South)

NEAR MIDSPAN

Notes:
See Sheet 12, 13, 19, and 24 of 51 for superstructure details and Bill of Material.
Bars indicated thus 6 x 5-#5 etc. indicates 6 lines of bars with 5 lengths per line.
See Sheet 18 of 51 for parapet reinforcement.
See sheet 48 of 51 for Bar Splicer Details.

SUPERSTRUCTURE (CROSS SECTIONS)

(STAGE I-NB & STAGE I SB)

F.A.I. RT. 57 SEC. (XI-6-2)VB-2

WILLIAMSON COUNTY

STA. 1516+58.56

S.N. 100-0086 (N.B.)

S.N. 100-0087 (S.B.)


DESIGNED	Michael D. Cima
CHECKED	Fess Tektelaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Damagala	January 22, 2007
PASSED	Ralph E. Anderson	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 17 51 SHEETS
F.A.I. 57	XI-6-2/VB-2	WILLIAMSON	917	850	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		

Contract #98950



Notes:
See Sheet 14, 15, 19, and 24 of 51 for superstructure details and Bill of Material.
Bars indicated thus 6 x 5-#5 etc. indicates 6 lines of bars with 5 lengths per line.
See Sheet 18 of 51 for parapet reinforcement.
See sheet 48 of 51 for Bar Splicer Details.

NEAR MIDSPAN
CROSS SECTION - STAGE II NORTHBOUND
(Looking South)



NEAR PIER
CROSS SECTION - STAGE II SOUTHBOUND
(Looking South)

SUPERSTRUCTURE (CROSS SECTIONS)
(STAGE II-NB & STAGE II SB)
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


DESIGNED Michael D. Cima
CHECKED Fess Tektelaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.

January 22, 2007
EXAMINED Thomas J. Domagalaki
PASSED Ralph E. Anderson

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEET NO.	SHEET	SHEET NO.
F.A.I. 57	(XI-6-2) VB-2	WILLIAMSON	917	851	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS		FED. AID PROJECT-		


Contract #98950



MIN. BAR LAP
#5 bars = 1'-8"
#8 bars = 3'-5"

Notes:
See Sheet 19 of 51 for superstructure details and Bill of Material.
Bars indicated thus 1 x 2-#5 etc. indicates 1 line of bars with 2 lengths per line.

INSIDE ELEVATION OF PARAPET
(East Parapet of Northbound Structure shown)
(West Parapet of Northbound Structure and East Parapet of Southbound Structure both similar)



INSIDE ELEVATION OF PARAPET
(West Parapet of Southbound Structure shown)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Namagalski*
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES


PARAPET ELEVATION
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	917	352
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	

SHEET NO. 19
51 SHEETS


Contract #98950




SECTION THRU PARAPETS (STAGE I CONSTRUCTION)



DETAIL A



SECTION THRU PARAPETS (STAGE II CONSTRUCTION)



PARAPET JOINT DETAILS

Notes:

The exterior surfaces of the floor drains shall be painted with the finish coat as specified in the special provisions for Cleaning and Painting New Metal Structures. The exterior surfaces of the drains shall be cleaned according to Steel Structures Painting Council's Spec. SSPC-SP1 prior to painting. Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.

NORTHBOUND SUPERSTRUCTURE
BILL OF MATERIAL

Bar	No.	Size	Length	Shape	
a(E)	245	#5	32'-3"	—	
a1(E)	177	#5	31'-8"	—	
a2(E)	490	#6	6'-0"	—	
a11(E)	245	#5	43'-7"	—	
a12(E)	177	#5	43'-0"	—	
b(E)	316	#5	34'-5"	—	
b1(E)	150	#6	30'-0"	—	
b2(E)	335	#5	27'-11"	—	
d(E)	145	#5	3'-0"	—	
d1(E)	278	#5	2'-5"	—	
d2(E)	145	#4	3'-0"	—	
d3(E)	290	#4	3'-8"	—	
d4(E)	12	#5	2'-4"	—	
d5(E)	145	#5	3'-8"	—	
d6(E)	145	#4	3'-8"	—	
e(E)	48	#4	14'-0"	—	
e1(E)	48	#4	7'-4"	—	
e2(E)	36	#4	14'-8"	—	
e3(E)	8	#8	28'-4"	—	
e4(E)	8	#5	28'-4"	—	
e5(E)	16	#8	7'-4"	—	
e6(E)	16	#5	7'-4"	—	
e7(E)	8	#8	24'-1"	—	
e8(E)	8	#5	23'-2"	—	
m(E)	22	#6	6'-8"	—	
m1(E)	8	#6	7'-9"	—	
m3(E)	28	#6	9'-10"	—	
m4(E)	4	#6	2'-9"	—	
m8(E)	4	#6	10'-6"	—	
m9(E)	2	#6	5'-4"	—	
m10(E)	20	#6	23'-3"	—	
m11(E)	6	#6	32'-5"	—	
m12(E)	4	#6	31'-6"	—	
s(E)	154	#5	6'-3"	—	
s1(E)	150	#4	8'-6"	—	
v(E)	150	#5	3'-4"	—	
Reinforcement Bars, Epoxy Coated				Pound	75,930
Concrete Superstructure				Cu. Yds.	318.0

SOUTHBOUND SUPERSTRUCTURE
BILL OF MATERIAL

Bar	No.	Size	Length	Shape	
a2(E)	490	#6	6'-0"	—	
a3(E)	245	#5	6'-11"	—	
a4(E)	177	#5	10'-4"	—	
a5(E)	82	#5	22'-11"	—	
a6(E)	59	#5	22'-4"	—	
a7(E)	82	#5	25'-4"	—	
a8(E)	59	#5	24'-9"	—	
a9(E)	81	#5	27'-9"	—	
a10(E)	59	#5	27'-2"	—	
a13(E)	245	#5	48'-7"	—	
a14(E)	177	#5	48'-0"	—	
b(E)	340	#5	34'-5"	—	
b1(E)	162	#6	30'-0"	—	
b2(E)	365	#5	27'-11"	—	
d(E)	145	#5	3'-0"	—	
d1(E)	278	#5	2'-5"	—	
d2(E)	145	#4	3'-0"	—	
d3(E)	290	#4	3'-8"	—	
d4(E)	12	#5	2'-4"	—	
d5(E)	145	#5	3'-8"	—	
d6(E)	145	#4	3'-8"	—	
e(E)	48	#4	14'-0"	—	
e1(E)	48	#4	7'-4"	—	
e2(E)	36	#4	14'-8"	—	
e3(E)	8	#8	28'-4"	—	
e4(E)	8	#5	28'-4"	—	
e5(E)	16	#8	7'-4"	—	
e6(E)	16	#5	7'-4"	—	
e7(E)	8	#8	24'-1"	—	
e8(E)	8	#5	23'-2"	—	
m(E)	23	#6	6'-8"	—	
m1(E)	10	#6	7'-9"	—	
m2(E)	6	#6	9'-2"	—	
m3(E)	26	#6	9'-10"	—	
m4(E)	4	#6	2'-9"	—	
m5(E)	5	#6	4'-2"	—	
m6(E)	23	#6	25'-9"	—	
m7(E)	2	#6	24'-10"	—	
m13(E)	3	#6	33'-0"	—	
m14(E)	2	#6	32'-1"	—	
s(E)	160	#5	6'-3"	—	
s1(E)	138	#4	8'-6"	—	
v(E)	154	#5	3'-4"	—	
Reinforcement Bars, Epoxy Coated				Pound	81,090
Concrete Superstructure				Cu. Yds.	327.6
Conduit Embedded in Structure, 2" PVC				Foot	133.0

For Bar Splicers (E) see sheet 48 of 51.

DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.

EXAMINED Thomas J. Domagala
PASSED Ralph E. Anderson
ENGINEER OF BRIDGE DESIGN
ENGINEER OF BRIDGES AND STRUCTURES

January 22, 2007

BARS d(E), d2(E),
d5(E) & d6(E)

BAR d1(E)

BAR d3(E)

BAR d4(E)

BAR s(E)


BAR s1(E)

BAR v(E)

SUPERSTRUCTURE DETAILS
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 20
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	917	353	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-	Contract #98950		



MIN. BAR LAP

#6 bar = 2'-9"

Notes:
Reinforcement bars in diaphragm are billed with superstructure on sheet 19 of 51.
Concrete in diaphragm is included with Concrete Superstructure on sheet 19 of 51.
For details of bars s(E) & s₁(E) see sheet 19 of 51.
The s(E) and s₁(E) bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.
For Bar Splicer Details see sheet 48 of 51.
For Section A-A see sheet 24 of 51.
Bars indicated thus 3x2-#6 etc. indicates 3 lines of bars with 2 lengths per line.



ELEVATION

Looking North, at North Abutment, SN 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.


EXAMINED	Thomas J. Demagalibi	January 22, 2007
PASSED	Ralph E. Anderson	

DIAPHRAGM DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROUTE NO.	SECTION	COUNTY	STATION	SHEET	SHEET NO. 21 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	354	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		

Contract #98950



MIN. BAR LAP
#6 bar = 2'-9"

Notes:
Reinforcement bars in diaphragm are billed with superstructure on sheet 19 of 51.
Concrete in diaphragm is included with Concrete Superstructure on sheet 19 of 51.
For details of bars s(E) & s1(E) see sheet 19 of 51.
The s(E) and s1(E) bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.
For Bar Splicer Details see sheet 48 of 51.
For Section A-A see sheet 24 of 51.
Bars indicated thus 3x2-#6 etc. indicates 3 lines of bars with 2 lengths per line.



ELEVATION

Looking North, at North Abutment, SN 100-0086 (N.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Danagalaki ENGINEER OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES


January 22, 2007

DIAPHRAGM DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 22 51 SHEETS
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	917	855	
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950




MIN. BAR LAP

#6 bar = 2'-9"

Notes:

- Reinforcement bars in diaphragm are billed with superstructure on sheet 19 of 51.
- Concrete in diaphragm is included with Concrete Superstructure on sheet 19 of 51.
- For details of bars s(E) & s₁(E) see sheet 19 of 51.
- The s(E) and s₁(E) bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.
- For Bar Splicer Details see sheet 48 of 51.
- For Section A-A see sheet 24 of 51.
- Bars indicated thus 2x2-#6 etc. indicates 2 lines of bars with 2 lengths per line.



ELEVATION

Looking South, at South Abutment, SN 100-0086 (N.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Domagalicki ENGINEER OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES

January 22, 2007



DIAPHRAGM DETAILS
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 23
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	356	51 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT-	

Contract #98950

MIN. BAR LAP
#6 bar = 2'-9"



Notes:
Reinforcement bars in diaphragm are billed with superstructure on sheet 19 of 51.
Concrete in diaphragm is included with Concrete Superstructure on sheet 19 of 51.
For details of bars s(E) & s1(E) see sheet 19 of 51.
The s(E) and s1(E) bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.
For Bar Splicer Details see sheet 48 of 51.
For Section A-A see sheet 24 of 51.
Bars indicated thus 2x2-#6 etc. indicates 2 lines of bars with 2 lengths per line.

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Domagalabi*
PRINCIPAL ENGINEER OF BRIDGE DESIGN
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

ELEVATION


Looking South, at South Abutment, SN 100-0087 (S.B.)

DIAPHRAGM DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEET NO.	SHEET	SHEET NO. 24
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	857	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS		FED. AID PROJECT		

Contract #98950



SECTION A-A

Dimensions at right angles to abutment, except as shown.

TOP OF CORBEL ELEVATION AT BACK OF ABUTMENTS		
Location	N.B. Structure	S.B. Structure
Bk. North Abutment	-	-
East Edge of Parapet	463.83	464.96
☉ Roadway & P.G.	465.54	465.53
West Edge of Parapet	464.96	464.72
Bk. South Abutment	-	-
East Edge of Parapet	464.63	465.67
☉ Roadway & P.G.	466.26	466.25
West Edge of Parapet	465.68	465.28

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.



EXAMINED	Thomas J. Domagalaki ENGINEER OF BRIDGE DESIGN	January 22, 2007
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES	

DIAPHRAGM DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 25 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	858	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT		

Contract #98950



FRAMING PLAN (NB)

(All beams are W30x99 AASHTO M270 Grade 50)

DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.


January 22, 2007
EXAMINED Thomas Damagalki
PASSED Ralph E. Anderson
ENGINEER OF BRIDGES AND STRUCTURES

FRAMING PLAN (NORTHBOUND)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET NO.	SHEET NO. 26 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	9/17	859	
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950



For specific beam lengths see "Beam Dimension Table" on sheet 27 of 51.

FRAMING PLAN (SB)

(All beams are W30x99 AASHTO M270 Grade 50)

*Dimensions are at ϕ of bearing.

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.


EXAMINED	Thomas J. Damagala	January 22, 2007
PASSED	Ralph E. Anderson	

FRAMING PLAN (SOUTHBOUND)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 27
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	860	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT			

Contract #98950




ELEVATION

All beams W30x99 and Splice plates shall be AASHTO M270 Grade 50 and shall meet Notch Toughness Requirements (NTR).

Beam No.	a	b	c	d	e	f	g	h	i	j
1-20	41'-7"	47'-4"	41'-7"	35'-1"	60'-4"	35'-1"	130'-6"	8'-10"	13'-5"	13'-5"
21	41'-6 3/4"	47'-3 7/8"	41'-6 3/4"	35'-0 7/8"	60'-3 5/8"	35'-0 7/8"	130'-5 3/8"	8'-10"	13'-4 7/8"	13'-4 7/8"
22	41'-6 3/4"	47'-3 5/8"	41'-6 3/4"	35'-0 3/4"	60'-3 5/8"	35'-0 3/4"	130'-5 1/8"	8'-10"	13'-4 3/4"	13'-4 3/4"
23	41'-6 7/8"	47'-3 3/4"	41'-6 7/8"	35'-0 7/8"	60'-3 3/4"	35'-0 7/8"	130'-5 1/2"	8'-10"	13'-4 7/8"	13'-4 7/8"

Flange Splice

PL 3/4" x 10 1/2" x 4'-6 1/4" (NTR)



Web Splice


PL 1/2" x 1'-1" x 2'-1 3/8" (NTR) (One Ea. Side)

Flange Splice

PL 3/4" x 10 1/2" x 4'-6 1/4" (NTR)

Flange Splice


PL 3/4" x 10 1/2" x 4'-6 1/4" (NTR)



FIELD SPLICE DETAIL

(46 Required)
For Splice locations 1 & 2


PL 1 3/8" x 2" Slotted Holes for 1" phi Anchor Bolts



END OF BEAM DETAIL

Note:

"NTR" denotes plates to which notch toughness requirements are applicable. Load carrying components designated "NTR" shall conform to the Supplemental Requirements for Notch Toughness, Zone 2.



SECTION A-A

DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.

EXAMINED Thomas J. Domagala
PASSED Ralph E. Anderson
January 22, 2007
ENGINEER OF BRIDGE DESIGN
ENGINEER OF BRIDGES AND STRUCTURES

STRUCTURAL STEEL DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	861
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

Contract #98950

SHEET NO. 28

51 SHEETS

	0.4 Sp. 1 or 0.6 Sp. 3	Pier 1 or 2	0.5 Sp. 2
I_s	(in ⁴) 3990	3990	3990
I_c (n)	(in ⁴) 11789	-	11789
I_c (3n)	(in ⁴) 8801	-	8801
S_s	(in ³) 269	269	269
S_c (n)	(in ³) 417	-	417
S_c (3n)	(in ³) 377	-	377
Z	(in ³) -	312	-
DC1	(k/ft) 0.788	0.788	0.788
M DC1	(k) 33.9	206.1	152.4
DC2	(k/ft) 0.082	0.082	0.082
M DC2	(k) 5.7	16.1	21.3
DW	(k/ft) 0.354	0.354	0.354
M DW	(k) 24.6	69.3	91.8
M $\frac{1}{2}$ + Imp	(k) 368.3	307.0	611.0
M _u (Strength I)	(k) 730.9	919.0	1423.9
$\phi_r M_n$, $\phi_r M_{nc}$	(k) 2099.6	1300	2099.6
f_s DC1	(ksi) 1.5	9.2	6.8
f_s DC2	(ksi) 0.2	0.7	0.7
f_s DW	(ksi) 0.8	3.1	2.9
f_s 1.3($\frac{1}{2}$ +I)	(ksi) 13.8	17.8	22.9
f_s (Service II)	(ksi) 16.3	30.8	33.3
f_s (Total)(Strength I)	(ksi) -	-	-
V _{sr}	(k) 36.5	-	50.4


	Abutment	Pier
R DC1 (k)	7.9	43.5
R DC2+DW (k)	5.2	23.3
R $\frac{1}{2}$ (k)	45.9	76.2
R Imp (k)	12.6	16.6
R Total (k)	71.6	159.6

*Data shown is for SN 100-0086 (N.B.), data for SN 100-0087 (S.B.) similar.


DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Domagalaki*
PROFESSOR OF BRIDGE DESIGN
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

- I_s , S_s : Non-composite moment of inertia and section modulus of the steel section used for computing f_s (Total-Strength I, and Service II) due to non-composite dead loads (in⁴ and in³).
- I_c (n), S_c (n): Composite moment of inertia and section modulus of the steel and deck based upon the modular ratio, "n", used for computing f_s (Total-Strength I, and Service II) due to short-term composite live loads (in⁴ and in³).
- I_c (3n), S_c (3n): Composite moment of inertia and section modulus of the steel and deck based upon 3 times the modular ratio, "3n", used for computing f_s (Total-Strength I, and Service II) due to long-term composite (superimposed) dead loads (in⁴ and in³).
- Z: Plastic Section Modulus of the steel section in non-composite areas. Omit line in Moment Table if not used in design calculations (in³).
- DC1: Un-factored non-composite dead load (kips/ft.).
- M DC1: Un-factored moment due to non-composite dead load (kip-ft.).
- DC2: Un-factored long-term composite (superimposed excluding future wearing surface) dead load (kips/ft.).
- M DC2: Un-factored moment due to long-term composite (superimposed excluding future wearing surface) dead load (kip-ft.).
- DW: Un-factored long-term composite (superimposed future wearing surface only) dead load (kips/ft.).
- M DW: Un-factored moment due to long-term composite (superimposed future wearing surface only) dead load (kip-ft.).
- M $\frac{1}{2}$ + Imp: Un-factored live load moment plus dynamic load allowance (impact) (kip-ft.).
- M_u (Strength I): Factored design moment (kip-ft.).
1.25 (M_{DC1} + M_{DC2}) + 1.5 M_{DW} + 1.75 M $\frac{1}{2}$ + Imp
- $\phi_r M_n$: Compact composite positive moment capacity computed according to Article 6.10.7.1 (kip-ft.).
- $\phi_r M_{nc}$: Compact non-composite negative moment capacity computed according to Article A6.1.1 (kip-ft.).
- f_s (Service II): Sum of stresses as computed from the moments below (ksi).
M_{DC1} + M_{DC2} + M_{DW} + 1.3 M $\frac{1}{2}$ + Imp
- f_s (Total)(Strength I): Sum of stresses as computed from the moments below on non-compact section (ksi).
1.25 (M_{DC1} + M_{DC2}) + 1.5 M_{DW} + 1.75 M $\frac{1}{2}$ + Imp
- V_{sr}: Factored shear range computed according to Article 6.10.10.



TOP VIEW



DIAPHRAGMS

Diaphragm	# Required
D	90
D ₁	72
D ₂	3
D ₃	3
D ₄	3
D ₅	3
D ₆	3
D ₇	3
D ₈	3
D ₉	3
D ₁₀	3

Note:
Two hardened washers shall be required over all oversize holes for diaphragms.
Use $\frac{1}{16}$ x $\frac{1}{2}$ vertical slotted holes in top and bottom connection angles, 6 x 4 x $\frac{1}{2}$ (or bent L) for east side of Beam 6 and west side of Beam 18 only. Provide $\frac{5}{16}$ plate washers for slotted holes. Bolts for slotted holes shall be finger tightened prior to the deck pour for Stage II Construction and then fully tightened after completion of the Stage II deck pour.
All diaphragms shall be installed as steel is erected and secured with erection pins and bolts except as otherwise noted. Individual diaphragms at supports may be temporarily disconnected to install bearing anchor rods.

**TOP OF BEAM ELEVATIONS

Location	℄ Brg. N. Abut.	℄ Brg. Pier 1	℄ Splice 1	℄ Splice 2	℄ Brg. Pier 2	℄ Brg. S. Abut.
Beam 1	464.57	464.73	464.76	465.05	465.09	465.36
Beam 2	464.95	465.11	465.14	465.44	465.48	465.74
Beam 3	465.33	465.49	465.52	465.82	465.86	466.12
Beam 4	465.71	465.87	465.90	466.20	466.24	466.50
Beam 5	465.99	466.13	466.16	466.41	466.45	466.70
Beam 6	466.11	466.24	466.27	466.53	466.57	466.82
Beam 7	466.20	466.33	466.36	466.62	466.66	466.90
Beam 8	466.09	466.22	466.25	466.51	466.55	466.79
Beam 9	465.96	466.09	466.12	466.38	466.42	466.67
Beam 10	465.81	465.95	465.98	466.23	466.27	466.52
Beam 11	465.66	465.80	465.83	466.08	466.12	466.37
Beam 12	465.67	465.80	465.83	466.08	466.12	466.37
Beam 13	465.81	465.94	465.97	466.23	466.27	466.51
Beam 14	465.95	466.08	466.11	466.37	466.41	466.66
Beam 15	466.07	466.21	466.24	466.49	466.53	466.78
Beam 16	466.18	466.31	466.34	466.60	466.64	466.88
Beam 17	466.11	466.24	466.27	466.53	466.57	466.81
Beam 18	466.00	466.13	466.16	466.42	466.46	466.70
Beam 19	465.85	465.98	466.01	466.27	466.31	466.56
Beam 20	465.71	465.84	465.87	466.13	466.17	466.41
Beam 21	465.61	465.73	465.76	466.00	466.04	466.26
Beam 22	465.52	465.62	465.64	465.87	465.90	466.12
Beam 23	465.42	465.51	465.53	465.74	465.77	465.97


**For fabrication only

STRUCTURAL STEEL DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET	SHEET NO. 29 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	9/17	862	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		

Contract #98950




ELEVATION AT ABUTMENT




SECTION A-A

1" ϕ x 12" anchor bolts with 2 1/4" x 2 1/4" x 5/16" \mathbb{E} washer under nut. 1 3/8" x 2" slotted hole in flange. 1 1/2" ϕ holes in bearing plate. (Contractor has the option of cast in place or drilled construction.)

FIXED BEARINGS AT ABUTMENTS
(46 Required)



ELEVATION AT PIER




SECTION B-B

FIXED BEARING AT PIERS
(46 Required)

Notes:

Anchor bolts at fixed bearings may be built into the masonry. See sheet 30 of 51 for Anchor Bolt installation details. All structural steel for the fixed bearings including plate materials and pintles shall be AASHTO M270 Grade 50, except shim plates. Two 1/8" adjusting shims shall be provided for each bearing in addition to all other plates or shims and placed as shown on bearing details.



PINTLE

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Damagala ENGINEER OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES

January 22, 2007

BEARING DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	STATES	SHEET NO.	SHEET NO. 30 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	863	
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT	

Contract #98950

The Illinois Coil-Lock Anchor Bolt is a proprietary item which is the property of the Illinois Department of Transportation. Use, reproduction or disclosure without express written permission is prohibited and protected under Federal copyright laws. The production and the fabrication of this bolt for use on highway projects in the State of Illinois shall be permitted and there shall be no incurred charges or fees to the manufacturer or the fabricator for producing or fabricating this bolt.

D	E	H	K	"d"
1"	1 1/8"	1 3/16"	1 3/4"	1/4"
1 1/4"	1 3/8"	1 1/16"	2"	3/8"
1 1/2"	1 5/8"	1 5/16"	2 1/8"	1/2"
2"	2 1/8"	1 13/16"	2 7/8"	1/2"
2 1/2"	2 5/8"	2 5/16"	3 3/8"	1"



MATERIALS FOR ILLINOIS COIL-LOCK ANCHOR BOLT

The anchor bolt shall be fabricated from cold drawn or hot finished seamless carbon steel mechanical tubing conforming to ASTM A 519, Grade 1026, CW and supplied with hexagonal nuts and cut washers.

The coil wire shall be made of any suitable soft steel wire. The finished anchor bolt shall be cleaned of rust and other foreign materials and wrapped or packaged to prevent contamination until they are installed. The epoxy grout shall be a two-component, epoxy resin bonding system conforming to ASTM C 881, Type I, Grade 1 and of a Class suitable for the temperature at installation.

INSTALLATION PROCEDURE for the ILLINOIS COIL-LOCK ANCHOR BOLT

1. With the coil wire in place, the bolt shall be inserted into the hole and turned clockwise to a snug fit in the hole. Nut and washer shall be placed on the bolt. The nut shall be tensioned until the steel base plates are held securely to the concrete bearing seat.
2. Epoxy grout shall be pumped through the zerk fitting with a pressure gun. Pumping shall continue until the epoxy overflows the hole around the bolt shank. After pumping is discontinued, excess epoxy shall be immediately wiped off.

ALTERNATE ANCHOR BOLTS

The Contractor may use, at his option, the capsule or the adhesive cartridge type anchor rods that have been previously tested and given a prior approval by the Department. The Contractor shall install these anchor rods in pre-drilled holes according to the manufacturer's recommendations and procedures.

- The capsule or the adhesive cartridge type anchor rods shall be a two part system composed of:
1. A threaded rod stud with nut and washer of the type specified.
 2. A sealed glass capsule or a sealed glass adhesive cartridge containing premeasured amounts of the adhesive chemical.

Location	Type
Abutments	A325
Piers	A325

ASTM F 1554 Grade 105, ASTM A 449 and AASHTO M 314 Grade 105 anchor bolts may be substituted for the anchor bolts shown above.

GENERAL NOTES

Holes in the masonry for anchor bolts shall be drilled through the base plates to the diameter and depth shown or according to the manufacturer's recommendation after beams or girders have been erected and adjusted. Prior to setting the bolts, the holes shall be dry and all dust and loose particles shall be removed by the use of compressed air or vacuuming. The anchor bolts, furnished and installed and including the epoxy grout or capsules shall not be paid for separately but shall be included in the unit bid price for Anchor Bolts, 1'.

ANCHOR BOLT DETAILS FOR BEARINGS

F.A.I. RT. 57 SEC. (X1-6-2)VB-2

WILLIAMSON COUNTY

STA. 1516+58.56

S.N. 100-0086 (N.B.)

S.N. 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	DECKY M. LEACH
CHECKED	M.D.C. & F.T.


January 22, 2007
 EXAMINED *Thomas J. Domagalaki*
 PASSED *Ralph E. Anderson*
 ENGINEER OF BRIDGES AND STRUCTURES

ABB-1 10-22-04


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	POST MILE	SHEET	SHEET NO. 31 51 SHEETS
F.A.I. 57	XI-6-2)VB-2	WILLIAMSON	917	SLA	
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-	Contract #98950		

Notes: Four steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For bar bending details and Field Cutting Diagram see sheet 33 of 51.



ELEVATION
(Looking North)



**SECTION THRU
NORTH ABUTMENT (SB)**


**PILE DATA
(N. ABUTMENT-SB)**

Type: HP14x73
Nominal Required Bearing: 578 kips
Factored Resistance Available: 289 kips
Est. Length: 60 feet
No. of Production Piles: 11
No. of Test Piles: 1 (Stage I Construction)

BILL OF MATERIAL

NORTH ABUTMENT-SN 100-0087 (S.B.)

Bar	No.	Size	Length	Shape
h(E)	18	#5	9'-5"	—
h1(E)	2	#5	11'-5"	—
h2(E)	2	#5	35'-2"	—
p(E)	24	#7	26'-10"	—
p6(E)	12	#7	25'-9"	—
s2(E)	47	#5	11'-5"	□
u(E)	10	#6	7'-2"	□
u1(E)	33	#5	6'-10"	□
v1(E)	130	#5	4'-4"	—
v2(E)	8	#5	10'-2"	—
Concrete Structures	Cu. Yd.	28.7		
Reinforcement Bars, Epoxy Coated	Pound	3800		
Structure Excavation	Cu. Yd.	169		
Furnishing Steel Piles HP14x73	Foot	660		
Driving Piles	Foot	660		
Test Pile Steel HP14x73	Each	1		
Concrete Encasement	Cu. Yd.	5.3		



PLAN

**NORTH ABUTMENT (STAGE I - SB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2**

WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Damagala*
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGE DESIGN
ENGINEER OF BRIDGES AND STRUCTURES


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	STATES	SHEET NO.	SHEET NO. 32
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	917	865	51 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT-	

Contract #98950




ELEVATION
(Looking North)



PLAN

MIN. BAR LAP
#7 bar = 4'-10"

Notes: Four steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For bar bending details and Field Cutting Diagram see sheet 33 of 51.
Bars indicated thus 12x2-#7 indicates 12 lines of bars with 2 lengths per line.
For Bill of Materials see sheet 31 of 51.



NORTH ABUTMENT (STAGE II - SB)
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.



EXAMINED	Thomas J. Domagala	January 22, 2007
PASSED	Ralph E. Anderson	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET	SHEET NO. 33
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	9/17	866	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS FED. AID PROJECT-				

Contract #98950


Notes: Four steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
Bars indicated thus 12x2-#7 indicates 12 lines of bars with 2 lengths per line.
For Bill of Material see sheet 34 of 51.



MIN. BAR LAPS
#5 bar = 1'-8"
#7 bar = 4'-10"



DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Demagala ENGINEER OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES



FIELD CUTTING DIAGRAM
Order v2(E) full length. Cut as shown and use remainder of bars in opposite face.

PLAN



NORTH ABUTMENT (STAGE II - NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

Notes: Pour steps monolithically with cap.
 Space reinforcement in cap to miss anchor bolts.
 For Anchor Bolt installation details see sheet 30 of 51.
 For Bar Splicer details see sheet 48 of 51.
 For bar bending details and Field Cutting Diagram see sheet 33 of 51.



STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

PILE DATA
 (N. ABUMENT - NB)

Type: HP14x73
 Nominal Required Bearing: 578 kips
 Factored Resistance Available: 289 kips
 Est. Length: 60 feet
 No. of Production Piles: 11


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 34 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	567	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		

Contract #98950



ELEVATION
 (Looking North)

SECTION THRU
 NORTH ABUMENT (NB)



PLAN

BILL OF MATERIAL
 NORTH ABUMENT-SN 100-0086 (N.B.)

Bar	No.	Size	Length	Shape
h(E)	18	#5	9'-5"	—
h3(E)	8	#5	22'-8"	—
h4(E)	2	#5	21'-0"	—
h5(E)	2	#5	26'-0"	—
h6(E)	2	#5	11'-10"	—
p1(E)	24	#7	24'-4"	—
p2(E)	12	#7	32'-6"	—
s2(E)	46	#5	11'-5"	□
u(E)	11	#6	7'-2"	—
u1(E)	50	#5	6'-10"	—
v1(E)	134	#5	4'-4"	—
v2(E)	8	#5	10'-2"	—
Concrete Encasement	Cu. Yd.	4.9		
Concrete Structures	Cu. Yd.	34.2		
Reinforcement Bars, Epoxy Coated	Pound	4190		
Structure Excavation	Cu. Yd.	192		
Furnishing Steel Piles HP14x73	Foot	660		
Driving Piles	Foot	660		

NORTH ABUMENT (STAGE I - NB)
 F.A.I. RT. 57 SEC. (X1-6-2)VB-2
 WILLIAMSON COUNTY
 STA. 1516+58.56
 S.N. 100-0086 (N.B.) & S.N. 100-0087 (S.B.)

DESIGNED Michael D. Cima
 CHECKED Fess Teklehaimanot
 DRAWN BECKY M. LEACH
 CHECKED M.D.C. & F.T.


January 22, 2007
 EXAMINED Thomas J. Domagalaki
 PASSED Ralph E. Anderson

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO. F.A.I. 57	SECTION XI-6-2 VB-2	COUNTY WILLIAMSON	SHEET 917	PROJECT 863	SHEET NO. 35 51 SHEETS
FED. ROAD DIST. NO. 7					ILLINOIS FED. AID PROJECT-

Contract #98950


Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For bar bending details and Field Cutting Diagram see sheet 33 of 51.



PILE DATA
(S. ABUTMENT - NB)

Type: HP14x73
Nominal Required Bearing: 578 kips
Factored Resistance Available: 289 kips
Est. Length: 60 feet
No. of Production Piles: 10
No. of Test Piles: 1 (Stage I Construction)

ELEVATION
(Looking South)




SECTION THRU
SOUTH ABUTMENT (NB)

BILL OF MATERIAL
SOUTH ABUTMENT - SN 100-0086 (N.B)

Bar	No.	Size	Length	Shape
h(E)	18	#5	9'-5"	———
h3(E)	8	#5	22'-8"	———
h4(E)	2	#5	21'-0"	———
h5(E)	2	#5	26'-0"	———
h6(E)	2	#5	11'-10"	———
p1(E)	24	#7	24'-4"	———
p2(E)	12	#7	32'-6"	———
s2(E)	46	#5	11'-5"	□
u(E)	11	#6	7'-2"	———
u1(E)	50	#5	6'-10"	———
v1(E)	134	#5	4'-4"	———
v2(E)	8	#5	10'-2"	———
Concrete Structures		Cu. Yd.	33.8	
Reinforcement Bars, Epoxy Coated		Pound	4190	
Structure Excavation		Cu. Yd.	180	
Furnishing Steel Piles HP14x73		Foot	600	
Driving Piles		Foot	600	
Test Pile Steel HP14x73		Each	1	
Concrete Encasement		Cu. Yd.	4.9	

SOUTH ABUTMENT (STAGE I - NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.) & S.N. 100-0087 (S.B.)



PLAN


DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Namagala	January 22, 2007
PASSED	Ralph E. Anderson	


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	STATES	SHEET NO.	SHEET NO. 36 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	369	
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT			

Contract #98950



ELEVATION
(Looking South)



PLAN

MIN. BAR LAPS

#5 bar = 1'-8"
#7 bar = 4'-10"

Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For bar bending details and Field Cutting Diagram see sheet 33 of 51.
Bars indicated thus 12x2-#7 indicates 12 lines of bars with 2 lengths per line.
For Bill of Material see sheet 35 of 51.

SOUTH ABUTMENT (STAGE II - NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)



DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Demagala*
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 37
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	870	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950



DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007

EXAMINED *Thomas J. Damagala*
ENGINEER OF BRIDGE DESIGN

PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For bar bending details and Field Cutting Diagram see sheet 33 of 51.
Bars indicated thus 12x2-#7 indicates 12 lines of bars with 2 lengths per line.
For Bill of Material see sheet 38 of 51.

MIN. BAR LAPS
#5 bar = 1'-8"
#7 bar = 4'-10"


SOUTH ABUTMENT (STAGE II - SB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

Notes: Four steps monolithically with cap.
 Space reinforcement in cap to miss anchor bolts.
 For Anchor Bolt installation details see sheet 30 of 51.
 For Bar Splicer details see sheet 48 of 51.
 For bar bending details and Field Cutting Diagram see sheet 33 of 51.

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION


ROUTE NO.	SECTION	COUNTY	SHEETS	SHEET	SHEET NO. 38
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	871	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			

Contract #98950



ELEVATION
 (Looking South)


SECTION THRU
 SOUTH ABUTMENT (SB)




PLAN

PILE DATA
 (S. ABUTMENT - SB)

Type: HP14x73
 Nominal Required Bearing: 578 kips
 Factored Resistance Available: 289 kips
 Est. Length: 60 feet
 No. of Production Piles: 12



ANCHOR BOLT OFFSET
 BEAMS 21-23



ANCHOR BOLT OFFSET
 BEAMS 1-20

BILL OF MATERIAL
 SOUTH ABUTMENT - SN 100-0087 (S.B.)

Bar	No.	Size	Length	Shape
h(E)	18	#5	9'-5"	—
h7(E)	2	#5	12'-7"	—
h0(E)	4	#5	25'-2"	—
p(E)	24	#7	26'-10"	—
p3(E)	12	#7	33'-0"	—
s2(E)	50	#5	11'-5"	□
u(E)	10	#6	7'-2"	—
u1(E)	42	#5	6'-10"	—
v1(E)	143	#5	4'-4"	—
v2(E)	8	#5	10'-2"	—
Concrete Encasement	Cu. Yd.		5.3	
Concrete Structures	Cu. Yd.		32.2	
Reinforcement Bars, Epoxy Coated	Pound		4170	
Structure Excavation	Cu. Yd.		180	
Furnishing Steel Piles HP14x73	Foot		720	
Driving Piles	Foot		720	

SOUTH ABUTMENT (STAGE I - SB)
 F.A.I. RT. 57 SEC. (X1-6-2)VB-2

WILLIAMSON COUNTY
 STA. 1516+58.56
 S.N. 100-0086 (N.B.)
 S.N. 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Domagala	January 22, 2007
PASSED	Ralph E. Anderson	

Notes: Four steps monolithically with cap.
 Space reinforcement in cap to miss anchor bolts.
 For Anchor Bolt installation details see sheet 30 of 51.
 For Bar Splicer details see sheet 48 of 51.
 For Bill of Material and bar bending details see sheet 47 of 51.


STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ROUTE NO. F.A.I. 57	SECTION (X1-6-2) VB-2	COUNTY WILLIAMSON	DATE 9-17 87	SHEET 87	SHEET NO. 39 51 SHEETS
ILLINOIS		FED. AID PROJECT-			


Contract #98950

PILE DATA
(PIER 1 - NB)


Type: HP14x73
 Nominal Required Bearing: 578 kips
 Factored Resistance Available: 289 kips
 Est. Length: 60 feet
 No. of Production Piles: 10
 No. of Test Piles: 1 (Stage I Construction)




TOP PLAN



SECTION B-B



ELEVATION
 (Looking South)



SECTION A-A

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.


January 22, 2007
 EXAMINED *Thomas J. Damagala*
 ENGINEER OF BRIDGE DESIGN
 PASSED *Ralph E. Anderson*
 ENGINEER OF BRIDGES AND STRUCTURES

PIER 1 (STAGE I - NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET NO.	SHEET NO. 40
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	9/17	373	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-			


Contract #98950



TOP PLAN



ELEVATION
(Looking South)



SECTION A-A

DESIGNED	Michael D. Cina
CHECKED	Fess Teklehaimanot
DRAWN	DECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Damagalki ENGINEER OF BRIDGE DESIGN
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES

Notes: Four steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Section B-B see sheet 39 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.




MIN. BAR LAP
#5 bars = 1'-8"
#7 bars = 4'-10"

PIER 1 (STAGE II - NB)
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	STATION	SHEET	SHEET NO. 41 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	874	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		

Contract #98950



DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Namagalski
PASSED	Ralph E. Anderson

Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Section B-B see sheet 42 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.

MIN. BAR LAPS

#5 bars = 1'-8"
#7 bars = 4'-10"

PIER 1 (STAGE II - SB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2

WILLIAMSON COUNTY





STA. 1516+58.56

S.N. 100-0086 (N.B.) & S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET NO.	SHEET NO. 42
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	875	51 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT-	

Contract #98950



Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.

PILE DATA
(PIER 1 - SB)

Type: HP14x73
Nominal Required Bearing: 578 kips
Factored Resistance Available: 289 kips
Est. Length: 60 feet
No. of Production Piles: 12

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.



January 22, 2007
EXAMINED *Thomas J. Domagalaki*
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGE DESIGN
ENGINEER OF BRIDGES AND STRUCTURES

PIER 1 (STAGE I - SB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	STATES	SHEET	SHEET NO. 43 51 SHEETS
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	917	876	
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT-	


Contract #98950



SECTION B-B



ELEVATION
(Looking South)



SECTION A-A

PILE DATA
PIER 2-NB

Type: HP14x73
Nominal Required Bearing: 578 kips
Factored Resistance Available: 289 kips
Est. Length: 60 feet
No. of Production Piles: 11

Notes: Four steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Domagala*
ENGINEER OF BRIDGE DESIGN
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

PIER 2 (STAGE I - NB)
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEETS	SHEET NO.
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	877
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	


SHEET NO. 44

51 SHEETS


Contract #98950



TOP PLAN



ELEVATION
(Looking South)



SECTION A-A

Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Section B-B see sheet 43 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.

MIN. BAR LAPS

#5 bars = 1'-8"
#7 bars = 4'-10"

DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.

EXAMINED Thomas J. Damagala
PASSED Ralph E. Anderson
ENGINEER OF BRIDGES AND STRUCTURES

January 22, 2007




PIER 2 (STAGE II - NB)
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.) & S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEET	SHEET NO.
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	917	878
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	

Contract #98950

SHEET NO. 45
51 SHEETS



DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

January 22, 2007

EXAMINED *Thomas J. Damagala*
ENGINEER OF BRIDGE DESIGN

PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Section B-B see sheet 46 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.


MIN. BAR LAPS
#5 bars = 1'-8"
#7 bars = 4'-10"

PIER 2 (STAGE II - SB)
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.) & S.N. 100-0087 (S.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 46 51 SHEETS
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	917	879	
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-		


Contract #98950




TOP PLAN



ELEVATION
(Looking South)



SECTION B-B



SECTION A-A

Notes: Pour steps monolithically with cap.
Space reinforcement in cap to miss anchor bolts.
For Anchor Bolt installation details see sheet 30 of 51.
For Bar Splicer details see sheet 48 of 51.
For Bill of Material and bar bending details see sheet 47 of 51.

PILE DATA
(PIER 2-SB)

Type: HP14x73
Nominal Required Bearing: 578 kips
Factored Resistance Available: 289 kips
Est. Length: 60 feet
No. of Production Piles: 12

23-Bar Splicers (E)
for #5 h3(E) bars
Each Face

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Damagalki PRINCIPAL OF BRIDGE DESIGN	January 22, 2007
PASSED	Ralph E. Anderson ENGINEER OF BRIDGES AND STRUCTURES	

PIER 2 (STAGE I - SB)
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 57	XI-6-2) VB-2	WILLIAMSON	917	330
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	

SHEET NO. 47
51 SHEETS
Contract #98950

BILL OF MATERIAL
PIER 1 - SN 100-0086 (N.B)

Bar	No.	Size	Length	Shape
h ₃ (E)	96	#5	22'-8"	—
h ₄ (E)	2	#5	21'-0"	—
h ₅ (E)	2	#5	26'-0"	—
h ₆ (E)	2	#5	11'-10"	—
h ₈ (E)	44	#5	32'-3"	—
p ₁ (E)	20	#7	24'-4"	—
p ₂ (E)	10	#7	32'-6"	—
s ₃ (E)	56	#5	9'-11"	□
u(E)	7	#6	7'-2"	▭
u ₂ (E)	44	#5	6'-4"	▭
u ₃ (E)	49	#5	7'-2"	▭
v ₃ (E)	158	#5	23'-2"	—
Concrete Structures	Cu. Yd.	147.0		
Reinforcement Bars, Epoxy Coated	Pound	10,660		
Structure Excavation	Cu. Yd.	111		
Furnishing Steel Piles HP14x73	Foot	600		
Driving Piles	Foot	600		
Test Pile Steel HP14x73	Each	1		

BILL OF MATERIAL
PIER 1 - SN 100-0087 (S.B)


Bar	No.	Size	Length	Shape
h ₆ (E)	2	#5	11'-10"	—
h ₈ (E)	46	#5	27'-5"	—
h ₁₀ (E)	96	#5	25'-2"	—
h ₁₁ (E)	2	#5	20'-6"	—
p(E)	20	#7	26'-10"	—
p ₄ (E)	10	#7	27'-9"	—
s ₃ (E)	56	#5	9'-11"	□
u(E)	7	#6	7'-2"	▭
u ₂ (E)	46	#5	6'-4"	▭
u ₃ (E)	43	#5	7'-2"	▭
v ₄ (E)	160	#5	24'-7"	—
Concrete Structures	Cu. Yd.	150.9		
Reinforcement Bars, Epoxy Coated	Pound	10,950		
Structure Excavation	Cu. Yd.	138		
Furnishing Steel Piles HP14x73	Foot	720		
Driving Piles	Foot	720		

BILL OF MATERIAL
PIER 2 - SN 100-0086 (N.B)

Bar	No.	Size	Length	Shape
h ₃ (E)	96	#5	22'-8"	—
h ₄ (E)	2	#5	21'-0"	—
h ₅ (E)	2	#5	26'-0"	—
h ₆ (E)	2	#5	11'-10"	—
h ₈ (E)	44	#5	32'-3"	—
p ₁ (E)	20	#7	24'-4"	—
p ₂ (E)	10	#7	32'-6"	—
s ₃ (E)	56	#5	9'-11"	□
u(E)	7	#6	7'-2"	▭
u ₂ (E)	44	#5	6'-4"	▭
u ₃ (E)	49	#5	7'-2"	▭
v ₅ (E)	158	#5	23'-6"	—
Concrete Structures	Cu. Yd.	149.1		
Reinforcement Bars, Epoxy Coated	Pound	10,660		
Structure Excavation	Cu. Yd.	125		
Furnishing Steel Piles HP14x73	Foot	660		
Driving Piles	Foot	660		


BILL OF MATERIAL
PIER 2 - SN 100-0087 (S.B)

Bar	No.	Size	Length	Shape
h ₁₀ (E)	96	#5	25'-2"	—
h ₁₁ (E)	2	#5	20'-6"	—
h ₁₂ (E)	2	#5	12'-3"	—
h ₁₃ (E)	46	#5	30'-10"	—
p(E)	20	#7	26'-10"	—
p ₅ (E)	10	#7	31'-1"	—
s ₃ (E)	62	#5	9'-11"	□
u(E)	7	#6	7'-2"	▭
u ₂ (E)	46	#5	6'-4"	▭
u ₃ (E)	43	#5	7'-2"	▭
v ₆ (E)	168	#5	24'-10"	—
Concrete Structures	Cu. Yd.	159.6		
Reinforcement Bars, Epoxy Coated	Pound	11,490		
Structure Excavation	Cu. Yd.	153		
Furnishing Steel Piles HP14x73	Foot	720		
Driving Piles	Foot	720		




ANCHOR BOLT OFFSET
BEAMS 1-20


Beam No.	A	B
Beams 1 thru 20	1/4"	7 3/4"
Beam 21	1/8"	7 3/4"
Beam 22	1/4"	7 3/4"
Beam 23	3/8"	7 3/4"




ANCHOR BOLT OFFSET
BEAMS 21-23



BAR s₃(E)



BAR u(E) & u₂(E)



BAR u₃(E)

DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.

January 22, 2007
EXAMINED Thomas J. Demagalaki
PASSED Ralph E. Anderson
ENGINEER OF BRIDGES AND STRUCTURES

PIER DETAILS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 48 51 SHEETS
F.A.I. 57	(X1-6-2) VB-2	WILLIAMSON	917	331	
FED. ROAD DIST. NO. 7	ILLINOIS		FED. AID PROJECT-		

Contract #98950

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.
Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length.
All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars.
Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.
Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:



- ① Minimum Capacity (Tension in kips) = $1.25 \times f_y \times A_t$
- ② Minimum *Pull-out Strength (Tension in kips) = $1.25 \times f_{s_{allow}} \times A_t$

Where f_y = Yield strength of lapped reinforcement bars in ksi.
 $f_{s_{allow}}$ = Allowable tensile stress in lapped reinforcement bars in ksi (Service Load)
 A_t = Tensile stress area of lapped reinforcement bars.
* = 28 day concrete

BAR SPLICER ASSEMBLIES			
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Strength Requirements	
		Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension
#4	1'-8"	14.7	5.9
#5	2'-0"	23.0	9.2
#6	2'-7"	33.1	13.3
#7	3'-5"	45.1	18.0
#8	4'-6"	58.9	23.6
#9	5'-9"	75.0	30.0
#10	7'-3"	95.0	38.0
#11	9'-0"	117.4	46.8


Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."

The diameter of this part is the same as the diameter of the bar spliced.




BAR SPLICER ASSEMBLY ALTERNATIVES

** Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.




INSTALLATION AND SETTING METHODS

"A" : Set bar splicer assembly by means of a template bolt.
"B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms.
(E) : Indicates epoxy coating.




FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

Bar Splicer for #5 bar
Min. Capacity = 23.0 kips - tension
Min. Pull-out Strength = 9.2 kips - tension
No. Required = 304



FOR DIAPHRAGMS AT ABUTMENTS

Bar Splicer for #6 bar
Min. Capacity = 23.0 kips - tension
Min. Pull-out Strength = 9.2 kips - tension
No. Required = 12



STANDARD

Bar Size	No. Assemblies Required	Location
#5	12	Abutment
#5	844	Superstructure
#5	192	Pier
#6	20	Diaphragm
#7	40	Pier
#7	48	Abutment

BAR SPLICER ASSEMBLY DETAILS

F.A.I. RT. 57 SEC. (X1-6-2)VB-2

WILLIAMSON COUNTY

STA. 1516+58.56

S.N. 100-0086 (N.B.)

S.N. 100-0087 (S.B.)

DESIGNED	Michael D. Cima
CHECKED	Fess Teklehaimanot
DRAWN	BECKY M. LEACH
CHECKED	M.D.C. & F.T.

EXAMINED	Thomas J. Domagalala	January 22, 2007
PASSED	Ralph E. Anderson	


BSD-1

10-22-04

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	DATE	SHEET	SHEET NO. 49 51 SHEETS
F.A.I. 57	XI-6-2 VB-2	WILLIAMSON	9/17	332	
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT-			

Contract #98950



DESIGNED Michael D. Cima
CHECKED Fess Teklehaimanot
DRAWN BECKY M. LEACH
CHECKED M.D.C. & F.T.

January 22, 2007
EXAMINED *Thomas J. Domagalala*
PASSED *Ralph E. Anderson*
ENGINEER OF BRIDGES AND STRUCTURES

Note: All dimensions are measured along skew angles unless otherwise indicated.

EXISTING AND PROPOSED PILE LAYOUT
F.A.I. RT. 57 SEC. (XI-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Illinois Department of Transportation SOIL BORING LOG Page 1 of 1
Date 1959

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY
SECTION X1-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086 Station 1516+58.56
BORING NO. 1 Station 1516+93
Offset 32.00ft R.L.C. Survey
Ground Surface Elev. 434.9 ft

DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE	DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE
0	Surface Water Elev. _____ ft		12	Very stiff blue silty sandy clay (continued)	2.78
3	Stream Bed Elev. _____ ft		12		2.66
4	Groundwater Elev.: _____ ft		18	Hard blue silty sandy clay 411.00	4.09
7	First Encounter _____ ft		12	Gray shale 408.10	
8	Upon Completion _____ ft		10		4.25
10	After _____ Hrs. _____ ft		11	Very stiff mottled silty clay 428.00	3.76
13			13	Hard mottled stony clay 423.50	2.94
20			10	Very stiff mottled sandy clay 421.00	2.94
			13	Very stiff blue silty sandy clay 418.00	

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208) BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation SOIL BORING LOG Page 1 of 1
Date 1959

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY
SECTION X1-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086 Station 1516+58.56
BORING NO. 2 Station 1516+13
Offset 32.00ft R.L.C. Survey
Ground Surface Elev. 435.6 ft

DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE	DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE
4	Surface Water Elev. _____ ft		14	Very stiff brown mottled stony clay (continued)	3.42
5	Stream Bed Elev. _____ ft		17		3.92
5	Groundwater Elev.: _____ ft		12	Very stiff brown mottled silty clay 431.50	
6	First Encounter _____ ft		10	Hard brown mottled silty clay 426.50	3.51
7	Upon Completion _____ ft		17	Gray shale 406.50	
8	After _____ Hrs. _____ ft		18		4.49
10			13	Very stiff brown mottled stony clay 421.50	3.92
13			10		3.10
20			10	Hard brown mottled stony clay 417.50	

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208) BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation SOIL BORING LOG Page 1 of 1
Date 1959

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY
SECTION X1-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086 Station 1516+58.56
BORING NO. 3 Station 1516+35
Offset 32.00ft R.L.C. Survey
Ground Surface Elev. 436.3 ft

DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE	DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE
5	Surface Water Elev. _____ ft		17	Very stiff brown mottled silty clay	4.25
6	Stream Bed Elev. _____ ft		16	Hard brown mottled stony clay (continued)	4.00
6	Groundwater Elev.: _____ ft		17		4.17
8	First Encounter _____ ft		7	Gray shale 409.60	
10	Upon Completion _____ ft		7		1.93
13	After _____ Hrs. _____ ft		10	Very stiff mottled clay till 426.50	2.94
16			16		2.94
20			12	Very stiff brown mottled silty stony clay 425.00	3.27
			7	Hard brown mottled stony clay 417.50	3.80
			10		3.27

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208) BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation SOIL BORING LOG Page 1 of 1
Date 1959

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY
SECTION X1-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086 Station 1516+58.56
BORING NO. 4 Station 1517+28
Offset 32.00ft R.L.C. Survey
Ground Surface Elev. 437.8 ft

DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE	DEPTH (ft)	SOIL DESCRIPTION	UNCONSOLIDATED COMPRESSIVE STRENGTH (UCS) FAILURE MODE
10	Surface Water Elev. _____ ft		10	Stiff yellow loessial silty clay	Lost sample
10	Stream Bed Elev. _____ ft		10	Stiff mottled clay till 435.00	Lost sample
14	Groundwater Elev.: _____ ft		14		3.23
17	First Encounter _____ ft		7	Hard gray mottled stony clay till 411.00	4.17
18	Upon Completion _____ ft		7		1.93
20	After _____ Hrs. _____ ft		10	Very stiff mottled clay till 426.50	2.94
			16		2.94
			12	Very stiff mottled sandy clay till 423.50	2.36
			9	Gray shale 405.50	2.41
			10		3.23
			10	Very stiff mottled sandy clay till 418.00	10.22
			10		10.22

Note: No stability problem

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208) BBS, form 137 (Rev. 8-99)

BORING LOGS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET	SHEET NO. 51
F.A.I. 57	XI-6-2/VB-2	WILLIAMSON	917	834	51 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS				FED. AID PROJECT-

Contract #98950

Illinois Department of Transportation
Division of Highways
Region 5 / District 9

SOIL BORING LOG

Page 1 of 2
Date 6/00

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY Bryan Keller
SECTION XI-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086
Station 1516+58.56

BORING NO. 1-S
Station 1516+58
Offset 6.00ft Rt. of Roadway
Ground Surface Elev. 465.3 ft

Surface Water Elev. ft	D	B	U	M	Surface Water Elev. ft	D	B	U	M
Stream Bed Elev. ft	E	L	C	O	Stream Bed Elev. ft	E	L	C	O
	P	O	S	I		P	O	S	I
	T	W	S			T	W	S	
	H	S	Qu	T		H	S	Qu	T
Groundwater Elev.: First Encounter 42.0 ft Upon Completion 42.0 ft After 425.3 Hrs. 461.3 ft									
(ft) (6") (tsf) (%)	(ft) (6") (tsf) (%)								
Soft, very moist, brown to grey Silty Clay A-6									
460.80									
Very stiff, moist, brown mottled grey, Clay A7-6									
458.30									
Stiff, moist, brown mottled grey, Clay A7-6									
453.30									
Stiff, moist, brown mottled grey, Silty Clay Loam A-6									
450.80									
Medium, very moist, grey mottled brown, Clay A7-6									
448.30									
Stiff to very stiff, moist, grey mottled brown, Silty Clay to Silty Clay Loam A-6									
425.80									

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208)
BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation
Division of Highways
Region 5 / District 9

SOIL BORING LOG

Page 2 of 2
Date 6/00

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY Bryan Keller
SECTION XI-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086
Station 1516+58.56

BORING NO. 1-S
Station 1516+58
Offset 6.00ft Rt. of Roadway
Ground Surface Elev. 465.3 ft

Surface Water Elev. ft	D	B	U	M	Surface Water Elev. ft	D	B	U	M
Stream Bed Elev. ft	E	L	C	O	Stream Bed Elev. ft	E	L	C	O
	P	O	S	I		P	O	S	I
	T	W	S			T	W	S	
	H	S	Qu	T		H	S	Qu	T
Groundwater Elev.: First Encounter 42.0 ft Upon Completion 42.0 ft After 425.3 Hrs. 461.3 ft									
(ft) (6") (tsf) (%)	(ft) (6") (tsf) (%)								
Medium, very moist, brown mottled brown, Clay to Silty Clay A7-6 (continued)									
420.80									
Stiff, moist, brown, Silty Clay Loam A-6 with sand layers									
415.80									
Stiff to very stiff, moist, brown mottled grey, Silty Clay Loam with some fine gravel									
415.80									
Stiff, moist, grey, Silty Loam to Silty Clay Loam A-4									
435.80									
Medium, moist, grey, Silty Loam to Silty Clay Loam A-4									
433.30									
Medium, very moist, grey, Silty Clay to Silty Clay Loam A-6									
430.80									
Medium, very moist, grey mottled brown, Clay A7-6									
450.80									
Stiff to very stiff, moist, grey mottled brown, Silty Clay to Silty Clay Loam A-6									
448.30									
Very stiff, moist, brown mottled grey, Clay A7-6									
428.30									
Stiff, moist, brown, Silty Clay A7-6									
426.10									

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208)
BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation
Division of Highways
Region 5 / District 9

SOIL BORING LOG

Page 1 of 2
Date 6/00

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY Bryan Keller
SECTION XI-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086
Station 1516+58.56

BORING NO. 2-S
Station 1517+57
Offset 6.00ft Rt. of Roadway
Ground Surface Elev. 465.8 ft

Surface Water Elev. ft	D	B	U	M	Surface Water Elev. ft	D	B	U	M
Stream Bed Elev. ft	E	L	C	O	Stream Bed Elev. ft	E	L	C	O
	P	O	S	I		P	O	S	I
	T	W	S			T	W	S	
	H	S	Qu	T		H	S	Qu	T
Groundwater Elev.: First Encounter 49.5 ft Upon Completion 58.0 ft After 425.3 Hrs. 461.3 ft									
(ft) (6") (tsf) (%)	(ft) (6") (tsf) (%)								
Very stiff, moist, brown mottled grey, Silty Clay A7-6									
461.10									
Stiff to very stiff, moist, brown mottled grey Silty Clay A-6									
451.10									
Stiff, moist, grey, Clay Loam A-4									
441.10									
Stiff, moist, grey mottled brown, Silty Clay to Silty Clay Loam A-6									
438.60									
Stiff, moist, brown mottled grey, Clay A7-6									
456.10									
Stiff, moist to very moist, brown mottled grey, Clay A7-6 with some gravel									
456.10									
Medium, very moist, grey, Silty Clay to Clay A7-6									
433.60									
Very stiff, moist, brown mottled grey, Clay A7-6									
431.10									
Stiff, moist to very moist, brown mottled grey, Clay A7-6									
428.60									
Stiff, moist to very moist, brown mottled grey, Clay A7-6									
426.10									

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208)
BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation
Division of Highways
Region 5 / District 9

SOIL BORING LOG

Page 2 of 2
Date 6/00

ROUTE FAI 57 DESCRIPTION bridge over railroad LOGGED BY Bryan Keller
SECTION XI-6VB LOCATION in Marion, SEC., TWP. 9S, RNG. 2E, 3 PM
COUNTY Williamson DRILLING METHOD HAMMER TYPE

STRUCT. NO. 100-0086
Station 1516+58.56

BORING NO. 2-S
Station 1517+57
Offset 6.00ft Rt. of Roadway
Ground Surface Elev. 465.8 ft

Surface Water Elev. ft	D	B	U	M	Surface Water Elev. ft	D	B	U	M
Stream Bed Elev. ft	E	L	C	O	Stream Bed Elev. ft	E	L	C	O
	P	O	S	I		P	O	S	I
	T	W	S			T	W	S	
	H	S	Qu	T		H	S	Qu	T
Groundwater Elev.: First Encounter 49.5 ft Upon Completion 58.0 ft After 425.3 Hrs. 461.3 ft									
(ft) (6") (tsf) (%)	(ft) (6") (tsf) (%)								
Medium, very moist, brown mottled grey, Silty Clay A7-6 (continued)									
404.60									
Hard, dry, brown Clay Shale									
403.10									
Bottom of hole = 62.3 feet									
Free water observed at 39.6 feet									
Elevation referenced to 1960 plans									
To convert "N" values to "N60" values, multiply by 1.25									
Stiff, moist, brown, Silty Clay A-6									
421.10									
Stiff, moist, brown, Silty Clay A7-6 with some fine gravel									
416.10									

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T208)
BBS, form 137 (Rev. 8-99)


BORING LOGS
F.A.I. RT. 57 SEC. (X1-6-2)VB-2
WILLIAMSON COUNTY
STA. 1516+58.56
S.N. 100-0086 (N.B.)
S.N. 100-0087 (S.B.)

GFL013.DWG SEPT. 15, 2005


BENCHMARK: PAINTED MARK ON MOST NORTHEAST CORNER OF EXISTING BRIDGE DECK, S.N. 100-0004 (N.B.) STA. 1529+18.38, 56.12' LT. @ F.A.I. 57 EL. 471.53

EXISTING STRUCTURE:
S.N. 100-0004 (N.B.) AND S.N. 100-0005 (S.B.) THE EXISTING STRUCTURES WERE BUILT IN 1960 UNDER F.A.I. ROUTE 57 SECTION XI-6HB-2. BOTH STRUCTURES CONSIST OF THREE CONTINUOUS SPANS (40'-7", 69'-2", 40'-7") FOR A TOTAL LENGTH OF 154'-0" MEASURED BACK TO BACK OF ABUTMENTS. THE SUPERSTRUCTURES CONSIST OF A 7" REINFORCED CONCRETE DECK ON WIDE FLANGE BEAMS. THE WIDE FLANGE BEAMS ARE COMPOSITE IN THE CENTER SPAN AND HINGED IN THE END SPANS. THE SUPERSTRUCTURES ARE SUPPORTED BY HAMMERHEAD TYPE PIERS ON PILE SUPPORTED FOOTINGS AND PILE BENT ABUTMENTS. THE OUT TO OUT DECK WIDTH OF THE NORTHBOUND STRUCTURE VARIES FROM 41'-11 1/8" TO 36'-9 5/8". THE OUT TO OUT DECK WIDTH OF THE SOUTHBOUND STRUCTURE VARIES FROM 53'-1 1/4" TO 51'-5 1/2". THE EXISTING STRUCTURES SHALL BE REMOVED IN STAGES AND DISPOSED OF ACCORDING TO SECTION 501 OF THE STANDARD SPECIFICATIONS. THE ROADWAY SHALL REMAIN OPEN TO TRAFFIC, USING STAGE CONSTRUCTION, DURING THE CONSTRUCTION PERIOD.


SALVAGE: SEE SPECIAL PROVISIONS FOR SALVAGE.




LOCATION SKETCH



PROFILE GRADE - F.A.I. RT. 57 NORTHBOUND & SOUTHBOUND LANES



PROFILE GRADE - EASTBOUND WEST MAIN STREET (MEDIAN EDGE OF LANE)




PROFILE GRADE - WESTBOUND WEST MAIN STREET (MEDIAN EDGE OF LANE)


BASELINE STATIONS ARE BASED ON GEOMETRICS ESTABLISHED IN OCTOBER 2002 AND ADJUSTED TO CLOSELY MATCH EXISTING PLANS

****RAMP "FF" BASELINE**
NOTE: THE S.B. TAPER OF THE RAMP BASELINE BEGINS AT STA. 1528+31.64, OFFSET 36.30' RT. AND ENDS AT STA. 1534+46.52, OFFSET 24.00' RT.

30'-0" BRIDGE APPROACH PAVEMENT STD. 420401 (SPECIAL)



ELEVATION



PLAN

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 57	(X1-6) HBK-2	WILLIAMSON	917	835
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

Contract #98950

DESIGN SPECIFICATIONS

2002 AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, 17TH EDITION

DESIGN STRESSES

FIELD UNITS
f'c = 3,500 psi
fy = 60,000 psi (REINF.)

STRUCTURAL STEEL

fy = 50,000 psi (M270, GRADE 50)
fy = 36,000 psi (M270, GRADE 36)

LOADING HS20-44 & ALT. MILITARY LOADING
ALLOW 50 psf FOR FUTURE WEARING SURFACE.

SEISMIC DATA

SEISMIC PERFORMANCE CATEGORY (SPC): B
BEDROCK ACCELERATION COEFFICIENT (A): 12.2%
SITE COEFFICIENT (S) = 1.5 (TYPE III)

STATION 1529+96.11
BUILT BY STATE OF ILLINOIS
F.A.I. RT 57 SEC. (X1-6) HBK-2
LOADING HS20 & ALT. STR. NO. 100-0084 (N.B.)

STATION 1529+96.11
BUILT BY STATE OF ILLINOIS
F.A.I. RT 57 SEC. (X1-6) HBK-2
LOADING HS20 & ALT. STR. NO. 100-0085 (S.B.)

NAME PLATES

See Std. 515001



Structural Engineer
Clark Dietz, Inc.
DATE: 1/22/07
Expires 11-30-2008

"I CERTIFY THAT TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THIS BRIDGE DESIGN IS STRUCTURALLY ADEQUATE FOR THE DESIGN LOADING SHOWN ON THE PLANS. THE DESIGN IS AN ECONOMICAL ONE FOR THE STYLE OF STRUCTURE AND COMPLIES WITH REQUIREMENTS OF THE CURRENT 'AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES'."

****RAMP GORE VARIES:**
15'-8 1/2" (N. ABUT.)
TO 6'-5 1/2" (S. ABUT.)

****SHOULDER AND RAMP DIMENSIONS** MEASURED PERPENDICULAR TO RAMP BASELINE. ADJUST RAMP GORE DIMENSIONS ACCORDINGLY.


APPROVED
FOR STRUCTURAL ADEQUACY ONLY

Robert E. Anderson
Engineer of Bridges and Structures
MEDIAN CONCRETE BARRIER & MEDIAN DRAINAGE SYSTEM PER RDWY. PLANS (EACH END)

****RAMP GORE VARIES:**
6'-10 1/2" (N. ABUT.)
TO 3'-4 3/4" (S. ABUT.)

GENERAL PLAN & ELEVATION

INTERSTATE 57 OVER WEST MAIN ST. (OLD IL RT. 13) F.A.I. RT. 57 SEC. (X1-6)HBK-2 WILLIAMSON COUNTY STATION 1529+96.11 STRUCTURE NO. 100-0084 (N.B.) STRUCTURE NO. 100-0085 (S.B.)



1617 SOUTH NEIL STREET SUITE 100 CHAMPAIGN, IL 61820 PHONE: 217-579-8800 FAX: 217-579-8802


GENERAL NOTES

- Fasteners shall be high strength bolts. Bolts $7/8"$ ϕ , open holes $15/16"$ ϕ , unless otherwise noted.
- Calculated weight of Structural Steel = 828,440 lbs M270 Gr. 50
22,200 lbs M270 Gr. 36
- Field welding of construction accessories will not be permitted to beams.
- Anchor bolts shall be set before bolting diaphragms over supports.
- The main load carrying member components subject to tensile stress shall conform to the Supplemental Requirements for Notch Toughness Zone 2. These components are the wide flange beams and all splice plate material.
- Reinforcement bars shall conform to the requirements of Illinois Modified ASTM A706.
- Slope wall shall be reinforced with welded wire fabric, 6"x6"-W4.0xW4.0, weighing 58 lbs. per 100 sq. ft.
- The embankment configuration shown shall be the minimum embankment that must be constructed prior to construction of the abutments.
- The inorganic zinc rich primer/Acrylic/Acrylic Paint System shall be used for shop and field painting of new structural steel except where otherwise noted. The color of the final finish coat for all interior steel surfaces shall be gray, Munsell No. 5B 7/1. The color of the final finish coat for exterior and bottom flange of the fascia beams shall be blue, Munsell No. 10B 3/6. See Special Provision for "Cleaning and Painting New Metal Structures."
- Bearing seal surfaces shall be constructed or adjusted to the designated elevations within a tolerance of $1/8$ inch. Adjustment shall be made either by grinding the surface or by shimming the bearing. Two $1/8$ " adjusting shims, of the dimensions of the bottom bearing plates, shall be provided for each bearing in addition to all other plates or shims.
- The Contractor shall drive 6 HP12x53 test piles in permanent locations: one at the South Abutment, one at the North Abutment, and the Pier for both Northbound and Southbound bridges as directed by the Engineer before ordering the remainder of piles.
- In addition to all other requirements of section 512 of the Standard Specifications, splices for HP12x53 piles shall develop the full capacity of the steel's cross sectional area of the pile for tension, shear and bending forces. One approved method of achieving this requirement is full penetration butt welding of the entire cross section. Other types of splices meeting the full capacity requirement may be allowed subject to the approval of the Engineer. Any proposal by the Contractor to use an alternate splice method must include adequate documentation demonstrating that the full tension, shear and bending capacities will be met. Appropriate welder qualifications will be required for the positions and processes used in splicing all piles. Nondestructive testing of completed welds will be limited to visual inspection.
- Reinforcing bars designated (E) shall be epoxy coated.
- The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Porous Granular Embankment (Special)	Cu. Yd.		440	440
Slope wall 4 Inch	Sq. Yd.		1,620	1,620
Preformed Joint Seal 2 1/2"	Foot	174		174
* Removal of Existing Structures #1	Each			1
* Removal of Existing Structures #2	Each			1
Structure Excavation	Cu. Yd.		947	947
Floor Drains	Each	24		24
Concrete Structures	Cu. Yd.		388.5	388.5
Concrete Superstructure	Cu. Yd.	849.4		849.4
Protective Coat	Sq. Yd.		3,218	3,218
Furnishing and Erecting Structural Steel	L. Sum	0.7		0.7
Stud Shear Connectors	Each	17,526		17,526
Reinforcement Bars, Epoxy Coated	Pound	193,020	71,880	264,900
Furnishing Steel Piles HP12x53	Foot		2,739	2,739
Driving Piles	Foot		2,739	2,739
Test Pile Steel HP12x53	Each		6	6
Name Plates	Each	2		2
Geocomposite Wall Drain	Sq. Yd.		208	208
Pipe Underdrains for Structures 4"	Foot		374	374
Temporary Sheet Piling	Sq. Ft.		730	730
Bar Splicers	Each	1,462	162	1,624
Protective Shield	Sq. Yd.		711	711
Bridge Deck Grooving	Sq. Yd.	2,843		2,843
Formliner Textured Surface	Sq. Ft.		1,542	1,542
Temporary Support System	L. Sum	1		1
Anchor Bolts, 1" ϕ	Each	92		92
Anchor Bolts, 1/2" ϕ	Each	46		46
Concrete Encasement	Cu. Yd.		17.5	17.5

*Structure #1 is N.B., Structure #2 is S.B.



FOOTING LAYOUT

ROUTE NO.	SECTION	COUNTY	SHEET NO.	SHEET TOTAL
FAT 57	(X1-6) HBK-2	WILLIAMSON	917	886
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

SHEET NO. 2
32 SHEETS

Contract #98950

INDEX OF DRAWINGS

- S-1 General Plan & Elevation
- S-2 General Notes & Bill of Material
- S-3 Temporary Sheet Piling
- S-4 Stage Construction Details
- S-5 Top of Deck Plan
- S-6 Top of Deck Elevations
- S-7 Top of Deck Elevations
- S-8 Top of Deck Elevations
- S-9 Top of Deck Elevations
- S-10 Deck Plan & Cross Section, Northbound
- S-11 Deck Plan & Cross Section, Southbound
- S-12 Parapet Details
- S-13 Diaphragm Elevations, Northbound
- S-14 Diaphragm Elevations, Southbound
- S-15 Superstructure Bill of Material & Light Pole Base
- S-16 Framing Plan, Northbound
- S-17 Framing Plan, Southbound
- S-18 Structural Steel Details, Fixed Bearing Details & Moment Table
- S-19 North Abutment, Northbound
- S-20 North Abutment, Southbound
- S-21 South Abutment, Northbound
- S-22 South Abutment, Southbound
- S-23 Pier, Northbound
- S-24 Pier, Southbound
- S-25 Pier Details, Northbound & Southbound
- S-26 Pier Form Liner Details and Temporary Support System
- S-27 Bar Splicer Assembly Details
- S-28 Temporary Concrete Barrier For Stage Construction
- S-29 Boring Logs
- S-30 Boring Logs
- S-31 Boring Logs
- S-32 Boring Logs

GENERAL NOTES & BILL OF MATERIAL

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
No. 184-000450
Clark Dietz
ENGINEERS
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923


NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM	PROJECT NO: 102314
DRAWN BY: MEW	DATE: 05/2006
CHECKED BY: SLD	
APPROVED BY: SMM	
ACTIVITY	INITIALS


DRAWING NUMBER

S-2

Note:
Existing timber approach piles and steel HP8x36 wingwall piles shall be removed to 1' below excavation line. Cost included with "Removal of Existing Structures".




TEMPORARY SHEET PILING AND ABUTMENT REMOVAL DETAILS AT NORTH ABUTMENT




TEMPORARY SHEET PILING AND ABUTMENT REMOVAL DETAILS AT SOUTH ABUTMENT

NOTES

- 1) If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.
- 2) The Contractor shall connect the first sheet to the existing abutment wall to ensure stability of sheets driven to the top of the existing footing. This connection shall be reviewed and accepted by the Engineer and included in the cost for Temporary Sheet Piling.




PLAN AT ABUTMENT



SECTION THRU ABUTMENT AND SLOPEWALL
(Horiz. dim. @ Rt. L's)

*Included in the cost of Pipe Underdrains for Structures.
**The cost of the 2\"/>

Note:
All drainage system components shall extend to 2'-0\"/>




NOTE

The cost of the 2\"/>



TEMPORARY SHEET PILING	
INTERSTATE 57 OVER WEST MAIN ST. (OLD IL RT. 13) F.A.I. RT. 57 SEC. (X1-6)HBK-2 WILLIAMSON COUNTY STATION 1529+96.11 STRUCTURE NO. 100-0084 (N.B.) STRUCTURE NO. 100-0085 (S.B.)	
DESIGN FIRM REGISTRATION No. 184-000450 Clark Dietz ENGINEERS 1817 SOUTH NEIL STREET SUITE 100 CHAMPAIGN, IL 61820 PHONE : 217.373.8900 FAX : 217.373.8923	
DESIGNED BY: SHM DRAWN BY: MEW CHECKED BY: SLD APPROVED BY: SHM	PROJECT NO: 102314 DATE: 05/2006 INITIALS
DRAWING NUMBER	
S-3	

Contract #98950



NOTES:

1. HATCHED AREA INDICATES REMOVAL OF EXISTING STRUCTURES.
2. REMOVAL OF EXISTING BRIDGE RAILING AND BITUMINOUS WEARING SURFACE IS INCLUDED IN REMOVAL OF EXISTING STRUCTURES.
3. SEE DWG. S-28 FOR TEMPORARY CONCRETE BARRIER DETAILS.
4. FOR QUANTITIES OF TEMPORARY CONCRETE BARRIER SEE ROADWAY PLANS.
5. THE CONTRACTOR SHALL NOT REMOVE ANY PORTION OF THE EXISTING PIERS UNTIL AFTER STAGE I CONSTRUCTION IS COMPLETED AND TRAFFIC IS TRANSFERRED TO THE STAGE I TRAFFIC LANES. DURING THE REMOVAL OF THE EXISTING PIERS, THE CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO AVOID DAMAGING THE PROPOSED NEW STRUCTURAL STEEL.
6. THE EXISTING ABUTMENTS SHALL BE REMOVED IN STAGES ALONG THE SAME LINE AS FOR REMOVAL OF THE EXISTING SUPERSTRUCTURE. SEE DWG. S-3 FOR ADDITIONAL DETAILS.



STAGE CONSTRUCTION DETAILS

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
No. 184-000450
Clark Dietz
ENGINEERS
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO: 102314
DRAWN BY: MEW DATE: 05/2006
CHECKED BY: SLD
APPROVED BY: SMM
ACTIVITY: DETAILS

DRAWING NUMBER

S-4

DESIGNED: B.G.H.
CHECKED: L.D.G.
DRAWN: K.H.L.
CHECKED: B.G.H.

Contract #98950





TABLE OF DEFLECTIONS

BEAM NO.	AA	BB	CC	DD	EE	FF
Beam 1	1 9/16"	1 7/8"	7/8"	3/4"	1 5/8"	1 3/8"
Beams 2 to 4	1 1/16"	1 15/16"	7/8"	9/16"	1 5/16"	1 1/16"
Beam 5	1 7/16"	1 3/4"	7/8"	1 1/16"	1 1/2"	1 1/4"
Beams 6 to 11; 14 to 22	1 7/16"	1 3/4"	1 5/16"	1 3/16"	1 3/4"	1 7/16"
Beams 12, 13 & 23	1 9/16"	1 7/8"	7/8"	7/8"	1 7/8"	1 9/16"

Note:
The above deflections are not to be used in the field if the engineer is working from the grade elevations adjusted for dead load deflections as shown on Dwg. S-6 thru S-9.



TOP OF DECK PLAN

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. SEC. (XI-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
No. 184-000450
Clark Dietz
ENGINEERS
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO: 102314
DRAWN BY: MEW DATE: 05/2006
CHECKED BY: SLD
APPROVED BY: SMM
ACTIVITY: DETAILS

DRAWING NUMBER
S-5

SOUTHBOUND STAGE CONSTRUCTION LINE & BASELINE

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	1529+07.557	12.000	472.933	472.933
@ Brg. N. Abut.	1529+08.808	12.000	472.932	472.932
A	1529+18.808	12.000	472.931	472.995
B	1529+28.808	12.000	472.927	473.042
C	1529+38.808	12.000	472.921	473.066
D	1529+48.808	12.000	472.914	473.062
E	1529+58.808	12.000	472.905	473.033
F	1529+68.808	12.000	472.895	472.983
G	1529+78.808	12.000	472.882	472.926
H	1529+88.808	12.000	472.868	472.878
@ Brg. Pier	1529+94.557	12.000	472.859	472.859
I	1530+04.557	12.000	472.842	472.863
J	1530+14.557	12.000	472.823	472.886
K	1530+24.557	12.000	472.803	472.909
L	1530+34.557	12.000	472.781	472.919
M	1530+44.557	12.000	472.757	472.907
N	1530+54.557	12.000	472.731	472.868
O	1530+64.557	12.000	472.704	472.800
P	1530+74.557	12.000	472.674	472.712
@ Brg. S. Abut.	1530+80.306	12.000	472.657	472.657
Bk. S. Abut.	1530+81.557	12.000	472.653	472.653

BEAM NO. 19

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	1529+07.513	13.250	472.907	472.907
@ Brg. N. Abut.	1529+08.764	13.250	472.906	472.906
A	1529+18.764	13.250	472.905	472.969
B	1529+28.764	13.250	472.901	473.016
C	1529+38.764	13.250	472.895	473.040
D	1529+48.764	13.250	472.888	473.036
E	1529+58.764	13.250	472.879	473.007
F	1529+68.764	13.250	472.869	472.957
G	1529+78.764	13.250	472.856	472.900
H	1529+88.764	13.250	472.842	472.852
@ Brg. Pier	1529+94.513	13.250	472.833	472.833
I	1530+04.513	13.250	472.816	472.837
J	1530+14.513	13.250	472.797	472.860
K	1530+24.513	13.250	472.777	472.883
L	1530+34.513	13.250	472.755	472.893
M	1530+44.513	13.250	472.731	472.881
N	1530+54.513	13.250	472.705	472.842
O	1530+64.513	13.250	472.678	472.774
P	1530+74.513	13.250	472.648	472.686
@ Brg. S. Abut.	1530+80.262	13.250	472.631	472.631
Bk. S. Abut.	1530+81.513	13.250	472.627	472.627

BEAM NO. 20

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	1529+07.266	20.250	472.735	472.735
@ Brg. N. Abut.	1529+08.517	20.250	472.734	472.734
A	1529+18.517	20.250	472.729	472.793
B	1529+28.517	20.250	472.721	472.836
C	1529+38.517	20.250	472.712	472.856
D	1529+48.517	20.250	472.701	472.849
E	1529+58.517	20.250	472.688	472.815
F	1529+68.517	20.250	472.673	472.762
G	1529+78.517	20.250	472.657	472.701
H	1529+88.517	20.250	472.639	472.649
@ Brg. Pier	1529+94.266	20.250	472.628	472.628
I	1530+04.266	20.250	472.607	472.628
J	1530+14.266	20.250	472.585	472.647
K	1530+24.266	20.250	472.560	472.666
L	1530+34.266	20.250	472.534	472.673
M	1530+44.266	20.250	472.506	472.657
N	1530+54.266	20.250	472.477	472.614
O	1530+64.266	20.250	472.446	472.542
P	1530+74.266	20.250	472.412	472.450
@ Brg. S. Abut.	1530+80.015	20.250	472.393	472.393
Bk. S. Abut.	1530+81.266	20.250	472.388	472.388

BEAM NO. 21

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	1529+07.020	27.250	472.455	472.455
@ Brg. N. Abut.	1529+08.270	27.250	472.454	472.454
A	1529+18.270	27.250	472.449	472.513
B	1529+28.270	27.250	472.441	472.556
C	1529+38.270	27.250	472.432	472.576
D	1529+48.270	27.250	472.421	472.569
E	1529+58.270	27.250	472.408	472.536
F	1529+68.270	27.250	472.394	472.482
G	1529+78.270	27.250	472.378	472.421
H	1529+88.270	27.250	472.360	472.369
@ Brg. Pier	1529+94.020	27.250	472.348	472.348
I	1530+04.020	27.250	472.328	472.348
J	1530+14.020	27.250	472.305	472.367
K	1530+24.020	27.250	472.281	472.387
L	1530+34.020	27.250	472.255	472.393
M	1530+44.020	27.250	472.227	472.377
N	1530+54.020	27.250	472.198	472.335
O	1530+64.020	27.250	472.166	472.263
P	1530+74.020	27.250	472.133	472.171
@ Brg. S. Abut.	1530+79.769	27.250	472.113	472.113
Bk. S. Abut.	1530+81.020	27.250	472.109	472.109

BEAM NO. 22

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	1529+06.773	34.250	472.175	472.175
@ Brg. N. Abut.	1529+08.024	34.250	472.174	472.174
A	1529+18.024	34.250	472.169	472.233
B	1529+28.024	34.250	472.161	472.277
C	1529+38.024	34.250	472.152	472.296
D	1529+48.024	34.250	472.141	472.289
E	1529+58.024	34.250	472.128	472.256
F	1529+68.024	34.250	472.114	472.203
G	1529+78.024	34.250	472.098	472.141
H	1529+88.024	34.250	472.080	472.090
@ Brg. Pier	1529+93.773	34.250	472.069	472.069
I	1530+03.773	34.250	472.048	472.069
J	1530+13.773	34.250	472.026	472.088
K	1530+23.773	34.250	472.001	472.107
L	1530+33.773	34.250	471.975	472.114
M	1530+43.773	34.250	471.948	472.098
N	1530+53.773	34.250	471.918	472.055
O	1530+63.773	34.250	471.887	471.984
P	1530+73.773	34.250	471.854	471.892
@ Brg. S. Abut.	1530+79.522	34.250	471.834	471.834
Bk. S. Abut.	1530+80.773	34.250	471.830	471.830

BEAM NO. 23

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	1529+06.526	41.250	471.895	471.895
@ Brg. N. Abut.	1529+07.777	41.250	471.894	471.894
A	1529+17.777	41.250	471.889	471.958
B	1529+27.777	41.250	471.881	472.004
C	1529+37.777	41.250	471.872	472.026
D	1529+47.777	41.250	471.861	472.019
E	1529+57.777	41.250	471.849	471.985
F	1529+67.777	41.250	471.834	471.929
G	1529+77.777	41.250	471.818	471.864
H	1529+87.777	41.250	471.800	471.811
@ Brg. Pier	1529+93.526	41.250	471.789	471.789
I	1530+03.526	41.250	471.769	471.790
J	1530+13.526	41.250	471.746	471.812
K	1530+23.526	41.250	471.722	471.835
L	1530+33.526	41.250	471.696	471.844
M	1530+43.526	41.250	471.668	471.829
N	1530+53.526	41.250	471.639	471.785
O	1530+63.526	41.250	471.608	471.711
P	1530+73.526	41.250	471.575	471.615
@ Brg. S. Abut.	1530+79.275	41.250	471.555	471.555
Bk. S. Abut.	1530+80.526	41.250	471.551	471.551

TOP OF DECK ELEVATIONS

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (XI-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

Clark Dietz
ENGINEERS

DESIGN FIRM REGISTRATION
NO. 184-000450
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DRAWING NUMBER


DESIGNED BY: SMH PROJECT NO: 102314
DRAWN BY: MCV DATE: 05/2006
CHECKED BY: SLD
APPROVED BY: SMH
ACTIVITY: DETAILS

S-9

Contract #98950

NOTES

1. See Dwg. S-15 for Superstructure Details and Bill of Material.
2. Bars indicated thus 20x3-#5 etc. indicates 20 lines of bars with 3 lengths per line.
3. See Dwg. S-12 for parapet reinforcement.
4. See Dwg. S-27 for Bar Splicer Details.
5. See Dwg. S-1 for Floor Drain locations.
6. For Section B-B see Dwg. S-13.




*Order a20(E) and a21(E) bars full length. Cut to fit skew and use remainder of bars in opposite end.

MIN. BAR LAP

#5	2'-2"
#6	2'-7"

PLAN-NORTHBOUND



**Spacing of #5 b2(E) bars vary between beams 1 and 5.

*** Shoulder and ramp dimensions measured perpendicular to ramp baseline. Adjust ramp gore dimensions accordingly.

DECK PLAN & CROSS SECTION, NORTHBOUND

INTERSTATE 57 OVER WEST MAIN ST. (OLD IL RT. 13) F.A.I. RT. 57 SEC. (X1-6)HBK-2 WILLIAMSON COUNTY STATION 1529+96.11 STRUCTURE NO. 100-0084 (N.B.) STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION No. 184-000450

Clark Dietz ENGINEERS

1817 SOUTH NEIL STREET SUITE 100 CHAMPAIGN, IL 61820 PHONE : 217.373.8900 FAX : 217.373.8923

NOTICE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.


DESIGNED BY: SMM PROJECT NO: 102314
 DRAWN BY: HEW DATE: 05/2006
 CHECKED BY: SLD
 APPROVED BY: SMM
 ACTIVITY: INITIALS

DRAWING NUMBER **S-10**


Contract #98950

NOTES

1. See Dwg. S-15 for Superstructure Details and Bill of Material.
2. Bars indicated thus 20x3-#5 etc. indicates 20 lines of bars with 3 lengths per line.
3. See Dwg. S-12 for parapet reinforcement.
4. See Dwg. S-27 for Bar Splicer Details.
5. See Dwg. S-1 for Floor Drain locations.
6. For Section C-C see Dwg. S-14.



PLAN-SOUTHBOUND



NEAR PIER

CROSS SECTION
(Looking South)

NEAR MIDSPAN

MIN. BAR LAP

#5	2'-2"
#6	2'-7"

DECK PLAN & CROSS SECTION, SOUTHBOUND


INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

Clark Dietz ENGINEERS


DESIGN FIRM REGISTRATION No. 184-000450
1817 SOUTH NEIL STREET SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

DESIGNED BY: SMM	PROJECT NO: 102314
DRAWN BY: MEW	DATE: 05/20/86
CHECKED BY: SLD	
APPROVED BY: SMM	
ACTIVITY: DETAILS	

*** Shoulder and ramp dimensions measured perpendicular to ramp baseline. Adjust ramp gore dimensions accordingly.




INSIDE ELEVATION OF PARAPET




INSIDE ELEVATION OF MEDIAN BARRIER

MIN. BAR LAP

#5	1'-8"
#8	3'-8"




DETAIL 1




PARAPET JOINT DETAILS

Notes:
The exterior surfaces of the floor drains shall be painted with the finish coat as specified in the special provisions for Cleaning and Painting New Metal Structures. The exterior surfaces of the drains shall be cleaned according to Steel Structures Painting Council's Spec. SSPC-SP1 prior to painting.
Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.



SECTION THRU OUTER PARAPET


See Dwg. S-14 for Section D-D.



SECTION THRU MEDIAN PARAPET


PARAPET DETAILS	
INTERSTATE 57 OVER WEST MAIN ST. (OLD IL RT. 13) F.A.I. RT. 57 SEC. (XI-6)HBK-2 WILLIAMSON COUNTY STATION 1529+96.11 STRUCTURE NO. 100-0084 (N.B.) STRUCTURE NO. 100-0085 (S.B.)	
Clark Dietz ENGINEERS	
DESIGN FIRM REGISTRATION No. 184-000450 1817 SOUTH NEIL STREET SUITE 100 CHAMPAIGN, IL 61820 PHONE : 217.373.8900 FAX : 217.373.8923	
NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.	
DESIGNED BY: SMM DRAWN BY: MEW CHECKED BY: SLD APPROVED BY: SMM ACTIVITY: INITIALS	PROJECT NO: 102314 DATE: 05/20/06 DRAWING NUMBER S-12

Contract #98950




NORTHBOUND DIAPHRAGM ELEVATION AT NORTH ABUTMENT

(Looking North)



NORTHBOUND DIAPHRAGM ELEVATION AT SOUTH ABUTMENT


(Looking South)



PLAN-EXPANSION JOINT DETAIL

NOTES

1. Reinforcement bars in diaphragm are billed with superstructure on Dwg. S-15.
2. Concrete in diaphragm is included with Concrete Superstructure on Dwg. S-15.
3. For details of bars s(E) & s₁(E) see Dwg. S-15.
4. The s(E) and s₁(E) bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.



SECTION B-B

Dimensions at right angles to abutment, except as shown.
* Where bottom of corbel is above bearing seat, build level across full width of abutment cap.

MIN. BAR LAP

#6	2'-9"
----	-------

DIAPHRAGM ELEVATIONS, NORTHBOUND

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)


Clark Dietz ENGINEERS

DESIGN FIRM REGISTRATION No. 184-000450
1817 SOUTH NEIL STREET SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SEALING ANY PORTION OF THIS DRAWING.


DESIGNED BY: SMM	PROJECT NO.: 102314
DRAWN BY: MEW	DATE: 05/20/06
CHECKED BY: SLD	
APPROVED BY: SMM	
ACTIVITY: DETAILS	

Contract #98950



SOUTHBOUND DIAPHRAGM ELEVATION AT NORTH ABUTMENT
(Looking North)

(Diaphragm Elevation at South Abutment similar, mirror image)






SECTION C-C

Dimensions at right angles to abutment, except as shown.
* Where bottom of corbel is above bearing seat, build level across full width of abutment cap.

MIN. BAR LAP

#6	2'-9"
----	-------



NOTES

1. Reinforcement bars in diaphragm are billed with superstructure on Dwg. S-15.
2. Concrete in diaphragm is included with Concrete Superstructure on Dwg. S-15.
3. For details of bars s(E) & s1(E) see Dwg. S-15.
4. The s(E) and s1(E) bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.

DIAPHRAGM ELEVATIONS, SOUTHBOUND
INTERSTATE 57 OVER WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

Clark Dietz ENGINEERS
DESIGN FIRM REGISTRATION No. 184-000450
1817 SOUTH NEIL STREET SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

DESIGNED BY: SMM	PROJECT NO: 102314
DRAWN BY: MEW	DATE: 05/2006
CHECKED BY: SLD	
APPROVED BY: SMM	
ACTIVITY	INITIALS


**NORTHBOUND
BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
a1(E)	318	#5	17'-6"	
a2(E)	80	#5	25'-6"	
a3(E)	79	#5	23'-2"	
a4(E)	79	#5	20'-10"	
a5(E)	79	#5	18'-6"	
a6(E)	1	#5	49'-7"	
a7(E)	1	#5	31'-7"	
a8(E)	1	#5	30'-3"	
a9(E)	1	#5	16'-3"	
a10(E)	230	#5	22'-4"	
a11(E)	58	#5	20'-0"	
a12(E)	57	#5	17'-8"	
a13(E)	57	#5	15'-5"	
a14(E)	58	#5	13'-1"	
a15(E)	318	#6	4'-6"	
a16(E)	2	#5	40'-10"	
a17(E)	2	#5	31'-6"	
a18(E)	324	#5	43'-7"	
a19(E)	232	#5	42'-11"	
b(E)	534	#5	30'-9"	
b1(E)	86	#6	49'-0"	
b2(E)	504	#5	26'-8"	
d(E)	190	#5	3'-0"	J
d1(E)	374	#5	2'-5"	J
d2(E)	190	#4	3'-0"	J
d3(E)	380	#4	3'-9"	J
d4(E)	6	#5	2'-2"	L
d5(E)	6	#6	4'-5"	L
d6(E)	10	#6	8'-11"	L
d7(E)	190	#5	3'-8"	L
d8(E)	190	#4	3'-8"	L
e(E)	112	#4	18'-1"	
e1(E)	24	#4	13'-0"	
e2(E)	24	#8	27'-0"	
e3(E)	8	#8	13'-0"	
e4(E)	24	#5	25'-8"	
e5(E)	8	#5	13'-0"	
m(E)	2	#6	40'-3"	
m1(E)	10	#6	43'-7"	
m2(E)	3	#6	41'-0"	
m3(E)	12	#6	7'-8"	
m4(E)	36	#6	9'-7"	
m5(E)	4	#6	2'-11"	
m6(E)	16	#6	6'-10"	
m7(E)	2	#6	2'-0"	
m8(E)	5	#6	4'-8"	
m9(E)	2	#6	31'-0"	
m10(E)	3	#6	31'-9"	
s(E)	160	#5	5'-7"	J
s1(E)	138	#4	8'-11"	J
v(E)	66	#5	3'-10"	J
v5(E)	94	#5	4'-5"	J
v6(E)				
Reinforcement Bars, Epoxy Coated		Pound	92,500	
Concrete Superstructure		Cu. Yds.	414.4	
Bar Splicers		Each	722	
Reinforcement Bars, Epoxy Coated		Pound	100,520	
Concrete Superstructure		Cu. Yds.	435.0	
Bar Splicers		Each	740	


Bars indicated thus 1 x 3-#5 etc. indicates 1 line of bars with 3 lengths per line.

**SOUTHBOUND
BILL OF MATERIAL**


Bar	No.	Size	Length	Shape
a14(E)	318	#6	4'-6"	
a20(E)	324	#5	43'-7"	
a21(E)	232	#5	42'-11"	
a30(E)	324	#5	32'-1"	
a31(E)	232	#5	31'-5"	
b(E)	480	#5	30'-9"	
b1(E)	77	#6	49'-0"	
b2(E)	462	#5	26'-8"	
d(E)	380	#5	3'-0"	J
d1(E)	374	#5	2'-5"	J
d2(E)	380	#4	3'-0"	J
d3(E)	380	#4	3'-9"	J
d4(E)	6	#5	2'-2"	L
d5(E)	6	#6	4'-5"	L
d6(E)	10	#6	8'-11"	L
d7(F)	190	#5	3'-8"	L
d8(E)	190	#4	3'-8"	L
e(E)	112	#4	18'-1"	
e1(E)	24	#4	13'-0"	
e2(E)	24	#8	27'-0"	
e3(E)	8	#8	13'-0"	
e4(E)	24	#5	25'-8"	
e5(F)	8	#5	13'-0"	
m1(E)	10	#6	43'-7"	
m4(E)	40	#6	9'-7"	
m5(E)	4	#6	2'-11"	
m11(E)	2	#6	5'-6"	
m12(E)	4	#6	31'-5"	
m13(E)	6	#6	32'-2"	
m14(E)	18	#6	6'-9"	
m15(E)	2	#6	1'-0"	
s(E)	154	#5	5'-7"	J
s1(E)	132	#4	8'-11"	J
v(E)	30	#5	3'-10"	J
v5(E)	56	#5	4'-5"	J
v6(E)	66	#5	4'-9"	J
Reinforcement Bars, Epoxy Coated		Pound	92,500	
Concrete Superstructure		Cu. Yds.	414.4	
Bar Splicers		Each	722	




BARS d(E) & d2(E)




BAR d1(E)




BAR d3(E)




BAR d4(E)




BARS d7(E) & d8(E)




BAR d5(E)




BAR d6(E)




BAR s(E)




BAR s1(E)




BAR v(E), v5(E) or v6(E)



BAR CUTTING DIAGRAM




PLAN



SECTION E-E

Note: Cost of anchor bolts and conduit included with Concrete Superstructure.



1" ϕ ANCHOR BOLT
(ASTM F 1554 Grade 105)

SUPERSTRUCTURE BILL OF MATERIAL & LIGHT POLE BASE

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000450

Clark Dietz
 ENGINEERS

1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923

NOTES: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO: I02314
 DRAWN BY: MEW DATE: 05/28/86
 CHECKED BY: SLD
 APPROVED BY: SMM
 ACTIVITY INITIALS

DRAWING NUMBER
S-15

Contract #98950

NOTES

1. N.T.R. designates members subject to the supplemental requirements for notch toughness (Zone 2).
2. All structural steel for beams and splice plates shall be AASHTO M270 Grade 50.
3. Fasteners shall be high strength bolts conforming to AASHTO M-164 specification (ASTM A325). Bolts 7/8" ϕ , open holes 15/16" ϕ , unless noted otherwise.
4. Number of shear studs req'd = 9,144 Northbound
5. For Section F-F see Dwg. S-17.




TABLE OF DIMENSIONS FOR DIAPHRAGMS

DIAPHRAGM	LENGTH
D	7'-2"
D1	6'-10"
D2	6'-6 1/4"
D3	6'-2 3/8"
D4	5'-11 7/8"
D5	5'-9 7/8"
D6	5'-6 7/8"
D7	5'-2 1/4"
D8	6'-10 1/4"
D9	6'-6 1/2"
D10	6'-2 5/8"
D11	6'-0 1/2"
D12	5'-9 5/8"
D13	5'-5 7/8"
D14	5'-2"


NORTHBOUND TOP OF BEAM ELEVATIONS
(For fabrication only)

LOCATION	BEAM 1	BEAM 2	BEAM 3	BEAM 4	BEAM 5	BEAM 6	BEAM 7	BEAM 8	BEAM 9	BEAM 10	BEAM 11	BEAM 12
⊕ Brg., N. Abut.	471.451	471.600	471.750	471.899	472.048	472.198	472.321	472.431	472.519	472.194	472.045	471.896
* Splice #1	471.470	471.600	471.731	471.861	471.989	472.136	472.261	472.370	472.259	472.134	471.985	471.840
⊕ Pier	471.454	471.573	471.699	471.824	471.953	472.107	472.231	472.341	472.229	472.105	471.956	471.811
* Splice #2	471.438	471.546	471.667	471.788	471.917	472.077	472.201	472.311	472.199	472.075	471.927	471.781
⊕ Brg., S. Abut.	471.356	471.457	471.559	471.661	471.762	471.912	472.037	472.147	472.036	471.912	471.764	471.615

*Elevations are given at top of W30x211.

TABLE OF DIMENSIONS

SIZER	a	b	c
1 & 4	85'-8 9/16"	20'-1 1/16"	17'-10 9/16"
2 & 3	85'-8 3/8"	20'-0 1/8"	17'-10 3/8"
5-12	85'-9"	20'-1 1/2"	17'-11"



BEAM ELEVATION

FRAMING PLAN, NORTHBOUND

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION No. 184-000450
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.


DESIGNED BY: SMM PROJECT NO: 102314
DRAWN BY: MEW DATE: 05/28/06
CHECKED BY: SLD
APPROVED BY: SMM
ACTIVITY INITIALS

DRAWING NUMBER
S-16

Contract #98950

NOTES

1. N.T.R. designates members subject to the supplemental requirements for notch toughness (Zone 2).
2. All structural steel for beams and splice plates shall be AASHTO M270 Grade 50.
3. Fasteners shall be high strength bolts conforming to AASHTO M-164 specification (ASTM A325). Bolts $\frac{7}{8}$ " ϕ , open holes $\frac{15}{16}$ " ϕ , unless noted otherwise.
4. Number of shear studs req'd = 8,382 Southbound




SECTION F-F

SOUTHBOUND TOP OF BEAM ELEVATIONS
(For fabrication only)


LOCATION	BEAM 13	BEAM 14	BEAM 15	BEAM 16	BEAM 17	BEAM 18	BEAM 19	BEAM 20	BEAM 21	BEAM 22	BEAM 23
⊙ Brg., N. Abut.	471.896	472.042	472.188	472.311	472.421	472.335	472.219	472.047	471.767	471.487	471.207
* Splice #1	471.840	471.983	472.129	472.253	472.363	472.277	472.162	471.963	471.684	471.404	471.128
⊙ Pier	471.811	471.954	472.100	472.224	472.334	472.248	472.133	471.928	471.648	471.368	471.092
* Splice #2	471.782	471.925	472.071	472.195	472.305	472.219	472.104	471.892	471.612	471.333	471.057
⊙ Brg., S. Abut.	471.616	471.762	471.909	472.033	472.144	472.058	471.943	471.705	471.426	471.147	470.867

*Elevations are given at top of W30x211.

⊙ 1" ϕ Holes in beams 6 and 17 for bar splicers. See Dwg's S-13 and S-14. Cost of drilling holes is included in contract unit price for Furnishing and Erecting Structural Steel.



⊙ 1" ϕ Holes in beams for m3(E) and m4(E) bars. See Dwg S-13 & S-14. Cost of drilling holes is included in contract unit price for Furnishing and Erecting Structural Steel.



BEAM ELEVATION

"NTR" denotes plates to which notch toughness requirements are applicable.

FRAMING PLAN, SOUTHBOUND


INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)




DESIGN FIRM REGISTRATION
No. 184-000480
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

DESIGNED BY:	SMM	PROJECT NO:	102314
DRAWN BY:	MEW	DATE:	05/2006
CHECKED BY:	SLD		
APPROVED BY:	SMM		
ACTIVITY:	INITIALS		

Contract #98950




PLAN




ELEVATION AT PIER

FIXED BEARING
(23 Required)




SECTION G-G

PINTLE




ELEVATION
FIELD SPLICE DETAIL


Note:
All beams and splice material except fill plates shall be AASHTO M270 Gr. 50 and shall meet Notch Toughness Requirements (N.T.R.).
All bearings and pintles shall be AASHTO M270 Gr. 50.



FIXED BEARING AT NORTH & SOUTH ABUTMENT
(46 Required)




SECTION H-H



DETAIL 1
TYP.

DETAIL 2
TYP.

DETAIL 3
TYP.




ELEVATION

SECTION H-H

DETAIL 4

DIAPHRAGM CONNECTION



STIFFENED ANGLE DETAIL

INTERIOR GIRDER MOMENT TABLE

	0.4 Sp. 1 of 0.6 Sp. 2	Pier
I_s	(in ⁴) 9170	10300
I_c (n)	(in ⁴) 20947	
I_c (3n)	(in ⁴) 15337	
S_s	(in ³) 598	665
S_c (n)	(in ³) 806	
S_c (3n)	(in ³) 731	
Z	(in ³) 751	
M	(K/ft.) 0.903	1.369
$M\phi$	(K) 456	1225
$s\phi$	(K/ft.) 0.444	
$M_s\phi$	(K) 248	
M_L	(K) 701	460
M (Imp)	(K) 165	108
$s_3[M_L + M$ (Imp)]	(K) 1443	947
M_a	(K) 2791	2824
M_u	(K) 3668	3111
$f_s\phi$ non-comp	(k.s.i.) 9.2	22.1
$f_s\phi$ (comp)	(k.s.i.) 4.1	
$f_s s_3[M_L + M$ (Imp)]	(k.s.i.) 21.5	17.1
f_s (Overload)	(k.s.i.) 34.8	39.2
f_s (Total)	(k.s.i.) 46	51.0
VR	(K) 46	

INTERIOR GIRDER REACTION TABLE

	Abut.	Pier
$R\phi$	(K) 43.7	144.7
R_L	(K) 45.7	59.8
Imp.	(K) 10.9	14.2
R (Total)	(K) 100.3	218.7

I_s and S_s are the moment of Inertia and section modulus of the steel section used in computing f_s (Total & Overload).
 I_c (n) and S_c (n) are the moment of inertia and section modulus of the composite section used in computing stresses due to Live Load.
 I_c (3n) and S_c (3n) are the moment of inertia and section modulus of the composite section used in computing stresses due to superimposed dead loads. (see AASHTO 10.38)
 VR is the maximum Live Load + impact shear range within the composite portion of the span.
 Z is the plastic section modulus used to determine the fully plastic moments in the non-composite areas.
 M_a (Applied Moment) = $1.3[M_L + M_s\phi + s_3(M_L + M$ (Imp))].
The Plastic Moment capacity (M_u) is computed according to AASHTO 10.48.1 and 10.50.1.1.
 $M\phi$ Moment due to dead loads on non-composite section.
 $M_s\phi$ Moment due to dead loads on composite section.
 M_L Moment due to live load on non-composite or composite section.
 M (Imp) Moment due to live load impact on non-composite or composite section.
 f_s (Overload) is the sum of the stresses due to $M\phi + M_s\phi + s_3(M_L + M$ (Imp)).
 f_s (Total) (Non-compact section) is the sum of the stresses due to $1.3[M_L + M_s\phi + s_3(M_L + M$ (Imp))].

NOTES:

- Bolts for slotted holes in diaphragm connection shall be finger tightened prior to deck slab pour and then fully tightened after completion of Stage II pouring.
- ASTM F1554 Grade 105, ASTM A449, and AASHTO M314 Grade 105 anchor bolts may be substituted for the anchor bolts shown.

STRUCTURAL STEEL DETAILS, FIXED BEARING DETAILS & MOMENT TABLE
 INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION No. 184-000450
 1817 SOUTH NEIL STREET SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8823

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SIMM	PROJECT NO: 102314
DRAWN BY: MEW	DATE: 05/2006
CHECKED BY: SLD	
APPROVED BY: SIMM	
ACTIVITY	DETAILS

DRAWING NUMBER
S-18


(D: 49 Req'd at Northbound, D1 thru D14: 2 Req'd at Northbound, D15: 70 Req'd at Southbound)

Note:
Two hardened washers shall be required over all oversized holes for diaphragms.

- NOTES**
- Four steps monolithically with cap.
 - The Steel H-Piles shall be according to AASHTO M270 Grade 50.
 - The test pile shall be driven to 110 percent of the Nominal Required Bearing indicated in the pile data information.

**NORTHBOUND
NORTH ABUTMENT
BILL OF MATERIAL**

Bar No.	Size	Length	Shape
h(E)	#5	9'-8"	—
h ₁ (E)	#5	19'-10"	—
h ₂ (E)	#5	43'-7"	—
h ₃ (E)	#5	21'-2"	—
p(E)	#7	40'-11"	—
p ₁ (E)	#7	43'-7"	—
s ₂ (E)	#4	11'-5"	□
u(E)	#6	7'-2"	—
u ₁ (E)	#5	3'-0"	—
u ₄ (E)	#5	3'-8"	—
v ₁ (E)	#5	4'-4"	—
v ₂ (E)	#5	10'-4"	—
Concrete Structures	Cu. Yds.	33.5	
Reinforcement Bars, Epoxy Coated	Pound	4,250	
Structure Excavation	Cu. Yds.	170	
Furnishing Steel Piles, HP12x53	Foot	507	
Driving Piles	Foot	507	
Test Pile Steel HP12x53	Each	1	
Bar Splicers	Each	14	
Concrete Encasement	Cu. Yds.	4.9	




PILE DATA
 Type: HP12x53
 Nominal Req'd Bearing: 420k
 Allowable Resistance Available: 140k
 Est. Length: 39'
 No. Req'd: 13 + 1 Test Pile


ELEVATION
 (Looking North)
 85'-3 1/2"

ANCHOR BOLT LAYOUT


BEAMS	ANGLE	A
1	91°-04'-28"	1/8"
2	90°-18'-04"	0"
3	89°-31'-39"	0"
4	88°-45'-15"	1/8"
5 Thru 12	87°-58'-53"	1/8"




PLAN



SECTION THRU ABUTMENT



PILE ENCASEMENT DETAIL



FIELD CUTTING DIAGRAM

Order v₂(E) bars full length. Cut as shown and use remainder of bars in opposite side.

NORTH ABUTMENT, NORTHBOUND

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000450
Clark Dietz
 ENGINEERS
 1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM	PROJECT NO: 102314
DRAWN BY: MEW	DATE: 05/28/08
CHECKED BY: SLD	
APPROVED BY: SMM	
ACTIVITY: INITIALS	

DRAWING NUMBER: S-19



Contract #98950

NOTES





1. Pour steps monolithically with cap.
2. The Steel H-Piles shall be according to AASHTO M270 Grade 50.
3. The test pile shall be driven to 110 percent of the Nominal Required Bearing indicated in the pile data information.

**SOUTHBOUND
NORTH ABUTMENT
BILL OF MATERIAL**

Bar	No.	Size	Length	Shape	
h(E)	16	#5	9'-8"	—	
h ₂ (E)	2	#5	43'-7"	—	
h ₄ (E)	2	#5	18'-5"	—	
h ₅ (E)	2	#5	29'-11"	—	
h ₆ (E)	2	#5	4'-5"	—	
p ₁ (E)	12	#7	43'-7"	—	
p ₃ (E)	12	#7	32'-1"	—	
s ₂ (E)	70	#4	11'-5"	□	
u(E)	9	#6	7'-2"	—	
u ₁ (E)	35	#5	3'-0"	—	
u ₄ (E)	63	#5	3'-8"	—	
v ₁ (E)	143	#5	4'-4"	—	
v ₂ (E)	8	#5	10'-4"	—	
Concrete Structures				Cu. Yds.	31.8
Reinforcement Bars, Epoxy Coated				Pound	3,930
Structure Excavation				Cu. Yds.	159
Furnishing Steel Piles, HP12x53				Foot	429
Driving Piles				Foot	429
Test Pile Steel HP12x53				Each	1
Bar Splicers				Each	16
Concrete Encasement				Cu. Yds.	4.2



PILE DATA
 Type: HP12x53
 Nominal Req'd Bearing: 420k
 Allowable Resistance Available: 140k
 Est. Length: 39'
 No. Req'd: 11 + 1 Test Pile



NORTH ABUTMENT, SOUTHBOUND

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (XI-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000450

1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923

Clark Dietz
 ENGINEERS

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO.: 102314
 DRAWN BY: MEW DATE: 05/28/06
 CHECKED BY: SLW
 APPROVED BY: SMM
 ACTIVITY INITIALS


DRAWING NUMBER
S-20

NOTES

1. Pour steps monolithically with cap.
2. The Steel H-Piles shall be according to AASHTO M270 Grade 50.
3. The test pile shall be driven to 110 percent of the Nominal Required Bearing indicated in the pile data information.


NORTHBOUND SOUTH ABUTMENT BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h(E)	16	#5	9'-8"	—
h3(E)	2	#5	21'-2"	—
h7(E)	2	#5	11'-6"	—
h8(E)	2	#5	36'-10"	—
p1(E)	12	#7	43'-7"	—
p2(E)	12	#7	31'-8"	—
s2(E)	71	#4	11'-5"	□
u(E)	8	#6	7'-2"	—
u1(E)	22	#5	3'-0"	—
u4(E)	49	#5	3'-8"	—
v1(E)	137	#5	4'-4"	—
v2(E)	8	#5	10'-4"	—
Concrete Structures			Cu. Yds.	29.2
Reinforcement Bars, Epoxy Coated			Pound	3,740
Structure Excavation			Cu. Yds.	144
Furnishing Steel Piles, HP12x53			Foot	407
Driving Piles			Foot	407
Test Pile Steel HP12x53			Each	1
Bar Splicers			Each	14
Concrete Encasement			Cu. Yds.	4.2








ANCHOR BOLT LAYOUT

BEAMS	ANGLE	A
1	91°-04'-28"	1/16"
2	90°-18'-04"	0"
3	89°-31'-39"	0"
4	88°-45'-15"	1/16"
5 Thru 12	87°-58'-53"	1/8"



PILE DATA

Type: HP12x53
 Nominal Req'd Bearing: 420k
 Allowable Resistance Available: 140k
 Est. Length: 37'
 No. Req'd: 11 + 1 Test Pile



SOUTH ABUTMENT, NORTHBOUND

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

Clark Dietz ENGINEERS

DESIGNED BY: SHM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/28/06
 CHECKED BY: SLD
 APPROVED BY: SHM
 ACTIVITY INITIALS

1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923








DRAWING NUMBER
S-21

- NOTES**
- Four steps monolithically with cap.
 - The Steel H-Piles shall be according to AASHTO M270 Grade 50.
 - The test pile shall be driven to 110 percent of the Nominal Required Bearing indicated in the pile data information.

SOUTHBOUND SOUTH ABUTMENT BILL OF MATERIAL

Bar No.	Size	Length	Shape
h(E)	16	#5	9'-8"
h ₂ (E)	2	#5	43'-7"
h ₄ (E)	2	#5	18'-5"
h ₅ (E)	2	#5	29'-11"
h ₆ (E)	2	#5	4'-5"
p ₁ (E)	12	#7	43'-7"
p ₃ (E)	12	#7	32'-1"
s ₂ (E)	70	#4	11'-5"
u(E)	8	#6	7'-2"
u ₁ (E)	98	#5	3'-0"
v ₁ (E)	143	#5	4'-4"
v ₂ (E)	8	#5	10'-4"
Concrete Structures		Cu. Yds.	32.1
Reinforcement Bars, Epoxy Coated		Pound	3,880
Structure Excavation		Cu. Yds.	161
Furnishing Steel Piles, HP12x53		Foot	396
Driving Piles		Foot	396
Test Pile Steel HP12x53		Each	1
Bar Splicers		Each	16
Concrete Encasement		Cu. Yds.	4.2

PILE DATA
 Type: HP12x53
 Nominal Req'd Bearing: 420k
 Allowable Resistance Available: 140k
 Est. Length: 36'
 No. Req'd: 11 + 1 Test Pile



SOUTH ABUTMENT, SOUTHBOUND

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

Clark Dietz ENGINEERS

DESIGN FIRM REGISTRATION No. 184-000450
 1817 SOUTH NEIL STREET SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900 FAX : 217.373.8923





DESIGNED BY: SMM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/2006
 CHECKED BY: SLD
 APPROVED BY: SMM
 ACTIVITY: INITIALS

DRAWING NUMBER: S-22

Contract #98950


Notes

- See Dwg. S-26 for Fluted Rope Texture Details.
- Four steps monolithically with cap.
- Space reinforcement in cap to miss anchor bolts.
- The Steel H-Piles shall be according to AASHTO M270 Grade 50.
- The test pile shall be driven to 110 percent of the Nominal Required Bearing indicated in the pile data information.



MIN. BAR LAP

#5	2'-2"
----	-------



PILE DATA

Type: HP12x53
 Nominal Req'd Bearing: 420k
 Allowable Resistance Available: 140k
 Est. Length: 20'
 No. Req'd: 25 + 1 Test Pile

PIER, NORTHBOUND

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGNED BY: SHM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/28/06
 CHECKED BY: SLD
 APPROVED BY: SHM
 ACTIVITY: DETAILS

1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923




NOTES: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DRAWING NUMBER: **S-23**

For Section P-P and Bill of Material see Dwg. S-25

Notes

- See Dwg. S-26 for Fluted Rope Texture Details.
- Pour steps monolithically with cap.
- Space reinforcement in cap to miss anchor bolts.
- The Steel H-Piles shall be according to AASHTO M270 Grade 50.
- The test pile shall be driven to 110 percent of the Nominal Required Bearing indicated in the pile data information.



MIN. BAR LAP

#5	2'-2"
----	-------

PILE DATA
 Type: HP12x53
 Nominal Req'd Bearing: 420k
 Allowable Resistance Available: 140k
 Est. Length: 20'
 No. Req'd: 25 + 1 Test Pile

PIER, SOUTHBOUND

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000450
Clark Dietz
 ENGINEERS
 1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.


DESIGNED BY: SHM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/20/06
 CHECKED BY: SLD
 APPROVED BY: SHM
 ACTIVITY: DETAILS

DRAWING NUMBER
S-24

For Section R-R and Bill of Material see Dwg. S-25

BILL OF MATERIAL NORTHBOUND PIER

Bar	No.	Size	Length	Shape
h ₃ (E)	2	#5	21'-2"	
h ₁₀ (E)	2	#5	18'-1"	
h ₁₁ (E)	4	#5	36'-0"	
h ₁₂ (E)	6	#5	43'-3"	
h ₁₃ (E)	8	#5	29'-0"	
h ₁₄ (E)	8	#5	36'-4"	
h ₁₈ (E)	4	#9	29'-0"	
h ₁₉ (E)	4	#9	36'-4"	
n(E)	100	#8	6'-10"	C
p ₄ (E)	6	#9	37'-7"	
p ₅ (E)	12	#9	17'-4"	
p ₆ (E)	12	#7	11'-8"	
p ₇ (E)	6	#9	28'-11"	
p ₈ (E)	6	#9	44'-10"	
p ₉ (E)	6	#9	36'-2"	
s ₃ (E)	40	#5	6'-3"	
s ₄ (E)	56	#5	6'-11"	
s ₅ (E)	98	#5	10'-5"	
s ₆ (E)	60	#6	10'-11"	
s ₇ (E)	90	#6	10'-4"	
s ₈ (E)	50	#6	9'-10"	
s ₉ (E)	40	#6	9'-5"	
s ₁₀ (E)	40	#6	8'-11"	
s ₁₁ (E)	70	#6	8'-7"	
s ₁₂ (E)	89	#5	6'-9"	
s ₁₃ (E)	79	#8	14'-5"	
s ₁₄ (E)	120	#4	3'-9"	
s ₁₅ (E)	120	#4	3'-9"	
s ₁₆ (E)	55	#4	3'-2"	
s ₁₇ (E)	55	#4	3'-2"	
t(E)	88	#9	13'-2"	
t ₁ (E)	69	#5	10'-0"	
u ₂ (E)	6	#6	7'-7"	
u ₃ (E)	85	#5	3'-9"	
v ₃ (E)	100	#7	13'-1"	
w(E)	20	#5	30'-4"	
w ₁ (E)	20	#5	37'-7"	
Concrete Structures	Cu. Yds.	131.3		
Structure Excavation	Cu. Yds.	160		
Reinforcement Bars, Epoxy Coated	Pound	28,270		
Furnishing Steel Piles, HP12x53	Foot	500		
Driving Piles	Foot	500		
Test Pile Steel HP12x53	Each	1		
Bar Splicers	Each	50		




BAR n(E)


BARS s₃(E), s₄(E), s₁₂(E), s₁₃(E), u₂(E), u₃(E) or t(E)

A & B DIMENSIONS


Bar	A	B
s ₃ (E)	1'-7"	2'-4"
s ₄ (E)	1'-7"	2'-8"
s ₁₂ (E)	2'-5"	2'-2"
s ₁₃ (E)	2'-5"	6'-0"
t(E)	10'-0"	1'-7"
u ₂ (E)	2'-5"	2'-7"
u ₃ (E)	2'-5"	9"



BAR p₆(E)




BARS p₄(E), p₈(E) or p₁₀(E)



BAR s₅(E), s₆(E), s₇(E), s₈(E), s₉(E), s₁₀(E) or s₁₁(E)

A, B & C DIMENSIONS


Bar	A	B	C
s ₅ (E)	1'-7"	3'-2"	5/2"
s ₆ (E)	1'-8"	3'-1 1/2"	8"
s ₇ (E)	1'-8"	2'-10"	8"
s ₈ (E)	1'-8"	2'-7"	8"
s ₉ (E)	1'-8"	2'-4 1/2"	8"
s ₁₀ (E)	1'-8"	2'-1 1/2"	8"
s ₁₁ (E)	1'-8"	1'-11 1/2"	8"




**ANCHOR BOLT LAYOUT
NORTH PIER**

BEAMS	ANGLE	A
1	91°-04'-28"	3/16"
2	90°-18'-04"	1/6"
3	89°-31'-39"	1/6"
4	88°-45'-15"	1/4"
5 Thru 12	87°-58'-53"	3/8"

*Note:
Space cross ties with closed stirrup ties.




**NORTHBOUND PIER
COLUMN ELEVATION**




SECTION P-P



BAR s₁₄(E) or s₁₆(E)




BAR s₁₅(E) or s₁₇(E)




**SECTION S-S
PILE STUD DETAIL**

BILL OF MATERIAL SOUTHBOUND PIER


Bar	No.	Size	Length	Shape
h ₄ (E)	2	#5	18'-5"	
h ₅ (E)	2	#5	29'-11"	
h ₆ (E)	2	#5	4'-5"	
h ₁₂ (E)	6	#5	43'-4"	
h ₁₅ (E)	4	#5	31'-11"	
h ₁₆ (E)	8	#5	26'-8"	
h ₁₇ (E)	8	#5	34'-8"	
h ₂₀ (E)	4	#9	26'-8"	
h ₂₁ (E)	4	#9	34'-8"	
n(E)	100	#8	6'-10"	C
p ₅ (E)	12	#9	17'-4"	
p ₆ (E)	12	#7	11'-8"	
p ₈ (E)	6	#9	44'-10"	
p ₉ (E)	6	#9	36'-2"	
p ₁₀ (E)	6	#9	33'-6"	
p ₁₁ (E)	6	#9	24'-10"	
s ₃ (E)	40	#5	6'-3"	
s ₄ (E)	56	#5	6'-11"	
s ₅ (E)	94	#5	10'-5"	
s ₆ (E)	60	#6	10'-11"	
s ₇ (E)	100	#6	10'-4"	
s ₈ (E)	60	#6	9'-10"	
s ₉ (E)	30	#6	9'-5"	
s ₁₀ (E)	30	#6	8'-11"	
s ₁₁ (E)	70	#6	8'-7"	
s ₁₂ (E)	85	#5	6'-9"	
s ₁₃ (E)	75	#8	14'-5"	
s ₁₄ (E)	125	#4	3'-9"	
s ₁₅ (E)	125	#4	3'-9"	
s ₁₆ (E)	50	#4	3'-2"	
s ₁₇ (E)	50	#4	3'-2"	
t(E)	89	#9	13'-2"	
t ₁ (E)	66	#5	10'-0"	
u ₂ (E)	6	#6	7'-7"	
u ₃ (E)	98	#5	3'-9"	
v ₄ (E)	100	#7	12'-10"	
w ₂ (E)	20	#5	28'-5"	
w ₃ (E)	20	#5	36'-5"	
Concrete Structures	Cu. Yd.	130.6		
Structure Excavation	Cu. Yd.	153		
Reinforcement Bars, Epoxy Coated	Pound	27,810		
Furnishing Steel Piles, HP12x53	Foot	500		
Driving Piles	Foot	500		
Test Pile Steel HP12x53	Each	1		
Bar Splicers	Each	52		



**SOUTHBOUND PIER
COLUMN ELEVATION**



SECTION R-R



**ANCHOR BOLT LAYOUT
SOUTH PIER**

**PIER DETAILS,
NORTHBOUND & SOUTHBOUND**

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)


**Clark Dietz
ENGINEERS**

DESIGN FIRM REGISTRATION
No. 184-000450
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923


REVISIONS	NAME	DATE

DESIGNED BY:	SMM	PROJECT NO.:	102314
DRAWN BY:	MEW	DATE:	05/2006
CHECKED BY:	SLD		
APPROVED BY:	SMM		
ACTIVITY:	DETAILS		


DRAWING NUMBER
S-25



ELEVATION




END VIEW




SECTION T-T
(THRU CAP BEAM AND CRASHWALL)

NOTE: Some reinforcement omitted for clarity.


PIER SKETCH




PLAN




PLAN



ELEVATION
NORTHBOUND PIER
(Looking North)
SOUTHBOUND PIER
(Looking South)



ELEVATION
BOTTOM BASE PLATE
Note: Grout shall be non-shrink.



ELEVATION
TOP BASE PLATE

NOTES:

1. Temporary Support System shall be installed prior to setting beams on new pier cap.
2. After removal of Temporary Support System patch concrete surface of base wall and cap to match surrounding areas.

BILL OF MATERIAL		
ITEM	UNIT	TOTAL
Temporary Support System	L.S.	1

PIER FORM LINER DETAILS AND TEMPORARY SUPPORT SYSTEM

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
No. 184-000450
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

Clark Dietz
ENGINEERS

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

PROJECT NO: 102314
DATE: 05/2006

DRAWING NUMBER
S-26

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.
 Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length.
 All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars.
 Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.
 Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

- ① Minimum Capacity (Tension in kips) = $1.25 \times f_y \times A_t$
- ② Minimum *Pull-out Strength (Tension in kips) = $1.25 \times f_{s,allow} \times A_t$

Where f_y = Yield strength of lapped reinforcement bars in ksi.
 $f_{s,allow}$ = Allowable tensile stress in lapped reinforcement bars in ksi (Service Load)
 A_t = Tensile stress area of lapped reinforcement bars.
 * = 28 day concrete

BAR SPLICER ASSEMBLIES			
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Strength Requirements	
		Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension
#4	1'-8"	14.7	5.9
#5	2'-0"	23.0	9.2
#6	2'-7"	33.1	13.3
#7	3'-5"	45.1	18.0
#8	4'-6"	58.9	23.6
#9	5'-9"	75.0	30.0
#10	7'-3"	95.0	38.0
#11	9'-0"	117.4	46.8

Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."


The diameter of this part is equal or larger than the diameter of bar spliced.

ROLLED THREAD DOWEL BAR



** ONE PIECE


Wire Connector



WELDED SECTIONS


BAR SPLICER ASSEMBLY ALTERNATIVES

** Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.




INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt.
 "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.
 (E) : Indicates epoxy coating.




FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

Bar Splicer for #5 bar
Min. Capacity = 23.0 kips - tension
Min. Pull-out Strength = 9.2 kips - tension
No. Required = 318



FOR PILE BENT ABUTMENTS

Bar Splicer for #5 bar
Min. Capacity = 23.0 kips - tension
Min. Pull-out Strength = 9.2 kips - tension
No. Required =



STANDARD

Bar Size	No. Assemblies Required	Location
7	12	N. Abut. - N.B.
5	2	N. Abut. - N.B.
7	12	N. Abut. - S.B.
5	4	N. Abut. - S.B.
7	12	S. Abut. - N.B.
5	2	S. Abut. - N.B.
7	12	S. Abut. - S.B.
5	4	S. Abut. - S.B.
5	556	Deck - N.B.
5	556	Deck - S.B.
5	34	Pier - N.B.
5	36	Pier - S.B.
9	16	Pier - N.B.
9	16	Pier - S.B.
6	8	Dia. N. Abut. - N.B.
6	8	Dia. N. Abut. - S.B.
6	8	Dia. S. Abut. - N.B.
6	8	Dia. S. Abut. - S.B.

BAR SPLICER ASSEMBLY DETAILS

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION No. 184-000450
Clark Dietz ENGINEERS
 1817 SOUTH NEIL STREET SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SEALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SHM PROJECT NO: 182314
 DRAWN BY: MEW DATE: 05/2006
 CHECKED BY: SLD
 APPROVED BY: SHM
 ACTIVITY INITIALS

DRAWING NUMBER


S-27

Contract #98950

NOTES

- Detail I - With Bar Splicer or Couplers:
Connect one (1) 1"x7"x10" steel \bar{P} to the top layer of couplers with 2-5/8" ϕ bolts screwed to coupler at approximate \bar{C} of each barrier panel.
- Detail II - With Extended Reinforcement Bars:
Connect one (1) 1"x7"x10" steel \bar{P} to the concrete slab with 2-5/8" ϕ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate \bar{C} of each barrier panel.
- Cost of anchorage is included with Temporary Concrete Barrier.

When "A" is 3'-6" or less, the temporary concrete barrier shall be anchored to the new slab according to Detail I or Detail II. No anchorage is required when "A" is greater than 3'-6".




See Detail I or Detail II.

Drill 1/4" ϕ Holes in existing slab for 1" ϕ x 11" dowel bars. Traffic side only. Cost included with Temporary Concrete Barrier.


NEW SLAB EXISTING SLAB

SECTIONS THRU SLAB




DETAIL I

The 1"x7"x10" Plate shall not be removed until Stage II Construction forms and reinforcement bars are in place.



DETAIL II

The 1"x7"x10" Plate shall not be removed until Stage II Construction forms and all reinforcement bars are in place and the concrete is ready to be placed.



1"x7"x10"

* Required only with Detail II

TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
No. 184-000450

Clark Dietz
ENGINEERS

1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESTINED BY: SHM PROJECT NO: 102314
DRAWN BY: MEW DATE: 05/28/06
CHECKED BY: SLD
APPROVED BY: SHM
ACTIVITY: INITIALS

DRAWING NUMBER
S-28

Contract #98950

ILLINOIS DEPARTMENT OF TRANSPORTATION
District Nine Materials

Bridge Foundation
Boring Log
Sheet 1 of 2

FAI 57 Over Old Route 13
Route: FAI 57 Structure Number: 100-0004, 100-0005 Date: 5/30/2000
Section XI-6HB-2 Bored By: Bryan Keller
County: Williamson Location: In Marion Checked By: R Moberly

Boring No	D E P T H	B L O W S	Qu tsf	W%	Surf Wat Elev: Ground Water Elevation when Drilling	D E P T H	B L O W S	Qu tsf	W%
Station 1530+86 Offset 7' Rt. CL Median Ground Surface 469.7 Ft					At: Hrs: 424.7				
Stiff, moist, brown to grey, Silty Clay A7-6					442.7	3	2.5B	16	
	1					6			
	2	1.9B	23			2			
	3					2	1.9B	20	
	5.0	2				30.0	2		
	1	1.4S	20			3	1.5B	19	
	2					4			
					437.7				
	2					1			
	2	1.1S	21			3	0.7S	26	
	4					3			
					435.2				
Stiff, moist to very moist, grey mottled brown, Clay A7-6	10.0	2				35.0	2		
		2	1.4S	22		2	1.8B	17	
		3				2			
		1				2			
		3	1.4S	22		2	1.7B	20	
		3				3			
					430.7				
Medium, very moist, grey, Silty Clay to Clay A7-6	15.0	1				40.0	100/2"		
		3	0.7B	22					
		2							
		1							
		2	0.8B	25					
		3							
					450.2				
Stiff, moist, grey mottled brown, Silty Clay to Silty Clay Loam A-6	20.0	1				45.0	100/1"		
		2	1.1B	22					
		3							
		2							
		5	1.2S	20					
		6							
					445.2				
	25.0	2				50.0	100/1"		

N-Std Pentr Test: 2" OD Sampler,

ILLINOIS DEPARTMENT OF TRANSPORTATION
District Nine Materials

Bridge Foundation
Boring Log
Sheet 1 of 2

FAI 57 Over Old Route 13
Route: FAI 57 Structure Number: 100-0004, 100-0005 Date: 5/31/2000
Section XI-6HB-2 Bored By: Bryan Keller
County: Williamson Location: In Marion Checked By: R Moberly

Boring No	D E P T H	B L O W S	Qu tsf	W%	Surf Wat Elev: Ground Water Elevation when Drilling	D E P T H	B L O W S	Qu tsf	W%
Station 1528+82 Offset 20' Lt. CL Median Ground Surface 471.0 Ft					At: Hrs: 429				
Bituminous Pavement over Concrete					469.5				
					444.0				
Very stiff, moist, grey mottled brown, Silty Clay A7-6		1				3	1.9S	17	
		2	2.4B	23		5			
		2				2			
					441.5				
Soft to medium, very moist, grey mottled brown, Clay A7-6	5.0	1				30.0	2		
		1	0.5B	26		4	1.2S	23	
		2				4			
					484.0				
Stiff, moist, grey mottled brown, Clay A7-6		1				30.0	2		
		1	1.5S	21		2	1.8B	17	
		2				3			
					439.0				
Stiff, moist, brown, Silty Clay A7-6		1				35.0	1		
		2	1.1B	22		2	1.9B	19	
		1				2			
					459.0				
Medium, very moist, brown mottled grey, Clay A7-6		1				434.0			
		2	0.6B	24		1	0.5B	21	
		2				1			
					431.5				
Stiff, moist, brown, Clay to Silty Clay A7-6	15.0	2				40.0	1		
		3	0.7B	26		5	1.7B	26	
		3				12			
					429.0				
Stiff, moist, brown, Silty Clay A-6		1				428.5	100/2"		
		2	1.2B	25					
		4							
					454.0				
Bottom of hole = 42.1 feet.	20.0	2				45.0			
		4	1.5B	22					
		4							
					454.0				
Stiff, moist, brown, Silty Clay A-6		1							
		3	1.4B	19					
		2							
					445.2				
	25.0	2				50.0	100/1"		

N-Std Pentr Test: 2" OD Sampler,

BORING LOGS

INTERSTATE 57 OVER
WEST MAIN ST. (OLD IL RT. 13)
F.A.I. RT. 57 SEC. (X1-6)HBK-2
WILLIAMSON COUNTY
STATION 1529+96.11
STRUCTURE NO. 100-0084 (N.B.)
STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
No. 184-000450
1817 SOUTH NEIL STREET
SUITE 100
CHAMPAIGN, IL 61820
PHONE : 217.373.8900
FAX : 217.373.8923

Clark Dietz
ENGINEERS

REVISIONS		DATE	DRAWING NUMBER
NAME			
			S-29

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY:	SMM	PROJECT NO:	102214
DRAWN BY:	MEW	DATE:	05/2006
CHECKED BY:	SLD		
APPROVED BY:	SMM		
ACTIVITY	INITIALS		

Contract #98950

100-0004
100-0005

Project Bridge FAI 04 Over SBI 13
 Route FAI 04 Station 1529+95.80 Date Aug. 58
 Section XI-6HB-2 Boring made by Francis Piefer
 County Williamson

Project Bridge FAI 04 Over SBI 13
 Route FAI 04 Station 1529+95.80 Date Aug. 58
 Section XI-6HB-2 Boring made by Francis Piefer
 County Williamson

Project Bridge FAI 04 Over SBI 13
 Route FAI 04 Station 1529+95.80 Date Aug. 58
 Section XI-6HB-2 Boring made by Gordon H. Denon
 County Williamson

Boring No. 1	Elevation	Blows per Foot	Qu.	Description	Elevation	Blows per Foot	Qu.
	432.5			Hard mottled clay.	432.5		
	432.0				432.0		
	431.0	26	4.65		431.0		
	430.5				430.5		
Surface of Ground.	451.9						
	449.5	5	2.44				
Very stiff mottled clay.	448.5						
	447.0						
	446.0	5	2.78				
	444.5						
	443.5	5	2.70	Brown sandstone			
	443.0						
Very stiff yellow clay.	442.0						
	441.0	5	2.62				
	440.5				418.5		
	439.5						
Stiff mottled sandy clay.	438.5	4	1.06				
	437.0						
	436.0	5	1.56				
	435.5						
Stiff mottled clay.	434.5						
	433.5	6	1.88				
	432.5						

Boring No. 2	Elevation	Blows per Foot	Qu.	Description	Elevation	Blows per Foot	Qu.
	432.5				432.5		
	432.0				432.0		
	431.0				431.0		
Surface of Ground.	451.9						
	449.5	4	1.96				
Stiff mottled clay.	448.5						
	448.0						
	447.0						
	446.0	5	2.36				
	444.5				423.5		
	443.5	5	2.20	Brown sandstone.			
	442.0						
	441.0	4	2.08				
	439.5						
	438.5	6	3.19				
Very stiff mottled clay.	437.0						
	436.0	7	3.35				
	434.5						
	433.5	16	2.30				
	432.5						

Boring No. 3	Elevation	Blows per Foot	Qu.	Description	Elevation	Blows per Foot	Qu.
	432.5				432.5		
	432.0				432.0		
	431.0				431.0		
Surface of Ground.	453.0						
	448.0						
Stiff mottled silty clay.	447.0	4	1.30				
	445.5						
	444.5	4	1.06				
	443.5						
Very stiff mottled silty clay.	443.0						
	442.0	6	2.36				
	441.5						
Stiff yellow sandy clay.	440.5						
	439.5	5	1.18				
	439.0						
	438.0						
Medium yellow sandy clay.	437.0	3	0.90				
	435.5						
	434.5	6	0.61				
	433.5						
Hard brown mottled till.	433.0						
	432.0	24	5.31				

BORING LOGS

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HKB-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000460
Clark Dietz
 ENGINEERS
 1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8800
 FAX : 217.373.8823

REVISIONS	
NAME	DATE

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/2006
 CHECKED BY: SLD
 APPROVED BY: SMM
 ACTIVITY INITIALS

DRAWING NUMBER
S-30

Contract #98950

Project: Bridge FAI 04 Over SBI 13
 Route: FAI 04 Station 1529+95.80
 Section: XI-6HB-2 Boring made by Gordon R. Benson
 County: Williamson
 Sheet 4 of 9 Sheets Date: Aug. 58

Boring No. 4	Elevation	Blows per Foot	Qu.	Soil Description
Surface of Ground	452.7			
Very stiff mottled silty clay.	450.0	4	2.45	Brown sandstone.
	449.0			
	447.5	5	2.74	
	446.5			
	445.0	7	2.36	
	444.0			
	443.5			
Medium yellow mottled silty clay, locally sandy.	442.5	4	0.85	
	441.5			
Stiff yellow mottled silty clay.	440.5	6	1.88	
	440.0			
	439.0	11	2.90	
	438.0			
	437.5			
Very stiff mottled clay.	436.5	15	2.75	
	435.0			
	434.0			
	433.0			

Project: Bridge FAI 04 Over SBI 13
 Route: FAI 04 Station 1529+95.80
 Section: XI-6HB-2 Boring made by Gordon R. Benson
 County: Williamson
 Sheet 5 of 9 Sheets Date: Aug. 58

Boring No. 5	Elevation	Blows per Foot	Qu.	Soil Description
Surface of Ground	455.2			
Medium mottled silty clay.	435.0			Brown sandstone.
	434.5		2.86	
Very stiff mottled silty clay.	434.0			
	432.5			
	432.0			
Medium mottled dry silty clay.	450.0	12	0.82	
	449.0			
	448.0			
	447.5	11	1.10	
	446.5			
Stiff mottled silty clay.	445.0	11	1.22	
	444.0			
	443.0			
	442.5	13	0.86	
	441.5			
Medium brown sandy clay.	440.0	4	0.65	
	439.0			
	438.5			
Medium mottled silty clay.	437.5	1	0.57	
	436.5			

Project: Bridge FAI 04 Over SBI 13
 Route: FAI 04 Station 1529+95.80
 Section: XI-6HB-2 Boring made by Francis Pfister
 County: Williamson
 Sheet 6 of 9 Sheets Date: Aug. 58

Boring No. 6	Elevation	Blows per Foot	Qu.	Soil Description
Surface of Ground	455.5			
Stiff brown sandy clay.	433.0	3	1.15	Brown sandstone.
	432.0			
	431.5			
Medium mottled clay.	453.0	6	0.90	
	452.0			
	451.0			
Stiff mottled silty clay.	450.5	8	1.15	
	449.5			
	449.0			
	448.0	9	2.78	
Very stiff mottled silty clay.	447.0			
	445.5	11	3.02	
	444.5			
	443.5			
Very stiff mottled stoney clay.	443.0	7	2.64	
	442.0			
	441.0			
	440.5	4	1.15	
	439.5			
Stiff brown sandy clay.	438.0	4	1.22	
	437.0			
	435.5			
	434.5	4	1.30	

BORING LOGS

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (XI-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000450
 1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923



REVISIONS	
NAME	DATE

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/2006
 CHECKED BY: SLD
 APPROVED BY: SMM
 ACTIVITY INITIALS

DRAWING NUMBER
S-31

Contract #98950

Project: Bridge FAI 04 Over SBI 13
 Route: FAI 04 Station 1529+95.80
 Section: X1-6HB-2 Boring made by Francis Piefer
 County: Williamson
 Sheet 7 of 9 Sheets
 Date: August 1958

Boring No. 7	Elevation	Blows per Foot	Qu.	Description
Boring located at Station 1529+56, 14 Ft Rt Centerline of West Lane.				
Surface of Ground	456.8			
	454.5	6	0.74	Very stiff brown sandy stoney clay.
Medium mottled very silty clay.	453.5	11	0.90	
	452.0			
	451.0			
	450.0			
	449.5	10	1.64	
Stiff brown silty sandy clay.	448.5			
	447.0	10	2.36	
	446.0			
	445.5			
Stiff brown very sandy stoney clay.	444.5	8	1.38	
	443.5			
	443.0			
	442.0	4	0.57	
	441.0			
Medium brown very sandy stoney clay.	439.5	4	0.82	
	438.5			
	437.5			

Project: Bridge FAI 04 Over SBI 13
 Route: FAI 04 Station 1529+95.80
 Section: X1-6HB-2 Boring made by Francis Piefer
 County: Williamson
 Sheet 8 of 9 Sheets
 Date: Aug. 58

Boring No. 8	Elevation	Blows per Foot	Qu.	Description
Boring located at Station 1529+14, 18 Ft Rt Centerline of West Lane.				
Surface of Ground	457.6			
	455.0	14	2.78	Very stiff brown sandy silty clay.
Very stiff brown mottled clay.	454.0			
	452.5	22	3.74	
	451.5			
	450.5			
	450.0	16	2.70	
Very stiff mottled stoney clay.	449.0			
	447.5	14	2.36	
	446.5			
	445.5			
Stiff mottled sandy clay.	445.0	6	1.56	
	444.0			
	443.5			
	442.5	4	0.90	
	441.5			
Medium mottled very sandy clay.	440.0	4	0.98	
	439.0			
	438.0			

Project: Bridge FAI 04 Over SBI 13
 Route: FAI 04 Station 1529+95.80
 Section: X1-6HB-2 Boring made by Francis Piefer
 County: Williamson
 Sheet 9 of 9 Sheets
 Date: Aug. 58

Boring No. 9	Elevation	Blows per Foot	Qu.	Description
Boring located at Station 1529+14 on Centerline of West Lane.				
Surface of Ground	457.1			
	454.5	6	1.38	Very stiff mottled sandy stoney clay.
Stiff mottled silty clay.	453.5			
	452.0	8	1.56	
	451.0			
	450.0			
	449.5	8	2.12	
Very stiff mottled silty clay.	448.5			
	447.0	10	3.42	
	446.0			
	445.5			
	444.5	8	1.96	
	443.5			
Stiff mottled silty sandy clay.	442.0	5	1.72	
	441.0			
	439.5	4	1.38	
	438.5			
	437.5			

BORING LOGS

INTERSTATE 57 OVER
 WEST MAIN ST. (OLD IL RT. 13)
 F.A.I. RT. 57 SEC. (X1-6)HBK-2
 WILLIAMSON COUNTY
 STATION 1529+96.11
 STRUCTURE NO. 100-0084 (N.B.)
 STRUCTURE NO. 100-0085 (S.B.)

DESIGN FIRM REGISTRATION
 No. 184-000450
Clark Dietz
 ENGINEERS
 1817 SOUTH NEIL STREET
 SUITE 100
 CHAMPAIGN, IL 61820
 PHONE : 217.373.8900
 FAX : 217.373.8923

REVISIONS	
NAME	DATE

NOTE: DIMENSIONAL DATA IS NOT TO BE OBTAINED BY SCALING ANY PORTION OF THIS DRAWING.

DESIGNED BY: SMM PROJECT NO: 102314
 DRAWN BY: MEW DATE: 05/22/05
 CHECKED BY: SLD
 APPROVED BY: SMM
 ACTIVITY: INITIALS

DRAWING NUMBER
S-32