

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...	...	...	24	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

- FAP 331 & FAP 776
- 10IRS-5; (1142)RS-3
- JACKSON & HAMILTON

## SUMMARY OF QUANTITIES

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAP 331 (IL 149)		FAP 776 (IL 142)	
				URBAN	100% STATE	URBAN	100% STATE
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	617	0		617	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1459	1459	▲	0	
40600300	AGGREGATE (PRIME COAT)	TON	35	25		10	
40600990	TEMPORARY RAMP	SO YD	247	38		209	
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	576	0		576	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N105	TON	1362	1362	▲	0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	23,063	16,208		6855	
44201385	CLASS C PATCHES, TYPE I, 13 INCH	SO YD	13	13		0	
44201389	CLASS C PATCHES, TYPE II, 13 INCH	SO YD	150	136		14	
44201394	CLASS C PATCHES, TYPE III, 13 INCH	SO YD	129	108		21	
44201396	CLASS C PATCHES, TY IV, 13 INCH	SO YD	634	234		400	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1		1	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5		0.5	
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	828	660		168	
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SO FT	541.6	400		141.6	
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	5700	4805	▲	895	
70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	2213	1833		380	
70300260	TEMPORARY PAVEMENT MARKING, LINE 12"	FOOT	170	150		20	
70300280	TEMPORARY PAVEMENT MARKING, LINE 24"	FOOT	287	140		147	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3901	3551	▲	350	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	541.6	400		141.6	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5700	4805	▲	895	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2213	1833		380	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170	150		20	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	287	140		147	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	155	108		47	

\*SPECIALTY ITEMS

▲ Rev. 2-20-07