

CODED PAY ITEM NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY	0004 ROADWAY	0044 BUILDING REMOVAL
20100500	TREE REMOVAL, ACRES	ACRE	47.2	47.2	
20200100	EARTH EXCAVATION	CU YD	1,234,969	1,234,969	
20800150	TRENCH BACKFILL	CU YD	798	798	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	142,616	142,616	
25000200	SEEDING, CLASS 2	ACRE	21.8	21.8	
25000300	SEEDING, CLASS 3	ACRE	27.4	27.4	
25000310	SEEDING, CLASS 4	ACRE	21.4	21.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6,642	6,642	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6,642	6,642	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6,642	6,642	
25100900	TURF REINFORCEMENT MAT	SQ YD	29,686	29,686	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	2,392	2,392	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	15,680	15,680	
28000400	PERIMETER EROSION BARRIER	FDOT	4,611	4,611	
28000510	INLET FILTERS	EACH	22	22	
28001000	AGGREGATE (EROSION CONTROL)	TON	1,711	1,711	
28100101	STONE RIPRAP, CLASS A1	SQ YD	352	352	
28100107	STONE RIPRAP, CLASS A4	SQ YD	352	352	
28200200	FILTER FABRIC	SQ YD	5321	5,321	
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	161	161	
31101860	SUBBASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	5,796	5,796	
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	62	62	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3	3	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	7	7	
44000100	PAVEMENT REMOVAL	SQ YD	7,306	7,306	
44004250	PAVED SHOULDER REMOVAL	SQ YD	5	5	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	320	320	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	5	5	
542A0253	PIPE CULVERTS, CLASS A, TYPE 1 48"	FOOT	110	110	
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	188	188	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	4	4	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	3	3	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1	

• SPECIALTY ITEM

CODED PAY ITEM NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY	0004 ROADWAY	0044 BUILDING REMOVAL
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	103	103	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	94	94	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	197	197	
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	213	213	
550A1300	STORM SEWERS, CLASS A, TYPE 5 30"	FOOT	356	356	
55100200	STORM SEWER REMOVAL 6"	FOOT	24	24	
55100300	STORM SEWER REMOVAL 8"	FOOT	41	41	
55100500	STORM SEWER REMOVAL 12"	FOOT	54	54	
55100600	STORM SEWER REMOVAL 14"	FOOT	43	43	
55100700	STORM SEWER REMOVAL 15"	FOOT	29	29	
55100900	STORM SEWER REMOVAL 18"	FOOT	6	6	
55101000	STORM SEWER REMOVAL 20"	FOOT	41	41	
55101200	STORM SEWER REMOVAL 24"	FOOT	29	29	
55101800	STORM SEWER REMOVAL 42"	FOOT	36	36	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3	
60109600	BACKSLOPE DRAINS, TYPE 1 4"	FOOT	300	300	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1	
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60500040	REMOVING MANHOLES	EACH	2	2	
60500060	REMOVING INLETS	EACH	1	1	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
66400305	CHAIN LINK FENCE, 6'	FOOT	3,954	3,954	
66408200	CHAIN LINK GATES, 6' X 24' DOUBLE	EACH	1	1	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	32	32	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24	
67100100	MOBILIZATION	L SUM	1	1	
67201100	SEALING ABANDONED MONITORING WELLS	EACH	6	6	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
• 72000100	SIGN PANEL - TYPE 1	SQ FT	36	36	
• 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4	
• 72900100	METAL POST - TYPE A	FOOT	84	84	
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1		1
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1		1
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1		1
Z0007604	BUILDING REMOVAL NO. 4	L SUM	1		1

FILE NAME = ...\\0160F78-sht-summary-01.dgn

USER NAME = ctb

DESIGNED - DTE

REVISED -

DRAWN - DTE

REVISED -

CHECKED - GAB

REVISED -

DATE - 1/20/2012

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S.

SHEET NO. 1 OF 2 SHEETS

STA.

TO STA.

F.A. RTE.

SECTION

COUNTY

TOTAL SHEETS

NO.

18A-1

McHENRY

115 3

CONTRACT NO. 60F78

FED. ROAD DIST. NO.

ILLINOIS FED. AID PROJECT