

CODED PAY ITEM NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY	0004 ROADWAY	0044 BUILDING REMOVAL
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,516	1,516	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0019598	DUST CONTROL, SPECIAL	GALLON	414,525	414,525	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,260	3,260	
Z0076600	TRAINEES	— HOUR			
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1	1	
X0327218	DETENTION BASIN OUTLET STRUCTURE	EACH	1	1	
X0327219	POLYMER TABLETS	UNIT	42	42	
X0327220	TRIPAM POLYMER	POUND	6,500	6,500	
X0426200	DEWATERING	L SUM	1	1	
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	368	368	
X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	3.2	3.2	
X2511630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	363,000	363,000	
X2800300	TEMPORARY DITCH CHECKS (SPECIAL)	EACH	750	750	
X5041800	CONCRETE ANCHORS	EACH	2	2	
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	416	416	
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	98	98	
X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	198	198	
X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	197	197	
X5538400	STORM SEWERS TO BE CLEANED 30"	FOOT	27	27	
X6025620	CATCH BASINS, TYPE A, 5'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	2	
X7330088	METAL TRUSS REMOVAL	L SUM	1	1	
Z0001202	CONCRETE BLOCK REMOVAL	CU YD	194	194	
X5539536	STORM SEWER TO BE CLEANED EQUIVALENT ROUND-SIZE 36"	FOOT	190	190	
X5539542	STORM SEWER TO BE CLEANED EQUIVALENT ROUND-SIZE 42"	FOOT	88	88	

• SPECIALTY ITEM

FILE NAME = ...\\D160F78-shr-summary-02.dgn	USER NAME = otb	DESIGNED - DTE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - DTE	REVISED -		SCALE: N.T.S.	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	18A-1	McHENRY	115	4	
		CHECKED - GAB	REVISED -		CONTRACT NO. 60F78								
		DATE - 1/20/2012	REVISED -		ILLINOIS FED. AID PROJECT								