

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0005	RTE 1 OVER IC RR (ABANDONED) SN 016-2859 0014
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	344	344	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94	-
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2490	2490	-
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	109	109	-
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	17	17	-
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	-
78300100	PAVEMENT MARKING REMOVAL	SQ FT	492	492	-
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	126	126	-
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	95	-	95
X5539700	STORM SEWERS TO BE CLEANED	FOOT	96	96	-
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	-
Z0004552	APPROACH SLAB REMOVAL	SQ YD	373	373	-
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	38	-	38
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	8	8	-
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	-
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1	-
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	-
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	172	-	172
Z0076600	TRAINEES	HOOR			
* B1100605	CONDUIT ATTACHED TO STRUCTURE, 2" PVC COATED GALVANIZED STEEL	FOOT	54	54	
* B1304100	JUNCTION BOX EMBEDDED IN STRUCTURE 12" X 12" X 6"	EACH	2	2	
* B5000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2	
* B7100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM 12F 3M 12F	FOOT	3500	3500	
* B7900200	DRILL EXISTING HANDHOLE	EACH	4	4	
* B9502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2050	2050	
* B9502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1450	1450	
* X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1	1	
* X0326133	TEMPORARY WOOD POLE, 45 FEET, CLASS 5	EACH	4	4	
* X0326364	TEMPORARY AERIAL CABLE WITH MESSENGER WIRE	FOOT	650	650	
* B1028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	511	511	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	750	750	
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	▲
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5	

* SPECIALTY ITEM

▲ Rev. 2-24-12

FILE NAME = P:\2007\ME07080_Ver\Ver_Phil\Cadd\W030_IL_R1\Shvs\03-04-D160P38-sht-500.dgn
 USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.8110 voice, 630.839.2566 fax
 www.mps-il.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	CJD	REVISED	-
DRAWN	CJD	REVISED	-
CHECKED	TVN	REVISED	-
DATE	12/14/2011	REVISED	-

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 1 (HALSTED ST)
 OVER IC RR (ABANDONED) (SN 016-2859)**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	2011-032-BR	COOK	41	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P38	

P:\2007\ME07080_Ver\Ver_Phil\Cadd\W030_IL_R1\Shvs\03-04-D160P38-sht-500.dgn