

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, AND COMMITMENTS
- 3-4 SUMMARY OF QUANTITIES
- 5 TYPICAL SECTIONS
- 6 ALIGNMENT, TIES AND BENCHMARKS
- 7 REMOVAL PLANS
- 8 PLAN AND PROFILE SHEETS
- 9-10 SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL
- 10A, 10B. **TEMPORARY INTERCONNECT PLANS**
- 11 PAVEMENT MARKING PLAN
- 12-29 STRUCTURAL SHEETS (NO. 016-2859)
- 30-32 EXISTING STRUCTURE PLAN (1968) FOR INFORMATION ONLY
- 33 DRIVEWAY DETAILS - DISTANCE BETWEEN R.O.W. AND FACE OF CURB LESS THAN 15' (4.5 m) (BD02)
- 34 FRAMES AND LIDS ADJUSTMENT WITH MILLING; AND FRAMES AND LIDS ADJUSTMENT WITHOUT MILLING (BD08)
- 35 PAVEMENT PATCHING FOR HMA SURFACE PAVEMENT (BD22)
- 36 BUTT JOINTS AND HMA TAPER (BD32)
- 37 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC10)
- 38 RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT) (TC11)
- 39 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC13)
- 40 PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING (TC16)
- 41 ARTERIAL ROAD INFORMATION SIGN (TC22)

**LIST OF ILLINOIS DOT HIGHWAY STANDARDS**

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 280001-05 TEMPORARY EROSION CONTROL SYSTEMS
- 420401-08 BRIDGE APPROACH PAVEMENT CONNECTOR
- 424001-05 CURB RAMPS FOR SIDEWALKS
- 606001-04 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 630001-09 STEEL PLATE BEAM GUARDRAIL
- 630301-05 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
- 631011-07 TRAFFIC BARRIER TERMINAL, TYPE 2
- 631026-05 TRAFFIC BARRIER TERMINAL, TYPE 5
- 631031-09 TRAFFIC BARRIER TERMINAL, TYPE 6
- 635006-03 REFLECTOR AND TERMINAL MARKER PLACEMENT
- 635011-02 REFLECTOR MARKER AND MOUNTING DETAILS
- 701602-05 URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
- 701501-06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701606-07 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
- 701701-07 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701801-04 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901 TRAFFIC CONTROL DEVICES
- 704001-06 TEMPORARY CONCRETE BARRIER

**GENERAL NOTES**

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. 48 HOUR NOTIFICATION IS REQUIRED.
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE UTILITY COMPANIES, AND THE VILLAGE OF HOMEWOOD.
3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
4. ANY PAVEMENT MARKINGS AND RAISED REFLECTIVE PAVEMENT MARKERS OBLITERATED BY MILLING AND RESURFACING OPERATIONS ON SIDE STREETS AND ENTRANCES SHALL BE REPLACED AND PAID FOR IN KIND.
5. ALL DAMAGE TO EXISTING PAVEMENT MARKING OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE. NO ADDITIONAL COST TO THE DEPARTMENT.
6. BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCES, ALL EXISTING PAVEMENT MARKING LINES AND RAISED REFLECTIVE PAVEMENT MARKERS IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL STRIPING SHALL BE AS DIRECTED BY THE ENGINEER.
7. DRAINAGE ADJUSTMENT OR RECONSTRUCTION LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
9. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
10. THE RESIDENT ENGINEER SHALL CONTACT PATRICE HARRIS, AREA TRAFFIC FIELD ENGINEER AT (708) 597-9800 A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
11. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
12. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
13. DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN ON THE PLANS.
14. FRAMES AND GRATES ADJUSTMENT OF PRIVATE UTILITIES WITHIN THE LIMITS OF THE IMPROVEMENTS SHALL BE DONE BY THEIR RESPECTIVE OWNERS AND ARE NOT PART OF THIS CONTRACT.
15. WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES WHERE THE SPEED LIMIT IS 45 MPH OR LESS AND 1 INCH WHERE THE SPEED LIMIT IS GREATER THAN 45 MPH. WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H).
16. BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HOT-MIX ASPHALT TAPER DETAILS" SHEET INCLUDED IN THE PLANS UNLESS OTHERWISE SPECIFIED.
17. PAVEMENT MARKING TAPE, TYPE III SHALL BE USED FOR SHORT TERM PAVEMENT MARKINGS ON ALL FINAL SURFACES. THE COST OF THE PAVEMENT MARKING TAPE, TYPE III AND IT'S REMOVAL SHALL BE INCLUDED IN THE COST OF SHORT TERM PAVEMENT MARKING.
18. THE CONTRACTOR SHALL PLACE PROPOSED PAVEMENT MARKINGS IN ACCORDANCE WITH DISTRICT 1 TYPICAL PAVEMENT MARKINGS DETAIL (TC-13).
19. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL LOGS, SHRUBS, BUSHES, SAPLINGS, UNDERBRUSH OR DEBRIS ACCORDING TO SECTION 201 OF THE STANDARD SPECIFICATIONS AT LOCATIONS REQUIRING ACCESS TO THE SUBSTRUCTURE. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT THE COST SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

**COMMITMENTS**

NO COMMITMENTS FOR THIS PROJECT

20. THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY THE DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTIONS.

FILE NAME : P:\2007\ME07080\_Ver-Var-Ph1\Cadd\W030\_IL\_R1\Shets\02-0160P38-akt-gemnote.dgn  
 USER : NONE  
 MILLENNIA PROFESSIONAL SERVICES



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.765.8110 voice, 630.839.2566 fax  
 www.mps-il.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED -	CJD	REVISED -	
DRAWN -	CJD	REVISED -	
CHECKED -	TVN	REVISED -	
DATE -	12/9/2011	REVISED -	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 1 (HALSTED ST)**  
**OVER IC RR (ABANDONED) (SN 016-2859)**

**INDEX OF SHEETS, LIST OF IDOT**  
**HIGHWAY STANDARD, GENERAL NOTES,**  
**AND COMMITMENTS**

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	2011-032-BR	COOK	41	2
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P38	

P:\2007\ME07080\_Ver-Var-Ph1\Cadd\W030\_IL\_R1\Shets\02-0160P38-akt-gemnote.dgn

**SUMMARY OF QUANTITIES**


**CONSTRUCTION TYPE CODE**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0005	RTE 1 OVER IC RR (ABANDONED) SN 016-2859 0014
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	344	344	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94	-
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2490	2490	-
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	109	109	-
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	17	17	-
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	-
78300100	PAVEMENT MARKING REMOVAL	SQ FT	492	492	-
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	126	126	-
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	95	-	95
X5539700	STORM SEWERS TO BE CLEANED	FOOT	96	96	-
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	-
Z0004552	APPROACH SLAB REMOVAL	SQ YD	373	373	-
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	38	-	38
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	8	8	-
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	-
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1	-
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	-
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	172	-	172
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOOR</del>			
* B1100605	CONDUIT ATTACHED TO STRUCTURE, 2" PVC COATED GALVANIZED STEEL	FOOT	54	54	
* B1304100	JUNCTION BOX EMBEDDED IN STRUCTURE 12" X 12" X 6"	EACH	2	2	
* B5000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2	
* B7100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM 12F 3M 12F	FOOT	3500	3500	
* B7900200	DRILL EXISTING HANDHOLE	EACH	4	4	
* B9502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2050	2050	
* B9502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1450	1450	
* X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1	1	
* X0326133	TEMPORARY WOOD POLE, 45 FEET, CLASS 5	EACH	4	4	
* X0326364	TEMPORARY AERIAL CABLE WITH MESSENGER WIRE	FOOT	650	650	
* B1028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	511	511	
* W6900200	NON-SPECIAL WASTE DISPOSAL	CU YD	750	750	
* W6900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	▲
* W6900530	SOIL DISPOSAL ANALYSIS	EACH	5	5	

\* SPECIALTY ITEM

▲ Rev. 2-24-12

FILE NAME = P:\2007\ME07080\_Ver\Ver\_Phil\Cadd\W030\_IL\_R1\Shvs\03-04-D160P38-sht-500.dgn  
 USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.8110 voice, 630.839.2566 fax  
 www.mps-il.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 12/14/2011	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 1 (HALSTED ST)  
 OVER IC RR (ABANDONED) (SN 016-2859)**

**SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE. 876	SECTION 2011-032-BR	COUNTY COOK	TOTAL SHEETS 41	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P38	