

**SUMMARY OF QUANTITIES**

**CONSTRUCTION TYPE CODE**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	RTE 1 OVER IC RR (ABANDONED) SN 016-2859		
				0005	0014		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	344	344			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94	-		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2490	2490	-		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	109	109	-		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	17	17	-		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	-		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	492	492	-		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	126	126	-		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	95	-	95		
X5539700	STORM SEWERS TO BE CLEANED	FOOT	96	96	-		
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	-		
Z0004552	APPROACH SLAB REMOVAL	SQ YD	373	373	-		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	38	-	38		
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	8	8	-		
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	-		
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1	-		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	-		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	172	-	172		
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOUR</del>					
* <del>B1100605</del>	<del>CONDUIT ATTACHED TO STRUCTURE, 2" PVC COATED GALVANIZED STEEL</del>	<del>FOOT</del>	<del>54</del>	<del>54</del>			
* <del>B1304100</del>	<del>JUNCTION BOX EMBEDDED IN STRUCTURE 12" X 12" X 6"</del>	<del>EACH</del>	<del>2</del>	<del>2</del>			
* <del>B5000200</del>	<del>MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION</del>	<del>EACH</del>	<del>2</del>	<del>2</del>			
* <del>B7100020</del>	<del>FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM 12F 5M12F</del>	<del>FOOT</del>	<del>3500</del>	<del>3500</del>			
* <del>B7900200</del>	<del>DRILL EXISTING HANDHOLE</del>	<del>EACH</del>	<del>4</del>	<del>4</del>			
* <del>B9502300</del>	<del>REMOVE ELECTRIC CABLE FROM CONDUIT</del>	<del>FOOT</del>	<del>2050</del>	<del>2050</del>			
* <del>B9502350</del>	<del>REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT</del>	<del>FOOT</del>	<del>1450</del>	<del>1450</del>			
* <del>X0325938</del>	<del>TEMPORARY WIRELESS INTERCONNECT, COMPLETE</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>			
* <del>X0326133</del>	<del>TEMPORARY WOOD POLE, 45 FEET, CLASS 5</del>	<del>EACH</del>	<del>4</del>	<del>4</del>			
* <del>X0326364</del>	<del>TEMPORARY AERIAL CABLE WITH MESSENGER WIRE</del>	<del>FOOT</del>	<del>650</del>	<del>650</del>			
* <del>B1028200</del>	<del>UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.</del>	<del>FOOT</del>	<del>511</del>	<del>511</del>			

\* SPECIALTY ITEM

FILE NAME = P:\2007\ME07080\_Ver-Vor-Phil\Cadd\W030\_IL\_R1\Shvs\03-04-D160P38-sht-500.dgn  
 USER = Phil  
 MILLENNIA PROFESSIONAL SERVICES



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.705.0110 voice, 630.839.2566 fax  
 www.mps-il.com

**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED	CJD	REVISED	-
DRAWN	CJD	REVISED	-
CHECKED	TVN	REVISED	-
DATE	12/14/2011	REVISED	-

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 1 (HALSTED ST)  
 OVER IC RR (ABANDONED) (SN 016-2859)**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	2011-032-BR	COOK	41	4
CONTRACT NO.			60P38	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.