

SUMMARY OF QUANTITIES

URBAN

901.FED./10/STATE

901/67/133/

Fed./State/City

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY	0021 SIGNAL AT THORNTON RD	0021 SIGNAL AT 138th ST	0021 SIGNAL AT BROADWAY ST
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	395	395			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	66	66			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	259	259			
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	633	633			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	37	37			
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	632	632			
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	260	260			
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	4	4			
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	39	39			
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1			
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	2			
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	15	15			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	28	28			
60500040	REMOVING MANHOLES	EACH	7	7			
60500050	REMOVING CATCH BASINS	EACH	17	17			
60500060	REMOVING INLETS	EACH	13	13			
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	26	26			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1586	1586			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1247	1247			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	227	227			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	775	775			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	5	5			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	14	14			
63200310	GUARDRAIL REMOVAL	FOOT	199	199			
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	1,451	1,451			
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	267	267			
63700900	CONCRETE BARRIER BASE	FOOT	1,781	1,781			
64300240	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	5	5			
64300350	IMPACT ATTENUATORS (FULLY REDIRECTIVE, WIDE), TEST LEVEL 2	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1			
70106700	TEMPORARY RUMBLE STRIPS	EACH	9	9			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,397	2,397			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	180	180			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30,846	30,846			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	657	657			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	133	133			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	248	248			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	189	189			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12,755	12,755			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,208	2,208			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,976	1,976			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	362	280	35	6	35

* DENOTES SPECIALTY ITEM

FILE NAME =
#FILE#

USER NAME = .USER.
PLOT SCALE = 50' / IN.
PLOT DATE = 12/28/2011

DESIGNED - EF
DRAWN - EF
CHECKED - RS
DATE - 12-28-2011

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INLAND AVE. (THORNTON RD. - BROADWAY ST.)
SUMMARY OF QUANTITIES

SCALE: 1"=50'

SHEET 2 OF 4 SHEETS STA. TO STA.

F.A.U. RTE. 2857	SECTION 2011-054-I	COUNTY COOK	TOTAL SHEETS 81	SHEET NO. 4
CONTRACT NO. 60P64			ILLINOIS FED. AID PROJECT	